

Copy 3
1968/59
(3)

COMMONWEALTH OF AUSTRALIA

DEPARTMENT OF NATIONAL DEVELOPMENT

BUREAU OF MINERAL RESOURCES, GEOLOGY AND GEOPHYSICS

Record No. 1968 / 59

019118

Geological Investigation of
The Lower Warangoi
Hydro-Electric Scheme,

New Britain, Territory of Papua and New Guinea
1964 - 1965

FINAL REPORT



by

J.R.L. Read

The information contained in this report has been obtained by the Department of National Development as part of the policy of the Commonwealth Government to assist in the exploration and development of mineral resources. It may not be published in any form or used in a company prospectus or statement without the permission in writing of the Director, Bureau of Mineral Resources, Geology and Geophysics.

GEOLOGICAL INVESTIGATION OF THE LOWER WARANGOI HYDRO-ELECTRIC SCHEME,

NEW BRITAIN, TERRITORY OF PAPUA AND NEW GUINEA

1964-1966 : Final Report

by

J.R.L. Read

Records 1968/59

The information contained in this report has been obtained by the Department of National Development, as part of the policy of the Commonwealth Government, to assist in the exploration and development of mineral resources. It may not be published in any form or used in a company prospectus without the permission in writing of the Director, Bureau of Mineral Resources, Geology and Geophysics.

CONTENTS

	<u>Page</u>
SUMMARY	
INTRODUCTION	2
General	2
Outline of Scheme	2
Topography	2
Location and Access	3
Mapping	3
Diamond Drilling	4
Water Pressure Testing	4
Geophysical Survey	4
Soils Investigation	5
GEOLOGY	5
REGIONAL	5
DAMSITE	6
ABUTMENTS	6
Stratigraphy	6
Structure	6
RIVER CHANNEL	7
STORAGE AREA	7
SOUTHERN RIDGE	7
Stratigraphy	7
Structure	9
MAIN RESERVOIR	9
ENGINEERING GEOLOGY	9
DAMSITE	9
ABUTMENTS	9
RIVER CHANNEL	10
STORAGE AREA	11
SOUTHERN RIDGE	11
MAIN RESERVOIR	12
SEISMICITY	13
SILTATION	13
CONCLUSIONS	14
RECOMMENDATIONS	15
REFERENCES	16

CONTENTS

Page

APPENDICES

- 1 Definitions of semi-quantitative descriptive terms
- 2 Geological Logs of diamond drill holes
- 3 Water pressure test computation sheets

TEXT FIGURES

1. Summary logs of diamond drill holes WD1 & WD2
2. Summary logs of diamond drill holes WD3 & WD9
3. Summary logs of diamond drill holes WD8A, WD8 & WD4A
4. Summary logs of diamond drill holes WD10, WD6 & WD5

PLATES

1. Locality plan. Scale, 1 inch : 8 miles.
2. Geological map of damsite. Scale, 1 inch : 80 feet.
3. Vertical geological section along axis of proposed dam.
Scale, 1 inch : 80 feet.
4. Geology of southern ridge with diagrammatic section.
Scale, 1 inch : 400 feet.

SUMMARY

The Lower Warangoi Hydro-Electric Scheme was proposed to supply the future electricity requirements of Rabaul and eventually of the whole Gazelle Peninsula. The site of the proposed dam is at a narrow constriction of the Lower Warangoi River through a major ridge which to the south forms a narrow divide between the Warangoi and Sigule River systems. It is located 32 miles by road from Rabaul and about 13 river miles from the mouth of the Warangoi River. To provide sufficient head and storage for a power station capable of generating 10 megawatts it would need to be 120 feet high.

Preliminary geological investigation, followed by a programme of diamond drilling, geophysical investigation, and soils mechanics testing was carried out between 1964 and 1966.

The damsite consists of volcanic agglomerate overlain by lesser deposits of reef-coral limestone. The river channel at the damsite is filled with river alluvium to a depth of 150 feet.

Agglomerate forms both abutments of the damsite. In the right abutment agglomerate extends for about 2600 feet from the river; it is overlain on the downstream side by fine-grained sediments and coralline limestone, and is replaced laterally in the remainder of the ridge, to the south-west, by fine-grained sediments which are interbedded with coarser-grained deposits of sandstone and conglomerate. The remainder of the storage area consists of fine-grained sediments, minor coralline limestone, and superficial deposits of pumice.

A 120-foot high dam would be entirely founded on agglomerate and river alluvium: agglomerate extends for a depth greater than that penetrated by diamond drilling beneath the damsite. It is predominantly moderately to highly weathered, correspondingly weak, and moderately to highly permeable. Alluvium in the river channel consists of interbedded sand and gravel.

The fine-grained sediments in the ridge forming the divide between the Warangoi and Sigule drainages are soft to slightly indurated and, in the terms of the Unified Soils Classification, belong to soil types CH and SC-CL. The sandstone and conglomerate occur together in three layers within the ridge, the lowest of which extends along the base of the ridge immediately below the proposed top storage level. The sandstone is loosely compacted and is of soil type SP-SM: the conglomerate is a densely packed gravel and is of soil type GP-GW. Both deposits are highly permeable.

The proposed scheme is located in one of the most seismically active regions of Papua and New Guinea, and all structures would have to be capable of withstanding high ground accelerations. The tributary rivers carry a high bed load at times of high flow and the rate of siltation of the reservoir is expected to be high. Any disruption of the land surface by a major earthquake would increase the rate of siltation.

It is concluded that because of the combination of the weathered condition and permeability of the agglomerate, the configuration of the river channel, the presence of highly permeable deposits in the divide between the Warangoi and Sigule drainages, the high seismicity of the region, and the likely high rate of siltation of the reservoir, it is extremely doubtful whether the scheme is geologically and economically sound.

It is recommended that further investigation be discontinued and that a full analysis and comparison of costs of all alternative schemes be carried out. Design investigation could only be justified if it were proved beyond all reasonable doubt that the Lower Warangoi hydro-electric scheme was the most economic project for providing electricity for Rabaul and, eventually, the whole Gazelle Peninsula.

INTRODUCTION

General

Following a decision to discard for geological reasons a previously investigated site on the Towanokoko - Pondo River systems (Fisher, 1959; Carter, 1962; and Best, 1963), the Lower Warangoi hydro-electric scheme was proposed to fulfil the future electricity requirements of Rabaul in the Gazelle Peninsula of New Britain, Territory of New Guinea (Plate 1).

An initial inspection of two possible damsites on the Lower Warangoi River was carried out in March, 1964. During the inspection it was found that only one site was possibly suitable for a hydro-electric scheme and a recommendation was made for a preliminary geological investigation of the site (Carter & MacGregor, 1964). This survey was carried out between August and October, 1964. During the course of the survey the proposed damsite and reservoir area were geologically mapped and a programme of diamond drilling, geophysical and soils testing recommended (Read, 1965).

Diamond drilling commenced in June, 1965 and, after the geophysical and soils mechanics surveys had been undertaken between July and October, 1966 the recommended investigation was completed in October, 1966.

Outline of Scheme

The proposed hydro-electric scheme would involve the construction of a 120-foot high dam to provide the necessary storage and head to develop 10 megawatts at a 50% annual load factor.

The power generated would supply Rabaul and would eventually include a transmission link for the whole Gazelle Peninsula (Papua and New Guinea Electricity Commission, 1966).

Topography

The site for the proposed damsite is at a narrow constriction of the Lower Warangoi River through a major ridge extending for several miles to the south-west from high ground on the left bank of the river to form a divide between the Warangoi and Sigule River systems (Plate 1). The configuration of the ridge is given in greater detail in Read (1965).

The high ground on the left bank of the river, which is predominantly flat-lying, extends for several miles north of the damsite and supports an intensive cocoa and coconut growing industry. South and south-west of the damsite the countryside is dissected into a complex system of ridges and valleys. It is predominantly covered by natural bush and is sparsely populated.

Between the damsite and the confluence of the Upper Warangoi and Kavavas Rivers the Warangoi Valley is particularly wide and flat. Upstream of the confluence the reservoir area is split into two parts which follow the main river channels for a distance of about five miles towards the headwaters of the catchment area.

Location and access

The proposed scheme is 32 miles by road from Rabaul (Plate 1). The nearest township, Kokopo, is 13 miles by road from the damsite, the last five miles of which are along private plantation roads maintained during the investigation by the Commonwealth Department of Works, Rabaul.

The damsite is situated about 13 river miles, or about eight air miles, from the mouth of the Warangoi River, and approximately $2\frac{1}{2}$ river miles downstream of the confluence of the tributary Upper Warangoi and Kavavas Rivers.

Public roads are open to light and heavy traffic at all times but plantation roads are accessible to light vehicles only during the wet season.

Mapping

Geological mapping of the main reservoir area was carried out during traverses down the Kavavas and Upper and Lower Warangoi Rivers using a base map drawn from aerial photographs of an approximate scale of one inch to 4000 feet.

Geological mapping of outcrop in the area of the ridge forming the divide between the Sigule and Warangoi River systems (the southern ridge) was carried out by tape, compass and abney level traverses. All traverses were subsequently tied to a surveyed line along the crest of the southern ridge and were re-surveyed by the Commonwealth Department of Works.

Detailed geological mapping of the left and right abutments was undertaken by plane table and tacheometric survey. Horizontal and vertical control was provided by a damsite survey grid pegged at 50-foot intervals by the Commonwealth Department of Works.

Diamond Drilling

The diamond drilling programme was carried out by drillers from the Commonwealth Department of Works using two E1000 and one F15C Mindrill rigs. All holes were drilled with either an NMLC or BMLC triple core barrel with a stationary, split, inner tube.

In all, 10 holes totalling 2186 feet were drilled: two, WD1 and WD2 on the left abutment; two, WD3 and WD9 on the right abutment; three, WD8, WD8A and WD4A in the foundations; and three, WD5, WD6 and WD10 along the southern ridge.

WD8 became jammed in river gravels and was abandoned in favour of WD8A which was drilled from the same location but at a steeper angle.

Owing to a lack of funds in the final stages of the investigation drillholes WD10 and WD5 were stopped before their specified depths were reached and a proposed hole on the southern ridge, WD7, was not proceeded with.

Geological logs of core from the drill holes are contained in Appendix 2.

Water Pressure Testing

Water pressure testing, generally at 20-foot intervals, was undertaken in all drill holes except WD4A and WD5. Testing was carried out using a Coventry Climax fire-pump, AX casing, and either NX or BX hydraulic and mechanical packers. Difficulties were experienced in obtaining a good seal using hydraulic packers and, whenever possible, mechanical packers were used.

Gauge pressures were corrected for hydrostatic head and friction losses in the supply line and packer. Packer losses were calculated from graphs determined from packer calibrations carried out at the site. The corrected results were used to determine the permeability, in feet per year, of each test section. The formula used to calculate permeability is one derived by the Snowy Mountains Hydro-electric Authority. In deriving the formula it was assumed that the rock in any test section has uniform permeability. This condition does not hold in fractured rocks, therefore the values obtained are useful only for comparison between test sections and as a gross indication of the transmissability of the rock tested.

Geophysical Survey

A geophysical survey was carried out by a team from the Geophysical Branch of the Bureau of Mineral Resources during July, September and October, 1966.

Ten seismic refraction profiles totalling about 15,200 feet were carried out across and along the crest of the southern ridge, in the damsite area, and north of the left abutment, and two magnetic ~~intensity traverses~~ were undertaken along the seismic profiles north of the left abutment.

In addition, 11 representative samples of agglomerate core from drill holes in the abutments were subjected to density, and sonic velocity measurements in the laboratory.

A report on the survey and testing is contained in a separate Bureau of Mineral Resources Record (Cifali, Milsom & Polak, in preparation).

Soils Investigation

Soil sampling and field permeability testing of sediments from the southern ridge was carried out by the Commonwealth Department of Works Central Testing and Research Laboratory during September and October, 1966.

The soil samples, which were classified and laboratory-tested for permeability and saturated shear strength, were taken from exposures on several traverses across the ridge, and from a costean and shaft excavated on the reservoir side of the ridge north of survey peg 8Δ (Plate 4).

A report on the investigation is contained in a Technical Report of the Central Testing and Research Laboratory (Blythe, 1967).

GEOLOGY

REGIONAL

The Gazelle Peninsula forms a prominent extension, of generally low to moderate relief, to the north-eastern end of the Island of New Britain. It consists of the Recent and Pleistocene volcanic complex of Blanche Bay (Fisher, 1939) overlying Tertiary sediments and volcanics which, in the west, abut unconformably against igneous and metamorphic rocks forming the central spine of the Island.

The oldest rocks exposed in the Warangoi area are basic volcanic agglomerate of probable Lower Tertiary age; at the damsite the agglomerate is overlain by Upper Miocene coralline limestone. The remainder of the stratigraphic sequence consists of claystone, siltstone, sandstone and conglomerate. A sample taken from these sediments near the base of the southern ridge was determined as Pliocene (Read, 1965).

All the sediments are flat-lying to gently dipping east or west. A regional fault pattern can be detected on aerial photographs of the Peninsula but no major fault lines were recognised on the ground.

DAMSITE

ABUTMENTS

Stratigraphy

Rock in the abutments is principally of two types: volcanic agglomerate; and coralline limestone.

Coralline limestone is draped unconformably in the form of a reef over the crest and on the downstream slopes of the left abutment, and also on the downstream flank of the right abutment (Plate 2). In addition, a thin lens of limestone was encountered at R.L. 60 feet in drill hole WD1 (Plate 3). The limestone is a pale buff, moderately hard rock containing many small ($\frac{1}{2}$ - 2 inch), cavities which are commonly infilled with calcareous debris.

Volcanic agglomerate forms the main bulk of the abutments, extending below river level deeper than was penetrated by diamond drilling (Plate 3). It is slightly to highly weathered and consists of medium to coarse-grained fragments of augite basalt and andesite set in a fine to medium-grained tuffaceous matrix.

Dykes and sills of augite basalt occur within the agglomerate and several beds of medium-grained tuffaceous sandstone were mapped within the agglomerate at the surface (Plate 2). The relationship to the rest of the sequence of the limestone encountered within the agglomerate in drill hole WD1 is not clear. In the absence of evidence of faulting the limestone is regarded as probably a continuation of the east-dipping bed of tuffaceous sandstone exposed at river level on the upstream face of the left abutment.

Structure

All the coralline limestone, and the tuffaceous beds within the agglomerate, dip between 10° and 35° to the east (Plate 2).

No regular jointing system is apparent at the surface or at depth in either the coral or the agglomerate. Joints are widely spaced and irregularly distributed, generally open, and coated with a thin layer of clay, calcite or chlorite, zeolites, or other secondary minerals.

Three faults, F1, F2 and F3 intersect the left abutment (Plate 2). F1 and F2 are normal faults offsetting the same sequence of tuffaceous sandstone, basalt flow and agglomerate in the upstream face of the abutment. Fault F1 has a displacement of 20 feet, strikes 056° (magnetic) and dips 85° north-west: fault F2 has a displacement of at least six feet, strikes 100° (magnetic) and dips 70° north. No trace of fault F2 was found in drill hole WD1.

Fault F3, on the downstream side of the abutment, strikes 065° (magnetic). It is considered to be a normal fault upthrown to the south-east, as coral overlying agglomerate on the western side of the fault does not occur to the east. A possible extension of the fault into the right abutment, suspected from surface mapping (Read, 1965), was not proven by diamond drilling.

RIVER CHANNEL

The minimum width of the river channel between the abutments is 300 feet. The river is only two or three feet deep at this point during periods of low flow although it is up to 15 feet deep in places nearby.

Diamond drilling and geophysical investigation have demonstrated that the river channel at the damsite is almost oblong in section and is filled with river gravels and sand to a depth of 150 feet (Plate 3).

Because of this unexpected configuration, drill holes specified to determine rock conditions beneath the channel could not be completed. However, agglomerate occurs throughout WD8A, which extends 60 feet beneath the base of the channel (Plate 3), and it appears that this rock type extends for some considerable depth beneath the damsite.

The possibility of faulting between the abutments was not proved. However, the exceptional depth of the river channel revealed indicates some form of structural control and the possibility of faulting cannot be ruled out.

STORAGE AREA

SOUTHERN RIDGE

Stratigraphy

The southern ridge extends to the south and south-west from the right abutment to form a divide between the Warangoi and Sigule River systems. The ridge is narrow, although for most of its length it stands more than 250 feet above river level at the damsite. Numerous creeks have been incised into the flanks of the ridge and in several places headward erosion by creeks has led to the formation of low-lying saddles in the crest of the ridge.

Over a crest length of about 2600 feet the ridge is composed of volcanic agglomerate flanked on the downstream side by a sequence of fine-grained sediments and coralline limestone: these sediments also occur on the upstream side of the ridge west of $\Omega 18$ (Plate 4).

Beyond 2600 feet the agglomerate and coralline limestone are replaced laterally by a sequence consisting entirely of fine-grained sediments, sandstone and conglomerate (Plate 4). The stratigraphic succession in this part of the ridge is broadly summarised below:-

<u>Bed</u>	<u>Thickness (feet)</u>
Silty and sandy claystone. CL* (?)	100
Sandstone and conglomerate. SP-SM, GP-GW	10 - 22
Blue mudstone. CH.	10 - 55
Sandstone and conglomerate. SP-SM, GP-GW.	8 - 50
Blue mudstone. CH.	28 - 60
Shell bed.	4 - 8
Blue mudstone. CH.	60
Sandstone and conglomerate. SP-SM, GP-GW	55
Blue mudstone. CH.	Unknown.

* Unified Soils Classification

The uppermost bed of silty and sandy claystone, visually classified as CL, extends along the length of the ridge except in the low-lying saddle areas between $\Delta 1$ and $\Delta 3$ and $\Delta 6$ to $\Delta 9$. It is underlain by three beds of sandstone and conglomerate each of which is separated by a bed of blue mudstone. A thin bed of grey, silty claystone containing an abundant Pliocene fauna (Read, 1965) is located within the blue mudstone between the middle and lower sandstone and conglomerate bed.

The sandstone consists of loosely compacted, uncemented, medium-grained sand which generally forms a layer about 10 feet thick above the conglomerate but in places occurs as thin layers within the upper 15 feet of the conglomerate. The sediment is poorly graded, contains minor amounts of silt and has been classified as SP-SM (Blythe, 1967). The conglomerate, classified as GP-GW (Blythe, 1967), consists of densely packed gravels containing variable quantities of fines, mostly clay.

The blue mudstone, which ranges in colour from blue where fresh to brown where weathered, has been classified as CH (Blythe, 1967). It is soft to slightly indurated and contains numerous bands of silty sand and silty clay (SC-CL, Blythe, 1967) especially near the upper and lower limits of the sandstone and conglomerate beds.

The thickness and vertical levels of the sandstone and conglomerate beds vary throughout the length of the ridge. The base of the upper bed rises from R.L. 275 feet at $\Delta 37$ to R.L. 350 feet at $\Delta 34$, from where it lenses out towards the agglomerate section of the ridge. The base of the middle bed increases considerably in thickness towards the east: at $\Delta 37$ the top of the deposit is located immediately below the shell bed at R.L. 204 feet but in the shaft has fallen to R.L. 170 feet. The extent of this lowermost sandstone and conglomerate bed east of the shaft is unknown but it probably continues at least to the agglomerate section of the ridge.

Structure

The sediments and the coralline limestone in the ridge are predominantly massive and poorly jointed. Bedding is essentially flat-lying with local variations east and west. Fore-set bedding and micro-bedding occur in the fine-grained sediments, and cross-bedding and graded-bedding occur in the sandstone.

Three minor faults were mapped in the ridge (Read, 1965). Two are in the agglomerate, strike east across the ridge and have vertical fault planes. The third is in the sediments north of $\Omega 33$; it strikes east, has a vertical fault plane and shows a maximum displacement of two feet.

MAIN RESERVOIR

The reservoir area is underlain almost entirely by a succession of flat-lying, soft to moderately indurated silty claystone, fine-grained sandstone and rare conglomerate.

Isolated outcrops of coralline limestone occur on the left bank of the river immediately upstream of the damsite. Coral was also located by geophysical methods north of the left abutment but the extent of the deposits was not determined (Cifali et al., in preparation).

Minor deposits of pumice occur as surface coverings over the sediments, and extensive banks of river gravel and sand up to 100 feet thick occur along the margins of the Kavavas River.

ENGINEERING GEOLOGY

DAMSITE

ABUTMENTS

The abutments of a storage dam with a crest height of 120 feet would be founded entirely in agglomerate (Plate 2), and the coralline limestone is therefore disregarded in consideration of the geological suitability of the abutments.

After surface mapping had been carried out in the preliminary geological investigation it was considered (Read, 1965) that the agglomerate would probably be fresh, hard and strong at depth. This has been proved incorrect, however, as diamond drilling located little fresh agglomerate in the abutments.

In drill holes WD1, WD2, WD3 and WD9 only 9% of the core recovered was fresh to slightly weathered; 47% was slightly to moderately weathered and 23% moderately to highly weathered. The degree of weathering is reflected in the tuffaceous matrix of the rock. Fresh agglomerate has a satisfactory bond between the matrix and the volcanic rock fragments making up the rest of the rock. As the degree of weathering increases the matrix becomes progressively pitted and friable, losing cohesion and strength so that a moderately weathered core sample can be broken across the rock fabric by hand. The approximate value of the overall compressive strength of the agglomerate in the abutments, determined from sonic wave velocities, was 5000 p.s.i. (Cifali et al., in preparation).

The fracture density per 10-foot of core obtained from the abutments is shown on histograms in Figures 1 and 2. It is considered that a large proportion of the fractures, which are numerous, was caused by breaking of weak rock during drilling, rather than by jointing. Generally the joints were widely and irregularly spaced, although nearly all joint faces were stained and coated with clay and secondary minerals indicating that they were open and directly contributing to the moderate to high permeability of the agglomerate.

The results of the water pressure tests carried out in drill holes WD1 WD2, WD3, and WD9 (Appendix III) are summarised in Figures 1 and 2. Permeabilities were lowest in WD1 and WD3 which have respective figures of 230 and 650 feet per year. The average in WD9 is 3100 feet per year and in WD2 5400 feet per year. The average value in WD2 may be slightly high due to two seemingly anomalously high values of 100,000 feet per year in the results.

The overall results of the water pressure testing indicate that water losses through ungrouted abutments would be high. They further indicate that the quantity of grout required to seal the abutments would be extremely high.

The suspected continuations of faults F2 and F3 (Read, 1965) were not proven and no major additional structures which could add to the known weakness of the abutments were discovered, either by diamond drilling or by geophysical investigation.

RIVER CHANNEL

The most unexpected feature discovered at the damsite was the depth of the alluvium-filled river channel between the abutments.

Results of diamond drilling in the area are summarised in Figure 3. Drill hole WD8 broke into the river channel after only 74 feet of drilling in moderately to highly weathered agglomerate. Drill hole WD4A, drilled vertically through the alluvium, penetrated 109 feet of river gravel and sand before jamming and final confirmation of the configuration of the channel was not forthcoming until the completion of the geophysical investigation (Cifali et al., in preparation).

LOWER WARANGOI HYDRO-ELECTRIC SCHEME

Fig. 1

SUMMARY LOGS OF DIAMOND DRILL HOLES WD1 & WD2

WD1 Coordinates : E + 23ft, 353ft NE.


RL : 320ft

Angle : 70°, 178° M.

WD2 : I + 34ft, 317ft NE.

361ft.

90°



- △△△ Agglomerate, Fresh to Slightly Weathered
- Agglomerate, Slightly to Moderately Weathered
- ××× Agglomerate, Moderately to Highly Weathered
- ××× Agglomerate, Highly to Completely Weathered



- △△△ Limestone and Agglomerate
- Limestone
- /// Andesite

LOWER WARANGOI HYDRO-ELECTRIC SCHEME

Fig. 7

SUMMARY LOGS OF DIAMOND DRILL HOLES WD3 & WD9

WD3 Coordinates : J+ 30, 265 ft SW RL : 130 ft Angle : 40°, 125° M
WD9 : O+ 30, 300 ft SW : 270 ft 90°



- △△△ Agglomerate, Fresh to Slightly Weathered
- △△△ Agglomerate, Slightly to Moderately Weathered
- △△△ Agglomerate, Moderately to Highly Weathered

Core recovered from WD8A was slightly to moderately weathered and correspondingly weak: fracturing of the core during drilling was extensive. Water pressure tests showed a moderate to high loss, the average permeability for the hole being 1400 feet per year.

No information was gained as to the possibility of faulting beneath the channel. However, as already mentioned, the configuration of the channel indicates some form of structural control and the possibility of faulting cannot be ruled out.

STORAGE AREA

SOUTHERN RIDGE

The agglomerate, which forms the southern ridge over a crest length of about 2600 feet from the right abutment, is identical with that at the damsite. The rock is of low quality and 82% of the agglomerate retrieved from drill hole WD10 was moderately to highly weathered, soft, friable and weak: core breakage during drilling was high (Figure 4).

The limestone on the downstream flank of the agglomerate is coralline, moderately hard and strong but exhibits numerous small open cavities typical of coral deposits. The possibility that this limestone is connected beneath the surface with identical deposits occurring west of $\Omega 18$ (Read, 1965) was not proven.

Classification and consolidated undrained shear tests of sediments in the southern ridge were carried out by the Commonwealth Department of Works' Central Testing and Research Laboratory, Melbourne.

Samples tested triaxially included three of the four main soil types in the ridge: CH; SC-CL: and SP-SM. The calculated ranges of saturated shear strength were as follows (after Blythe, 1967, Table 4):-

<u>Soil Type</u>	<u>C', p.s.i.</u>	<u>ϕ'</u>
CH	1-6	44-52°
SC-CL	0-1	36-41°
SM-SP	1-2.5	35-40°
GW-GP	Not tested but considered ϕ' would not be less than 45° and the gravel has some cohesion.	

As the sediments tested are typical of all those in the southern ridge these values would be representative for calculations of slope stability factors along the ridge.

Water losses during pressure testing of the agglomerate in the ridge were moderate to high, the average permeability being 1400 feet per year (Figure 4 and Appendix 3). The sediments were water-pressure-tested in drill hole WD6 (Figure 4 and Appendix 3) and field and laboratory permeability tests were carried out on selected samples by the Commonwealth Department of Works Central Testing and Research Laboratory.

Results of the tests on the various soil types were as follows:-

Pressure Testing, Drill Hole WD6

<u>Reduced Level (feet)</u>	<u>Soil Type</u>	<u>Range of Permeability, Feet/Year</u>
216-196	CH	180-2000
196-176	CL	750-2200
176-166	GP-GW & SP-SM	350-1300
166-156	GP-GW	100,000

Permeability Testing (after Blythe, Table 4, 1967)

<u>Sample</u>	<u>Soil Type</u>	<u>Range of Permeability, Feet/Year</u>
11-0-2, 11-0-6	CH	1-10
11-0-7, 11-0-11	SC-CL	1-10
11-0-1, 11-0-12 and 11-0-26	SM-SP	1-10
11-0-9	GW	10-1000
11-0-10	GP	1000-10,000

The discrepancy between the pressure testing and the permeability testing results has not been satisfactorily explained. It is clear, however, that the permeability of the silty and clayey sediments (CH, CL and SC) is considerably lower than that of the sandstone and conglomerate beds (SP-SM and GP-GW) which, although showing variable results, have an extremely high permeability. When pressure testing the GP-GW layer between R.L. 166 feet and R.L. 156 feet in drill hole WD6 a very high rate of flow (74 gallons per minute) occurred, and it was possible only to produce sufficient pressure to counteract pressure losses caused by friction in the supply line and packer. Even if the range of permeabilities calculated by the Central Testing and Research Laboratory for the sandstone and conglomerate beds is accepted as the more reliable, the total volume of water likely to be lost through the lowermost sandstone and conglomerate bed, which is 55 feet thick and extends immediately below top water line (R.L. 220 feet) over a distance of at least 8000 feet around the base of the ridge, is impressive.

MAIN RESERVOIR

The sediments in the remainder of the reservoir are similar to those in the southern ridge and values of saturated shear strength and internal friction calculated from samples from the ridge should be valid for any calculations of slope stability factors.



No other major leakage paths were proven. The distribution of coral limestone north of the left abutment was not clarified by geophysical investigation and the likelihood of leakage in this area remains unknown.

LOWER WARANGOI HYDRO-ELECTRIC SCHEME

Fig. 3

SUMMARY LOGS OF DIAMOND DRILL HOLES WD8A, WD8 & WD4A

WD8A	Coordinates: K+ 23, 134ft NE.	RL: 120ft.	Angle: 70, 252M
WD8	: K+ 25, 134ft NE.	120ft	40, 252M
WD4A	J+ 10, 155ft SW.	110ft	90




-  Agglomerate, Slightly to Moderately Weathered
-  Agglomerate, Moderately to Highly Weathered
-  River Gravel & Sand

LOWER WARANGOI HYDRO-ELECTRIC SCHEME

Fig. 4

SUMMARY LOGS OF DIAMOND DRILL HOLES WD10, WD6 & WD5

WD10	Location	Traverse T4, Peg 15	RL	300ft.	Angle	55°, 295M
WD6		Midway Pegs Δ8 & Δ9		291ft.		90°
WD5		Traverse T16, Peg 5		194ft.		90°



	Claystone and Mudstone		Agglomerate Moderately to Highly Weathered
	Sandy Claystone		Claystone and Sand
	Limestone and Agglomerate		Mudstone, Claystone and Sand
	Limestone		Blue Mudstone
	Agglomerate Fresh to Slightly Weathered		Sandstone and Conglomerate

SEISMICITY

The proposed hydro-electric scheme is located in one of the most seismically active regions of the Territory of New Guinea: an average of four earthquakes of intensity IX on the Modified Mercalli Scale can be expected to occur in a 25-year period (Brooks, 1965).

The strongest series of earth tremors felt in the Gazelle Peninsula for some years occurred on August 14, 1967. The two largest shocks, which occurred in the morning, were of magnitude 6.2 and 6.4 as measured in Port Moresby on the Richter Scale. Over 150 aftershocks were recorded at Rabaul on the 14th, and subsequent days. The largest of these was of magnitude 5.6 on the Richter Scale.

All the shocks originated at a shallow depth (i.e., less than 33 kilometres from the surface) and were centred between two and four miles south-east of Kokopo (Plate 1). The maximum felt intensities recorded were IX on the Modified Mercalli Scale. Wooden frame buildings were shifted off their foundations and masonry of category D was destroyed. However, most of this damage resulted because the methods of founding the buildings were completely inadequate and no attempt had been made to ensure that a building acted as a whole in resisting horizontal forces.

An aerial inspection of the Gazelle Peninsula was carried out shortly after the disturbances had ceased. In the epicentral area extensive but superficial movement of cultivated slopes, embankments and placed fill had taken place. Many of the high, overhanging cuts in volcanic ash along the Kokopo - Rabaul road collapsed but no signs of earth movement were seen in a close inspection of the damsite, reservoir and catchment areas.

SILTATION

The Lower Warangoi River and the tributary Upper Warangoi and Kavavas Rivers carry a heavy bed load at times of high flow. During the preliminary geological investigation it was noticed (Read, 1965) that rapid increase in load took place after only moderate rainfall in the catchment area. The rate of siltation in the reservoir is therefore expected to be high, especially in the wet season.

Slope failure induced by earthquake activity would increase the rate of siltation. Although no landslides were observed in the Warangoi district following the Kokopo earthquakes in August, 1967, the extent of earth movements, even though only superficial, which took place in the Kokopo area underlines the likely reaction of potentially unstable slopes to a strong seismic shock with an epicentre located in the vicinity of the catchment or reservoir area.

CONCLUSIONS

Topographically, the proposed damsite and reservoir area on the Lower Warangoi River are suitable for the development of a hydro-electric scheme. However, there are unfavourable geological features which restrict considerably the usefulness of the site. These are:-

1. The weathered condition of the volcanic agglomerate. A high proportion of the agglomerate recovered from the damsite and the southern ridge by diamond drilling is moderately to highly weathered and correspondingly weak. Although more detailed strength testing of selected samples would be required for design purposes the overall weakness of the abutments indicates that either an earth-fill or rock-fill dam rather than a concrete structure would be required.
2. The configuration of the river channel between the abutments. The river channel is 300 feet wide at the narrowest point between the abutments, is approximately square-shaped, and is filled with river gravel and sand to a depth of 150 feet. Any structure would therefore require the use of river gravel and sand as a foundation which would again limit the choice to either an earth- or rock-fill dam. Problems associated with any design would include the likelihood of differential settlement between the river alluvium in the channel and the agglomerate in the abutments, and the provision of a suitable cut-off wall in the alluvium beneath the dam. To make the most effective use of the site a particularly sophisticated, and probably expensive, design would be necessary.
3. The permeability of the agglomerate. Jointing and weathering of the agglomerate has produced a body of rock at the damsite and along the southern ridge which has proved during water-pressure testing to be moderately to highly permeable. Prevention of further deterioration in rock condition due to water seepage, and loss of water through the abutments and the agglomerate sections of the southern ridge, would require extensive grouting. Although test holes would be necessary to estimate reliably the quantity of grout required per hole permeabilities indicate that the consumption would be high. As grout protection would be required over a total horizontal distance in excess of 3000 feet and to an average depth of at least 200 feet, the cost would be extremely high.
4. The presence of highly permeable sandstone and conglomerate beds in the southern ridge. The lowermost sandstone and conglomerate bed in the southern ridge is 55 feet thick and extends for a distance of at least 8000 feet around the base of the ridge immediately below the proposed top storage level. As water-pressure testing in drill hole WD6 and field permeability testing carried out by the Commonwealth Department of Works Central Testing and Research Laboratory has demonstrated the permeability of these beds to be extremely high, the potential water loss from the reservoir into the Sigule River drainage system is of serious proportions. In addition to the hazard of loss of water from the reservoir the possible long term effect of pressurised water seepage on the strength of the deposits should also be considered. Any failure in these beds could lead directly to increased leakage and eventual failure of the surrounding fine-grained sediments in the ridge. To ensure the safety and long life of the reservoir it would therefore be necessary to ensure that the lowermost sandstone and conglomerate bed was effectively sealed - an undertaking which, because of the extent and location of the bed, may be impracticable.

5. Seismicity. The location of the proposed scheme in an area of high seismicity poses several problems, which can be summarised as follows:-

- (i) Any design would be complicated by the need to found the dam on two materials- agglomerate and river sand and gravel - which would have markedly different responses to seismic shocks. Also more detailed investigation would be required to determine the particle velocity and acceleration developed in the sand and gravel foundation and the possible momentary loss of load-bearing capacity due to liquification or partial liquification of water-saturated sand.
- (ii) The cut-off wall in the river alluvium beneath the damsite, which would be a deep structure, would need to be flexible or self-healing to withstand high ground accelerations.
- (iii) In addition to allowing for high accelerations in the design of the dam it would also be necessary to give full consideration to the effect of regular, moderate to high seismic activity in the storage area. Any tendency towards slope instability, especially during the wet season, may be exaggerated by direct seismic impact on the sediments in the storage area, or by the erosive action of earthquake-induced waves in the reservoir.
- (iv) The dam would have to have sufficient freeboard to avoid overtopping by waves induced directly by seismic waves or by major landslide activity.

6. Siltation. The Lower Warangoi River and its tributaries carry a heavy silt load at times of high flow which would be reinforced following any disruption of the land surface by a major earthquake. In order to determine the probable useful life of the storage area it would be desirable to undertake an intensive programme of measurement of the bed load movement.

Overall, it is concluded that the Lower Warangoi hydro-electric scheme is, geologically, a doubtful proposition requiring further selective and expensive investigation before a structurally sound design could be specified. Although further investigation would probably provide sufficient information to enable the scheme to be implemented, it is considered that the cost would prove prohibitive.

RECOMMENDATIONS

Further investigation of the Lower Warangoi hydro-electric scheme should be discontinued until all other alternative methods of producing the power required to supply Rabaul and eventually the Gazelle Peninsula have been fully investigated. Design investigation could only be justified if studies of alternative schemes proved beyond reasonable doubt that the Lower Warangoi Scheme was the most economic proposition.

REFERENCES

- BEST, E.J., 1966 - Geological feasibility investigation of the Towanokoko-Pondo hydro-electric scheme. Bur. Min. Resour. Aust. Rec. 1966/133 (unpubl.).
- BLYTHE, K.R., 1967 - Soils investigation: Southern Ridge, Warangoi hydro-electric scheme, New Britain. Com.Dep.Works, C.T. & R.L. Techn. Rept. No. 47
- BROOKS, J.A., 1965 - Earthquake activity and seismic risk in Papua and New Guinea. Bur. Min. Resour. Aust. Rep. No. 74
- CARTER, E.K., 1962 - Geological investigations of the Towanokoko-Pondo hydro-electric scheme, New Britain, T.P.N.G., Bur.Min.Resour. Aust. Rec. 1962/120. (unpubl.).
- CARTER, E.K., & MACGREGOR, J.P., 1964 - Geology of a possible hydro-electric scheme on the Lower Warangoi River, New Britain, T.N.G. Preliminary inspection. Bur. Min. Resour. Aust. Rec. 1964/105 (unpubl.).
- CIFALI, G., MILSOM, J., & POLAK, E.J., 1967 - Warangoi dams site, New Britain, 1966, geophysical survey. Bur. Min. Resour. Aust. Rec. (in preparation).
- FISHER, N.H., 1939 - Geology and volcanology of Blanche Bay and the surrounding area, New Britain. Admin. T.N.G., Geol. Bull. No. 1.
- FISHER, N.H., 1959 - Geological reconnaissance of the Towanokoko-Pondo River hydro-electric scheme. Bur. Min. Resour. Aust. Rec. 1959/120 (unpubl.).
- PAPUA AND NEW GUINEA ELECTRICITY COMMISSION, 1966 - Annual Report, 1966.
- READ, J.R.L., 1965 - Preliminary geological investigation of the Lower Warangoi hydro-electric scheme, New Britain, T.P.N.G., August-November, 1964. Bur. Min. Resour. Aust. Rec. 1965/15 (unpubl.).

APPENDIX I

DEFINITIONS OF SEMI-QUANTITATIVE DESCRIPTIVE TERMS

The following terms have been used in this report:

Grade Scale.

Coarse-grained	$\frac{1}{2}$ mm to 1 mm in diameter
Medium-grained	$\frac{1}{4}$ mm to $\frac{1}{2}$ mm in diameter
Fine-grained	$\frac{1}{8}$ mm to $\frac{1}{4}$ mm in diameter

Weathering

Fresh	Rock shows no discolouration, loss of strength nor any other defect due to weathering.
Slightly weathered	Rock is slightly discoloured, but not noticeably lower in strength than the fresh rock.
Moderately weathered	Rock is usually discoloured and weakened to such an extent that a 2-inch drill core can be broken up readily by hand across the rock fabric. Wet strength usually much lower than dry strength.
Completely weathered	The rock is discoloured and is entirely changed to a soil, but the original fabric is mostly preserved. The properties of the soil depend upon the composition and structure of the parent rock.

APPENDIX 2

Geological Logs of Diamond Drill Holes

חפ

doi:10.1017/S0022292410000504

-70

178. M



154

672

100 Hydraulic
 100 Carving
 100 p.p.s.

32847

Two diagrams of a branching structure, possibly a tree or a path, with nodes labeled with numbers. The top diagram shows a vertical chain of nodes labeled 25, 15, 45, 15, 15, 15, 15. The bottom diagram shows a branching structure with nodes labeled 25, 45, 55, 45, 15, 15, 15.

[illegible]

BUREAU OF MINERAL RESOURCES,
GEOLOGY AND GEOPHYSICS

GEOLOGICAL LOG OF DRILL HOLE

PROJECT LOWER SWANAGEI H-8 SEHAME

LOCATION LAKE ABUJAH

DAKOTA ROAD R-13, 193 NB.

FAULT FROM HORIZONTAL -20°

COORDINATES

DIRECTION 78° 19'

N. 1 880 14'

HOLE NO.

WD1

SHEET 3 OF 4

DEPTH FEET	DESCRIPTION (COLOR, GRAIN, STRUCTURE, ETC.)	REMARKS (FACIES, LITHO, ETC.)	STRUCTURE (FOLDS, VEINS, BEAMS, ETC.)	WATER PRESSURE TEST (LOG IN COLUMN OF HOLE NO. 100)
0				70
10				70
20				70
30				70
40				70
50				70
60				70
70				70
80				70
90				70
100				70
110				70
120				70
130				70
140				70
150				70
160				70
170				70
180				70
190				70
200				70
210				70
220				70
230				70
240				70
250				70
260				70
270				70
280				70
290				70
300				70
310				70
320				70
330				70
340				70
350				70
360				70
370				70
380				70
390				70
400				70
410				70
420				70
430				70
440				70
450				70
460				70
470				70
480				70
490				70
500				70
510				70
520				70
530				70
540				70
550				70
560				70
570				70
580				70
590				70
600				70
610				70
620				70
630				70
640				70
650				70
660				70
670				70
680				70
690				70
700				70
710				70
720				70
730				70
740				70
750				70
760				70
770				70
780				70
790				70
800				70
810				70
820				70
830				70
840				70
850				70
860				70
870				70
880				70
890				70
900				70
910				70
920				70
930				70
940				70
950				70
960				70
970				70
980				70
990				70
1000				70

AGGLOMERATE. Light to dark grey, medium to coarse grained. Moderately to highly weathered. Rare fresh to slightly weathered pieces with maximum size of 3 in. Average pieces 2 in.

Rare, irregular joints, lightly coated with calcite. Core breaks easily through matrix into component fragments.

AGGLOMERATE. Remained zone. Fragments of limestone contained in moderately hard, calcareous matrix.

Broken zone 280' - 285' 8"

CORALLINE LIMESTONE. Cream colored. Numerous voids. Moderately hard and strong but with occasional very soft, highly weathered patches.

Agglomerate-limestone contact, although re-worked, apparently normal to core axis.

WELL NO. WD1
DATE 1/10/65
LOGGED BY J. R. Head
CHECKED BY J. R. Head
REVISION 10/10/65

REMARKS: (FACIES, LITHO, ETC.)

WATER PRESSURE TESTS
HOLE NO. WD1
DATE 1/10/65
LOGGED BY J. R. Head
CHECKED BY J. R. Head
REVISION 10/10/65

WELL LOG		DATE		TIME		WATER LEVEL		WATER PRESSURE TEST	
SURFACE OF WEATHERING		WELL DEPTH		WELL DEPTH		WELL DEPTH		WELL DEPTH	
CORALLINE LIMESTONE	As above.	8 1/2	9 1/2	10 1/2	11 1/2	12 1/2	13 1/2	14 1/2	15 1/2
Slightly to Moderately Weathered.		16 1/2	17 1/2	18 1/2	19 1/2	20 1/2	21 1/2	22 1/2	23 1/2
AGGLOMERATE	Reversed zone. Fragments of limestone contained in a soft, friable, calcareous matrix. Rare fresh pieces of agglomerate, maximum size 2 in.	24 1/2	25 1/2	26 1/2	27 1/2	28 1/2	29 1/2	30 1/2	31 1/2
Moderately to Highly Weathered.		32 1/2	33 1/2	34 1/2	35 1/2	36 1/2	37 1/2	38 1/2	39 1/2
AGGLOMERATE	Light grey to brown. Medium-grained. Moderately hard and strong.	40 1/2	41 1/2	42 1/2	43 1/2	44 1/2	45 1/2	46 1/2	47 1/2
Slightly Weathered.		48 1/2	49 1/2	50 1/2	51 1/2	52 1/2	53 1/2	54 1/2	55 1/2
END OF HOLE		56 1/2	57 1/2	58 1/2	59 1/2	60 1/2	61 1/2	62 1/2	63 1/2

[illegible]

REPORT ON YOUR TEST

POWER TOOL NH Hydraulic

POWER LINE AR CORING

VERTICAL TOOLS 1 inch - 80 psi

USE APPROPRIATE TOOLS (POWERED)
FOR REPORTING THE PRODUCTION OF RESULTS TO THE USER - 100%

PHOTOGRAPHY REFERENCE SYSTEM

DATE AND TIME

NAME <u>Donald E. Felt</u> TITLE <u>Director</u> ORGANIZATION <u>NSA</u> ADDRESS <u>Room 3A</u> CITY <u>Washington</u> STATE <u>D.C.</u> ZIP <u>20505</u> PHONE <u>202-456-7890</u> FAX <u>202-456-7891</u> E-MAIL <u>dfelt@nsa.gov</u> COMMENTS <u>10/1/80</u>	NAME <u>Mr. [illegible]</u> TITLE <u>[illegible]</u> ORGANIZATION <u>[illegible]</u> ADDRESS <u>[illegible]</u> CITY <u>[illegible]</u> STATE <u>[illegible]</u> ZIP <u>[illegible]</u> PHONE <u>[illegible]</u> FAX <u>[illegible]</u> E-MAIL <u>[illegible]</u> COMMENTS <u>[illegible]</u>
---	---

BUREAU OF MINERAL RESOURCES
GEOLOGY AND GEOPHYSICS

PROJECT LOWER WARANGI, HYDRO-ELECTRIC SCHEME

LOCATION DAMSITE, RIGHT ABUTMENT

HOLE NO.

WD 3

GEOLOGICAL LOG OF DRILL HOLE

ANGLE FROM HORIZONTAL -40

DIRECTION 125° MAG

COORDINATES T+30, 265 FT, S.W.

R. 130 FT

SHEET 2 OF 3

ROCK TYPE & DEGREE OF WEATHERING	DESCRIPTION (COLOUR, GRAIN, STRENGTH, HARDNESS, ETC.)	DEPTH LOG	STRUCTURE LOG	TEST LOG	STRUCTURES (JOINTS, VENS, SEAMS, FAULTS, CRUSHED ZONES)	WATER PRESSURE TEST (PRESS. IN PSI, FEET OF WATER, ETC.)
AGGLOMERATE	Agglomerate as above but with occasional andesitic boulders up to 2ft. in length. Pieces $\frac{1}{4}$ " - 15", made 5°.	110			Slightly broken zones 107'6" - 107'10", 108'9" - 110".	
Slightly to Moderately Weathered.		120			Joints widely spaced, 30", 45", 65", lightly coated with calcite & clay.	
	Pieces $\frac{1}{4}$ " - 10", made 6°.	130			Moderately broken zone 127'5" - 128'2".	
		140				
		148				
AGGLOMERATE	Volcanic fragments light to dark grey. Matrix brown. Moderately soft, rarely moderately hard. Moderately weak matrix friable and core readily broken by hand. Pieces $\frac{1}{4}$ " - 15", made 8°.	150			Moderately broken zones 143'8" - 144", 146'6" - 146'8", 147'10" - 148'3".	
Moderately weathered.		160			Moderately broken zone 155'7" - 156'3".	
		170			Slightly broken zone 165'10" - 166".	
		180			Joints widely spaced, 45", 70", coated with calcite & clay.	
	Pieces $\frac{1}{4}$ " - 8", made 3°.	190			Moderately broken zones 187'4" - 188'5", 189'8" - 190", 193" - 196", 196'5" - 196'10", 197'4" - 197'8".	



DRILL TYPE Hydraulic
LOG NAME NMALC
Tape Tube
DRILLER T. Condon C.D.W.
COMPLETED 21-5-66
CHECKED BY F.B. Read
VERTICAL SCALE 1 inch = 10 feet

THIS LOG IS THE PROPERTY OF THE BUREAU OF MINERAL RESOURCES AND IS LOANED TO YOU BY THE BUREAU OF MINERAL RESOURCES. IT IS TO BE RETURNED TO THE BUREAU OF MINERAL RESOURCES WHEN YOU HAVE FINISHED WITH IT.

WATER PRESSURE TEST
DRILLER TYPE M. Mechanical
DRILLER NAME M. Carey
VERTICAL SCALE 1 inch = 20 feet
DRILLER TYPE M. Carey
DRILLER NAME M. Carey
DRILLER TYPE M. Carey
DRILLER NAME M. Carey

BUREAU OF MINERAL RESOURCES,
GEOLOGY AND GEOPHYSICS

GEOLOGICAL LOG OF DRILL HOLE

PROJECT LOWER WARANGAL HYDRO-ELECTRIC SCHEME
LOCATION DAMITE, RIGHT ABUTMENT
ANGLE FROM HORIZONTAL -40° DIRECTION 125° MAG
COORDINATES T=20, 285 FT. S.W. N=130 FT.

HOLE NO.
WD 3
SHEET **3** OF **3**

ROCK TYPE & DEGREE OF WEATHERING	DESCRIPTION (COLOR, GRAIN, STRENGTH, HARDNESS, ETC.)	DEPTH & SIZE OF CORE	FRACTURE LOG	JOINTS & FOLDS	STRUCTURES (JOINTS, FOLDS, SCALE, CALCITE, CRUSTED, ETC.)	WATER LEVEL	WATER PRESSURE TEST (TIME IN MINUTES, PRESSURE IN PSI)
AGGLOMERATE Moderately weathered	Agglomerate as above Matrix pitted and friable Pieces 1/2" - 6", made 2"	0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150 160 170 180 190 200 210 220 230	None		Moderately broken zone 30' - 30'5" Slightly broken zone 310'8" - 310'6" Moderately broken zone 320' - 320'15" Slightly broken zones 324'7" - 324'8", 330'2" - 330'7"	100 120 140 160 180 200 220 240 260 280 300 320 340 360 380 400 420 440 460 480 500 520 540 560 580 600 620 640 660 680 700 720 740 760 780 800 820 840 860 880 900 920 940 960 980 1000 1020 1040 1060 1080 1100 1120 1140 1160 1180 1200 1220 1240 1260 1280 1300 1320 1340 1360 1380 1400 1420 1440 1460 1480 1500 1520 1540 1560 1580 1600 1620 1640 1660 1680 1700 1720 1740 1760 1780 1800 1820 1840 1860 1880 1900 1920 1940 1960 1980 2000 2020 2040 2060 2080 2100 2120 2140 2160 2180 2200 2220 2240 2260 2280 2300 2320 2340 2360 2380 2400 2420 2440 2460 2480 2500 2520 2540 2560 2580 2600 2620 2640 2660 2680 2700 2720 2740 2760 2780 2800 2820 2840 2860 2880 2900 2920 2940 2960 2980 3000 3020 3040 3060 3080 3100 3120 3140 3160 3180 3200 3220 3240 3260 3280 3300 3320 3340 3360 3380 3400 3420 3440 3460 3480 3500 3520 3540 3560 3580 3600 3620 3640 3660 3680 3700 3720 3740 3760 3780 3800 3820 3840 3860 3880 3900 3920 3940 3960 3980 4000 4020 4040 4060 4080 4100 4120 4140 4160 4180 4200 4220 4240 4260 4280 4300 4320 4340 4360 4380 4400 4420 4440 4460 4480 4500 4520 4540 4560 4580 4600 4620 4640 4660 4680 4700 4720 4740 4760 4780 4800 4820 4840 4860 4880 4900 4920 4940 4960 4980 5000 5020 5040 5060 5080 5100 5120 5140 5160 5180 5200 5220 5240 5260 5280 5300 5320 5340 5360 5380 5400 5420 5440 5460 5480 5500 5520 5540 5560 5580 5600 5620 5640 5660 5680 5700 5720 5740 5760 5780 5800 5820 5840 5860 5880 5900 5920 5940 5960 5980 6000 6020 6040 6060 6080 6100 6120 6140 6160 6180 6200 6220 6240 6260 6280 6300 6320 6340 6360 6380 6400 6420 6440 6460 6480 6500 6520 6540 6560 6580 6600 6620 6640 6660 6680 6700 6720 6740 6760 6780 6800 6820 6840 6860 6880 6900 6920 6940 6960 6980 7000 7020 7040 7060 7080 7100 7120 7140 7160 7180 7200 7220 7240 7260 7280 7300 7320 7340 7360 7380 7400 7420 7440 7460 7480 7500 7520 7540 7560 7580 7600 7620 7640 7660 7680 7700 7720 7740 7760 7780 7800 7820 7840 7860 7880 7900 7920 7940 7960 7980 8000 8020 8040 8060 8080 8100 8120 8140 8160 8180 8200 8220 8240 8260 8280 8300 8320 8340 8360 8380 8400 8420 8440 8460 8480 8500 8520 8540 8560 8580 8600 8620 8640 8660 8680 8700 8720 8740 8760 8780 8800 8820 8840 8860 8880 8900 8920 8940 8960 8980 9000 9020 9040 9060 9080 9100 9120 9140 9160 9180 9200 9220 9240 9260 9280 9300 9320 9340 9360 9380 9400 9420 9440 9460 9480 9500 9520 9540 9560 9580 9600 9620 9640 9660 9680 9700 9720 9740 9760 9780 9800 9820 9840 9860 9880 9900 9920 9940 9960 9980 10000	100 120 140 160 180 200 220 240 260 280 300 320 340 360 380 400 420 440 460 480 500 520 540 560 580 600 620 640 660 680 700 720 740 760 780 800 820 840 860 880 900 920 940 960 980 1000 1020 1040 1060 1080 1100 1120 1140 1160 1180 1200 1220 1240 1260 1280 1300 1320 1340 1360 1380 1400 1420 1440 1460 1480 1500 1520 1540 1560 1580 1600 1620 1640 1660 1680 1700 1720 1740 1760 1780 1800 1820 1840 1860 1880 1900 1920 1940 1960 1980 2000 2020 2040 2060 2080 2100 2120 2140 2160 2180 2200 2220 2240 2260 2280 2300 2320 2340 2360 2380 2400 2420 2440 2460 2480 2500 2520 2540 2560 2580 2600 2620 2640 2660 2680 2700 2720 2740 2760 2780 2800 2820 2840 2860 2880 2900 2920 2940 2960 2980 3000 3020 3040 3060 3080 3100 3120 3140 3160 3180 3200 3220 3240 3260 3280 3300 3320 3340 3360 3380 3400 3420 3440 3460 3480 3500 3520 3540 3560 3580 3600 3620 3640 3660 3680 3700 3720 3740 3760 3780 3800 3820 3840 3860 3880 3900 3920 3940 3960 3980 4000 4020 4040 4060 4080 4100 4120 4140 4160 4180 4200 4220 4240 4260 4280 4300 4320 4340 4360 4380 4400 4420 4440 4460 4480 4500 4520 4540 4560 4580 4600 4620 4640 4660 4680 4700 4720 4740 4760 4780 4800 4820 4840 4860 4880 4900 4920 4940 4960 4980 5000 5020 5040 5060 5080 5100 5120 5140 5160 5180 5200 5220 5240 5260 5280 5300 5320 5340 5360 5380 5400 5420 5440 5460 5480 5500 5520 5540 5560 5580 5600 5620 5640 5660 5680 5700 5720 5740 5760 5780 5800 5820 5840 5860 5880 5900 5920 5940 5960 5980 6000 6020 6040 6060 6080 6100 6120 6140 6160 6180 6200 6220 6240 6260 6280 6300 6320 6340 6360 6380 6400 6420 6440 6460 6480 6500 6520 6540 6560 6580 6600 6620 6640 6660 6680 6700 6720 6740 6760 6780 6800 6820 6840 6860 6880 6900 6920 6940 6960 6980 7000 7020 7040 7060 7080 7100 7120 7140 7160 7180 7200 7220 7240 7260 7280 7300 7320 7340 7360 7380 7400 7420 7440 7460 7480 7500 7520 7540 7560 7580 7600 7620 7640 7660 7680 7700 7720 7740 7760 7780 7800 7820 7840 7860 7880 7900 7920 7940 7960 7980 8000 8020 8040 8060 8080 8100 8120 8140 8160 8180 8200 8220 8240 8260 8280 8300 8320 8340 8360 8380 8400 8420 8440 8460 8480 8500 8520 8540 8560 8580 8600 8620 8640 8660 8680 8700 8720 8740 8760 8780 8800 8820 8840 8860 8880 8900 8920 8940 8960 8980 9000 9020 9040 9060 9080 9100 9120 9140 9160 9180 9200 9220 9240 9260 9280 9300 9320 9340 9360 9380 9400 9420 9440 9460 9480 9500 9520 9540 9560 9580 9600 9620 9640 9660 9680 9700 9720 9740 9760 9780 9800 9820 9840 9860 9880 9900 9920 9940 9960 9980 10000
	End of hole 231 feet.						

Drill Bit Hydraulic
Core Sample Type ATAC
Fracture Basal
Driller T. Gordon Case
Completed 1958-59
Location J.P. Road
Vertical Scale 1 inch = 10 feet

FRACTURE LOG: Summary of fractures and joint planes in rock core and rock mass.
REMARKS AND JOINT PLACES: Summary of fracture locations.

WATER PRESSURE TESTS
Packer Type H. Mechanical
Supply Line At Casing
Vertical Scale 1 inch = 200 psi
Reports give the gauge pressure.
Test surface and indicated quantity by fracture in core.
PHOTOGRAPH REFERENCE SYSTEM
BLACK AND WHITE
COLOR

1.1

621.6 二卷一冊 370

End of hole 109 feet
in sand & gravel.

43

20

52

For

1

50

45

10


10

25

1942-1943. The following is a list of the names of the persons who were members of the Board of Directors of the American Red Cross during the year 1942-1943.

WATER RESOURCES TODAY

NAME: _____
 ADDRESS: _____
 CITY: _____
 STATE: _____
 ZIP: _____
 PHONE: _____
 FAX: _____
 E-MAIL: _____
 SIGNATURE: _____
 DATE: _____



DRILL TYPE *Mindrift FISC*
DRILL *Hydraulic*
LOG SAMPLE TYPE *NHLC*
Triple Tube
LOG BY *R. Haddings C.O.D.*
DATE *15-7-66*
COMPLETED *21-7-66*
CHECKED BY *J.R. Reed*
REVISION *Check 10 ft.*

REMARKS: This is a summary of the log of the hole. It is not intended to be a complete record of the log. The log is a summary of the log of the hole. It is not intended to be a complete record of the log.

OTHER MEASUREMENTS

PHOTOGRAPH REFERENCE SYSTEM
IN FEET AND INCHES

BUREAU OF MINERAL RESOURCES,
GEOLOGY AND GEOPHYSICS

GEOLOGICAL LOG OF DRILL HOLE

PROJECT LOWER WARREBOI HYDRO-ELECTRIC SCHEME

LOCATION SOUTHERN RIDGE CADDIE MOUNTAIN

265X C.S. AND A.9.

ANGLE FROM HORIZONTAL -90


COORDINATES

DIRECTION 291 feet

HOLE NO.

WD 6

SHEET 2 of 3



WATER METER 21000
 TYPE Hydraulic
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"

WATER METER 21000
 TYPE Hydraulic
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"

WATER METER 21000
 TYPE Hydraulic
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"
 SIZE 1/2" x 1/2" x 1/2"

BUREAU OF MINERAL RESOURCES,
GEOLOGY AND GEOPHYSICS

GEOLOGICAL LOG OF DRILL HOLE

PROJECT LOWER WARREN HYDRO-ELECTRIC SCHEME

LOCATION SOUTHERN RIDGE SADDLE, MIDWAY

REES 28 AND 29

ANGLE FROM HORIZONTAL -90


COORDINATES

DIRECTION 291 feet

HOLE NO.

WD 6

SHEET 3 OF 3



DRILL TYPE Hydraulic
 CORE BARREL TYPE BMCC
 TAPES Tape Tube
 OPERATOR S. Walpole, C.D.W.
 COMMENCED 22-6-66
 COMPLETED 4-10-66
 LOGGED BY J.R.L. Reed
 VERIFICATION 1 inch ± 10 ft.

FRACTURE LOG - Number of fractures per foot of core length and their orientation in the core wall.

WATER PRESSURE LOGS

WATER TYPE
 PRESSURE
 TEMPERATURE
 FLOW RATE
 FLOW METER
 FLOW METER
 FLOW METER

ROCK TYPE (AS DETERMINED BY WEATHERING)	DESCRIPTION (FINDINGS, GRADE, STRIKE, DIP, etc.)	DEPTH (FEET)	DIAMETER (INCHES)	TESTS (e.g., pH, etc.)	WATER PRESSURE TESTS (e.g., etc.)
AGGLOMERATE	Light to dark grey. Medium to coarse-grained. Andesitic. Moderately soft to soft. Weak, friable, very easily broken into small fragments. Occasional pieces up to a maximum size of 6". Average pieces 3".	10 20 30 40 50 60 70 80 90	10 10 10 10 10 10 10 10 10		
RIVER GRAVELS.	Small, 1/2-1", pieces of agglomerate and rounded pebbles of agglomerate, granite, basalt, granodiorite, limestone & feldspar porphyry. Average diameter 1/2".	90	10		

Look of determinable structure. Core breaks into component fragments through the weak matrix.

140 ft.

SCALE 1 CM
HORIZONTAL SCALE
VERTICAL SCALE
Figures given in square brackets
for vertical are horizontal projections by standard - slope
PHTHOGRAPH BY THESEK FIDAN
B-608 492 4075

GEOLOGICAL LOG OF DRILL HOLE


HOLE FROM SURFACE

-70

DATE 22.11.17

COORDINATES K 23, 124 61, NE

120 11




WELL NO. *Monroville 81000*
TYPE *Hydraulic*
DATE *1917*
BY *T. J. Barrell*
CORRECTION *E. Schaefer, C.A.W.*
DATE *19-11-17*
REMARKS *10' - 1' 24*
CORRECTION *J. B. Reed*
REMARKS *10' 24*

REMARKS *10' 24*

REMARKS *10' 24*

REMARKS *10' 24*



Model E1000
Hydraulic
Tripole Tube
E. Schneider Ltd.
19-11-65
10-1-66
J.R. Read
1 inch 10 feet

THESE TESTS WERE MADE AT THE BUREAU OF MINERAL RESOURCES, GEOLOGY AND GEOPHYSICS, CANBERRA, AUSTRALIA.

WATER PROPERTIES (1965)
No. 1 & 2, hydraulic &
No. 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000, 1001, 1002, 1003, 1004, 1005, 1006, 1007, 1008, 1009, 1010, 1011, 1012, 1013, 1014, 1015, 1016, 1017, 1018, 1019, 1020, 1021, 1022, 1023, 1024, 1025, 1026, 1027, 1028, 1029, 1030, 1031, 1032, 1033, 1034, 1035, 1036, 1037, 1038, 1039, 1040, 1041, 1042, 1043, 1044, 1045, 1046, 1047, 1048, 1049, 1050, 1051, 1052, 1053, 1054, 1055, 1056, 1057, 1058, 1059, 1060, 1061, 1062, 1063, 1064, 1065, 1066, 1067, 1068, 1069, 1070, 1071, 1072, 1073, 1074, 1075, 1076, 1077, 1078, 1079, 1080, 1081, 1082, 1083, 1084, 1085, 1086, 1087, 1088, 1089, 1090, 1091, 1092, 1093, 1094, 1095, 1096, 1097, 1098, 1099, 1100, 1101, 1102, 1103, 1104, 1105, 1106, 1107, 1108, 1109, 1110, 1111, 1112, 1113, 1114, 1115, 1116, 1117, 1118, 1119, 1120, 1121, 1122, 1123, 1124, 1125, 1126, 1127, 1128, 1129, 1130, 1131, 1132, 1133, 1134, 1135, 1136, 1137, 1138, 1139, 1140, 1141, 1142, 1143, 1144, 1145, 1146, 1147, 1148, 1149, 1150, 1151, 1152, 1153, 1154, 1155, 1156, 1157, 1158, 1159, 1160, 1161, 1162, 1163, 1164, 1165, 1166, 1167, 1168, 1169, 1170, 1171, 1172, 1173, 1174, 1175, 1176, 1177, 1178, 1179, 1180, 1181, 1182, 1183, 1184, 1185, 1186, 1187, 1188, 1189, 1190, 1191, 1192, 1193, 1194, 1195, 1196, 1197, 1198, 1199, 1200, 1201, 1202, 1203, 1204, 1205, 1206, 1207, 1208, 1209, 1210, 1211, 1212, 1213, 1214, 1215, 1216, 1217, 1218, 1219, 1220, 1221, 1222, 1223, 1224, 1225, 1226, 1227, 1228, 1229, 1230, 1231, 1232, 1233, 1234, 1235, 1236, 1237, 1238, 1239, 1240, 1241, 1242, 1243, 1244, 1245, 1246, 1247, 1248, 1249, 1250, 1251, 1252, 1253, 1254, 1255, 1256, 1257, 1258, 1259, 1260, 1261, 1262, 1263, 1264, 1265, 1266, 1267, 1268, 1269, 1270, 1271, 1272, 1273, 1274, 1275, 1276, 1277, 1278, 1279, 1280, 1281, 1282, 1283, 1284, 1285, 1286, 1287, 1288, 1289, 1290, 1291, 1292, 1293, 1294, 1295, 1296, 1297, 1298, 1299, 1300, 1301, 1302, 1303, 1304, 1305, 1306, 1307, 1308, 1309, 1310, 1311, 1312, 1313, 1314, 1315, 1316, 1317, 1318, 1319, 1320, 1321, 1322, 1323, 1324, 1325, 1326, 1327, 1328, 1329, 1330, 1331, 1332, 1333, 1334, 1335, 1336, 1337, 1338, 1339, 1340, 1341, 1342, 1343, 1344, 1345, 1346, 1347, 1348, 1349, 1350, 1351, 1352, 1353, 1354, 1355, 1356, 1357, 1358, 1359, 1360, 1361, 1362, 1363, 1364, 1365, 1366, 1367, 1368, 1369, 1370, 1371, 1372, 1373, 1374, 1375, 1376, 1377, 1378, 1379, 1380, 1381, 1382, 1383, 1384, 1385, 1386, 1387, 1388, 1389, 1390, 1391, 1392, 1393, 1394, 1395, 1396, 1397, 1398, 1399, 1400, 1401, 1402, 1403, 1404, 1405, 1406, 1407, 1408, 1409, 1410, 1411, 1412, 1413, 1414, 1415, 1416, 1417, 1418, 1419, 1420, 1421, 1422, 1423, 1424, 1425, 1426, 1427, 1428, 1429, 1430, 1431, 1432, 1433, 1434, 1435, 1436, 1437, 1438, 1439, 1440, 1441, 1442, 1443, 1444, 1445, 1446, 1447, 1448, 1449, 1450, 1451, 1452, 1453, 1454, 1455, 1456, 1457, 1458, 1459, 1460, 1461, 1462, 1463, 1464, 1465, 1466, 1467, 1468, 1469, 1470, 1471, 1472, 1473, 1474, 1475, 1476, 1477, 1478, 1479, 1480, 1481, 1482, 1483, 1484, 1485, 1486, 1487, 1488, 1489, 1490, 1491, 1492, 1493, 1494, 1495, 1496, 1497, 1498, 1499, 1500, 1501, 1502, 1503, 1504, 1505, 1506, 1507, 1508, 1509, 1510, 1511, 1512, 1513, 1514, 1515, 1516, 1517, 1518, 1519, 1520, 1521, 1522, 1523, 1524, 1525, 1526, 1527, 1528, 1529, 1530, 1531, 1532, 1533, 1534, 1535, 1536, 1537, 1538, 1539, 1540, 1541, 1542, 1543, 1544, 1545, 1546, 1547, 1548, 1549, 1550, 1551, 1552, 1553, 1554, 1555, 1556, 1557, 1558, 1559, 1560, 1561, 1562, 1563, 1564, 1565, 1566, 1567, 1568, 1569, 1570, 1571, 1572, 1573, 1574, 1575, 1576, 1577, 1578, 1579, 1580, 1581, 1582, 1583, 1584, 1585, 1586, 1587, 1588, 1589, 1590, 1591, 1592, 1593, 1594, 1595, 1596, 1597, 1598, 1599, 1600, 1601, 1602, 1603, 1604, 1605, 1606, 1607, 1608, 1609, 1610, 1611, 1612, 1613, 1614, 1615, 1616, 1617, 1618, 1619, 1620, 1621, 1622, 1623, 1624, 1625, 1626, 1627, 1628, 1629, 1630, 1631, 1632, 1633, 1634, 1635, 1636, 1637, 1638, 1639, 1640, 1641, 1642, 1643, 1644, 1645, 1646, 1647, 1648, 1649, 1650, 1651, 1652, 1653, 1654, 1655, 1656, 1657, 1658, 1659, 1660, 1661, 1662, 1663, 1664, 1665, 1666, 1667, 1668, 1669, 1670, 1671, 1672, 1673, 1674, 1675, 1676, 1677, 1678, 1679, 1680, 1681, 1682, 1683, 1684, 1685, 1686, 1687, 1688, 1689, 1690, 1691, 1692, 1693, 1694, 1695, 1696, 1697, 1698, 1699, 1700, 1701, 1702, 1703, 1704, 1705, 1706, 1707, 1708, 1709, 1710, 1711, 1712, 1713, 1714, 1715, 1716, 1717, 1718, 1719, 1720, 1721, 1722, 1723, 1724, 1725, 1726, 1727, 1728, 1729, 1730, 1731, 1732, 1733, 1734, 1735, 1736, 1737, 1738, 1739, 1740, 1741, 1742, 1743, 1744, 1745, 1746, 1747, 1748, 1749, 1750, 1751, 1752, 1753, 1754, 1755, 1756, 1757, 1758, 1759, 1760, 1761, 1762, 1763, 1764, 1765, 1766, 1767, 1768, 1769, 1770, 1771, 1772, 1773, 1774, 1775, 1776, 1777, 1778, 1779, 1780, 1781, 1782, 1783, 1784, 1785, 1786, 1787, 1788, 1789, 1790, 1791, 1792, 1793, 1794, 1795, 1796, 1797, 1798, 1799, 1800, 1801, 1802, 1803, 1804, 1805, 1806, 1807, 1808, 1809, 1810, 1811, 1812, 1813, 1814, 1815, 1816, 1817, 1818, 1819, 1820, 1821, 1822, 1823, 1824, 1825, 1826, 1827, 1828, 1829, 1830, 1831, 1832, 1833, 1834, 1835, 1836, 1837, 1838, 1839, 1840, 1841, 1842, 1843, 1844, 1845, 1846, 1847, 1848, 1849, 1850, 1851, 1852, 1853, 1854, 1855, 1856, 1857, 1858, 1859, 1860, 1861, 1862, 1863, 1864, 1865, 1866, 1867, 1868, 1869, 1870, 1871, 1872, 1873, 1874, 1875, 1876, 1877, 1878, 1879, 1880, 1881, 1882, 1883, 1884, 1885, 1886, 1887, 1888, 1889, 1890, 1891, 1892, 1893, 1894, 1895, 1896, 1897, 1898, 1899, 1900, 1901, 1902, 1903, 1904, 1905, 1906, 1907, 1908, 1909, 1910, 1911, 1912, 1913, 1914, 1915, 1916, 1917, 1918, 1919, 1920, 1921, 1922, 1923, 1924, 1925, 1926, 1927, 1928, 1929, 1930, 1931, 1932, 1933, 1934, 1935, 1936, 1937, 1938, 1939, 1940, 1941, 1942, 1943, 1944, 1945, 1946, 1947, 1948, 1949, 1950, 1951, 1952, 1953, 1954, 1955, 1956, 1957, 1958, 1959, 1960, 1961, 1962, 1963, 1964, 1965, 1966, 1967, 1968, 19

BUREAU OF MINERAL RESOURCES,
GEOLOGY AND GEOPHYSICS

PROJECT LOWER WARANGOI HYDRO-ELECTRIC SCHEME

LOCATION DAMSITE, LEFT ABUTMENT

HOLE NO.


WD8A

GEOLOGICAL LOG OF DRILL HOLE

ANGLE FROM HORIZONTAL -70° DIRECTION 157° MAG.

COORDINATES N+23, 134 ft. N.E. E.L. 120 ft.

SHEET 3 OF 3



Drill: Hydraulic
Core Sample Type: GMLC
Trip: Barrel
By: F. Schneider, C.W.
Completed: 12-11-66
Logged: 10-3-66
Checked by: J.R.L. Reed
Vertical Scale: 1 inch = 10 feet

FRAC-
TURE
LOG: Number of fractures per foot of core, size of fracture, and direction of fracture. (Log and fracture log are to be made on a separate sheet.)

WATER PRESSURE TESTS
Pressure Type: BX Mechanical
Depth: 105 feet
Vertical Scale: 1 inch = 200 psi
Photograph Reference System
Black and White

OVERBURDEN		Soil and agglomerate series	27'9"	10	16'	20	25'	30	38'7"	40	50	55'	60	70	80	90
OVERBURDEN	Soil and agglomerate series															
AGGLOMERATE	Andesitic, fine to medium grained, dark grey. Moderately to highly weathered.	Pieces $< \frac{1}{2}$ "														
AGGLOMERATE	Andesitic, fine to medium-grained, light grey. Moderately hard, moderately strong.	Pieces $\frac{1}{4}$ " - 8", made 1"														
AGGLOMERATE	Andesitic, fine to medium-grained, light grey. Hard, strong.	Pieces $\frac{1}{4}$ " - 17", made 6"														
AGGLOMERATE	Andesitic, fine to medium-grained, light grey to light brown. Moderately hard, moderately strong.	Pieces $\frac{1}{4}$ " - 20", made 10"														
AGGLOMERATE	Andesitic, medium grained volcanic fragments light grey, often vesicular. Matrix brown, edgy and pitted. Moderately soft to moderately hard. Moderately weak with occasional moderately strong patches. Core mostly readily broken by hand.	Pieces $\frac{1}{4}$ " - 2", made $\frac{1}{2}$ "														
						</										

GEOLOGICAL LOG OF DRILL HOLE

ANGLE FROM HORIZONTAL

 -90°


COORDINATES

220

WD9

2 of 4


GENERAL INFORMATION		DESCRIPTION		SPECIFICATIONS		TESTS		ANALYSIS		REMARKS	
DATE	TIME	LOCATION	DEPTH	DIAMETER	WEIGHT	STRENGTH	MODULUS	COMPOSITION	STRUCTURE	OTHER	REMARKS
1941		102'-104'6"		NMLC						Cuttings only 102'-104'6"	
1941		110'		NMLC						Agglomerate, as above	
1941		120'		NMLC						Highly broken zone 110'-113'	
1941		130'		NMLC						Highly broken friable zone 125'3" - 125'10"	
1941		140'		NMLC						Moderately broken across intersecting joints 127' - 127'10"	
1941		150'		NMLC						Moderately broken zones 133' - 133'4", 134'7" - 135'135'7" - 135'10"	
1941		160'		NMLC						Slightly broken zones 141' - 141'3", 142'2" - 143'7"	
1941		170'		NMLC						Joints lightly coated with clay & calcite, widely spaced 30", 55", 70"	
1941		180'		NMLC						Slightly broken zone 150' - 150'4"	
1941		190'		NMLC						Cuttings only 155' - 155'8"	
1941		200'		NMLC						Pieces 1/2" - 12", mode 2"	
1941		210'		NMLC						Cuttings only 171' - 171'8" and 175'5" - 177'5"	
1941		220'		NMLC						Moderately broken zones 166'8" - 166'11", 167'8" - 168'2", 170' - 170'3"	
1941		230'		NMLC						Core highly broken 180' - 200' due to failure of weak material during drilling	
1941		240'		NMLC						Pieces 1/4" - 5", mode 3/4"	
1941		250'		NMLC						Cuttings only 189'3" - 190'9"	



Dr. in Charge P.B.C.
Field Hydroelectric
Date 1960
By Trish Tade
Checked by R. Madhavi C.M.
Comments
Drawn by L.R. Rood
Vertical Scale 1 inch = 10 feet

FIGURE LOG: Number of specimens and size of core taken at each depth and location in
SECTION AND TEST PLANNED - Figure and specimen number in the core log.

WATER PRESSURE TEST
Pressure Type N & B Madhavi
Supply Line At Casing
Vertical Scale 1 inch = 200 p.p.s.
Figure Log: The figure pressure
test section and specimen number in the
PHOTOGRAPH REFERENCE SYSTEM
BLACK AND WHITE



DRILL TYPE *Climax FSC*
PUMP *Hydraulic*
CORE BARREL TYPE *BMSC*
Triax Tube
DRILLER *R. Chasings* C.O.W.
COMPLETER
LOGGED BY *J.E.L. Read*
VERTICAL SCALE *1 inch = 10 feet*

REMARKS
REMARKS AND ADJUST PLANNED - ADJUSTED TO MEASURE PROBLEM IN THE CORE LOG

WATER PRESSURE TESTS
PUMP TYPE *B Mechanical*
CORELINE *AX Casing*
VERTICAL SCALE *1 inch = 200 psi*
PHOTOGRAPH - REFERENCE SYSTEM
BLACK AND WHITE

GEOLOGICAL LOG OF DRILL HOLE

ANGLE FROM HORIZONTAL

-55°

DIRECTION 295° MAG.

COORDINATES

R.L. 300.44

SHEET 1 of 2

ROCK TYPE & DEGREE OF WEATHERING	DESCRIPTION LITHOLOGY, COLOUR, STRENGTH, HARDNESS, ETC.	GRAPHIC LOG	DEPTH & SIZE OF CORE	FRACURE LOG	LIFT & % CORE RECOVERY	STRUCTURES JOINTS, VENS, SEAMS, FAULTS, CRUSHED ZONES	WATER PRESSURE TEST LOG IN GROUND 200' MINUTE 200' MIN
CLAYSTONE Fresh	Soft, weak, brown, silty plastic clay		10				
MUDSTONE Fresh	Black, soft, weak, with numerous shrinkage cracks.		18'6"				
SANDY CLAYSTONE. Fresh.	Light gray to light brown, irregularly sandy & silty. Moderately indurated, moderately weak. Although core largely intact is easily snapped by hand. Pieces $\frac{1}{4}$ " - 26", made 14".		20			Broken & crushed zone 21'4" - 22'4"	
			30				
			40			Broken & crushed zone 40'9" - 41'8"	
			50			45" joints at 49'1" & 49'6"	
	Becoming calcareous medium-coarse-grained from 55'.		55			30" joints at 54' & 56'6"	
LIMESTONE Slightly to Moderately Weathered.	Whitish-cream. Coralline, moderately soft to moder- ately hard. Moderately weak. Slight solution activity. Pieces $\frac{1}{4}$ " - 6", made 2"		70				
LIMESTONE & AGGLOMERATE Slightly to Moderately Weathered	Cream-light grey - brown. Reworked coralline limestone & agglomerate. Contact gradational. Moderately soft to moder- ately hard. Moderately weak. Slight solution activity. Pieces $\frac{1}{4}$ " - 10", made 3"		80			Highly broken zones 70'10" - 71'10" & 72'8" - 72'11"	
			90			Highly broken zone 86'10" - 87'2"	
AGGLOMERATE Moderately to Highly Weathered.							

DRILL TYPE: Mindoll E1000FEED: HydraulicCORE BARREL TYPE: NMCCTUBE: Triple TubeDRILLER: F. Condon C.D.W.COMMENCED: 15-6-66COMPLETED: 9-66LOGGED BY: J.R. ReadVERTICAL SCALE: 1 inch = 100 ft.

NOTES

FRACURE LOG: Number of fractures per foot at each 20' interval of core test are shown in
BEDDING AND JOINT PLANES: Angles are measured relative to the core axis

WATER PRESSURE TEST

PRESSURE TYPE

SURFACE LINE

VERTICAL SCALE

Figures given are gauge pressure.

Test sections are indicated graphically on diagram

PHOTOGRAPH REFERENCE: 27515M

BLACK AND WHITE

COLOUR

ROCK TYPE & DEGREE OF WEATHERING	DESCRIPTION LITHOLOGY, COLOUR, STRENGTH, HARDNESS, ETC.	GRAPHIC LOG	DEPTH & SIZE OF CORE	FRAC- TURE LOG	UNIT & % CORE RECOVERY	STRUCTURES JOINTS, VEIN, SEAMS, FOLDS, CRUSHED ZONES	WATER PRESSURE TEST Loss in gallons per minute over 100'
AGGLOMERATE Moderately to Highly Weathered	Purple-brown, dark grey in patches. Soft to moderately soft, friable Weak. Pieces $\frac{1}{4}$ "-5", made $\frac{1}{2}$ ".		90 100 110 120 130 140 147' 4"		From 90' core is badly broken due to failure of rotten matrix during drifting. Continues to 147'.		510
AGGLOMERATE Fresh to Slightly Weathered	Fine-grained. Light grey. Moderately hard, Moderately strong. Pieces $\frac{1}{2}$ "-12", made 1".		150 160 167' 6"		Moderately broken zone 151' 3" - 161' 6" 45° joint 153' 1" Slightly broken zone along joint parallel to core axis 156' 10" - 159' 9" Slightly broken zone 160' 5" - 160' 7".		
AGGLOMERATE Moderately to Highly Weathered	Volcanic fragments light grey, matrix yellow & brown Soft, friable, weak. Pieces $\frac{1}{4}$ "-10", made 3".		170 180 190 END OF HOLE 203 FEET		Moderately broken zones 167' 3" - 168' 5", 172' 1" - 175' Remainder of core although largely intact is weak and can be readily broken.		

DRILL TYPE: *Mindrii B1000*
REEL: *Hydraulic*
CORE BARREL TYPE: *N.M.L.C.*
Triph Tube
DRILLER: *T. Cander C.W.*
COMMENCED: *15-6-66*
COMPLETED: *8-66*
LOGGED BY: *J.R. Read*
VERTICAL SCALE: *1 inch = 100 ft.*

NOTES
FRACTURE LOG - Number of fractures per foot of core. Zones of core with no fractures in
BEDDING AND JOINT PLANES - Angles are measured relative to horizontal in the core box.

WATER PRESSURE TESTS
HIGHER TYPE: *M Mechanical*
SUPPLY LINE: *AX Casing*
VERTICAL SCALE: *1 inch = 200 p.s.i.*
Figures given are gauge pressure.
Test sections are indicated graphically to nearest 100 ft.
PHOTOGRAPH REFERENCE SYSTEM
BLACK AND WHITE
COLOUR

APPENDIX 3

Water Pressure Test Computation Sheets

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

WD 1 Sheet 1

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION SUPPLY LINE (p.s.i.)	LOSSES PACKER (p.s.i.)	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)											
Hole No. WD.1 Co-ordinates E+23, 353 NE (C.D.W. Survey Grid) R.L. 320 feet Angle from horizontal -70°																	
Packer:- N Hydraulic Supply line:- AX Casing Water Supply:- Coventry Climax pump Bearing 178° magnetic																	
29.6.65	67'	77'	5	10	18560.0	18566.3	6.3	1.26	10	62	64'6"	26.9	0	0	37	0.16	140
			5	10	18566.3	18574.0	7.7	1.54			AX						
			5	10	18574.0	18582.9	8.9	1.78			Casing						
			5	10	18582.9	18591.8	8.9	1.78									
			5	10	18591.8	18600.6	8.8	1.76									
			5	16	18624.0	18637.5	13.5	2.70					0	0	43	0.27	200
			5	16	18637.5	18650.8	13.3	2.66									
			5	16	18650.8	18663.9	13.1	2.62									
			5	25	18700.0	18725.0	25.0	5.00					0	0	52	0.50	300
			5	25	18725.0	18750.4	25.4	5.08									
			5	25	18750.4	18775.4	25.0	5.00									
			5	30	18810.0	18838.1	28.1	5.62					0	0	57	0.56	300
			5	30	18838.1	18865.7	27.6	5.52									
			5	30	18865.7	18910.0	27.7	5.54									
			5	25	18910.0	18933.5	23.5	4.70					0	0	52	0.47	350
			5	25	18933.5	18970.0	23.2	4.64									
			5	16	18970.0	18983.5	13.5	2.70					0	0	43	0.27	200
			5	16	18983.5	19005.0	13.2	2.64									
			5	10	19005.0	19014.1	9.1	1.82					0	0	37	0.18	150
			5	10	19014.1	19023.1	9.0	1.80									
8.7.65	77'	90'	5	15	200	345	145	29.0	13	83'	74'6"	36	1.2	15	35	2.46	2000
			5	15	345	505	160	32.0			AX						
			5	15	505	675	170	34.0			Casing						
			5	15	675	845	170	34.0									
14.7.65	89'	100'	5	10	500	623	123	24.6	11	88'	86'6"	38.2	0.7	7.4	40	2.05	1700
			5	10	623	738	115	23.0			AX						
			5	10	738	845	107	21.4			Casing						
			5	10	845	953	108	21.6									
			5	15	0	113	113	22.6					0.7	7.4	45	2.05	1500
			5	15	113	226	113	22.6									
			5	15	226	400	113	22.6									
			5	25	400	550	150	30.0					1.1	12	50	2.64	1500
			5	25	550	690	140	28.0									
21.7.65	94'	110'	5	20	19120.0	19135.4	15.4	3.08	16	86'	91'6"	37.3	0	0	57	0.19	110
			5	20	19135.4	19150.8	15.4	3.08			AX						
			5	20	19150.8	19166.1	15.3	3.06			Casing						
			5	20	19166.1	19181.4	15.3	3.06									
			5	30	19200.0	19215.7	15.7	3.14					0	0	67	0.19	90
			5	30	19215.7	19231.2	15.5	3.10									
			5	30	19231.2	19246.6	15.4	3.08									
			5	30	19246.6	19262.7	15.5	3.10									
			5	40	19290.0	19305.5	15.5	3.10					0	0	77	0.19	80
			5	40	19305.5	19321.0	15.5	3.10									
			5	40	19321.0	19351.7	15.3	3.06									
			5	40	19336.3	19370.0	15.4	3.04									
			5	50	19370.0	19386.2	16.2	3.24					0	0	87	0.20	75
			5	50	19386.2	19402.1	15.9	3.18									
			5	50	19402.1	19418.0	15.9	3.18									
			5	50	19418.0	19433.9	15.9	3.18									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

WD1 Sheet 2

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)											
Hole No WD1 (Cont.)																	
21.7.65	94'	110'	5	40	19450.0	19465.3	15.3	3.06	16	86'	4 1/6"	37.3	0	0	77	0.19	80
			5	40	19465.3	19480.7	15.4	3.08					AX				
			5	30	19490.0	19504.8	14.8	2.96					Casing				
			5	30	19504.8	19519.7	14.9	2.98					0	0	67	0.19	90
			5	30	19519.7	19534.4	14.7	2.94									
			5	20	19545.0	19559.8	14.8	2.96					0	0	57	0.19	110
			5	20	19559.8	19574.2	14.4	2.88									
5	20	19574.2	19588.8	14.6	2.92												
22.7.65	103' 6"	120'	5	20	19635.0	650.1	15.1	3.02	16.6	90'	10 1/4"	39	0	0	59	0.18	90
			5	20	650.1	664.8	14.7	2.94					AX				
			5	20	664.8	679.5	14.7	2.94					Casing				
			5	20	679.5	694.5	14.7	2.94									
			5	35	710.0	724.4	14.4	2.88					0	0	74	0.17	70
			5	35	724.4	738.7	14.3	2.86									
			5	35	738.7	752.3	13.6	2.72									
			5	35	752.3	766.4	14.1	2.82									
			5	35	766.4	780.2	13.8	2.76									
			5	45	800.0	814.1	14.1	2.82					0	0	84	0.17	65
			5	45	814.1	828.4	14.3	2.86									
			5	45	828.4	842.8	14.4	2.88									
			5	45	842.8	857.1	14.3	2.86									
			5	55	880.0	895.8	15.8	3.16					0	0	94	0.19	65
			5	55	895.8	911.7	15.9	3.18									
			5	55	911.7	927.7	16.0	3.20									
			5	55	927.7	943.6	15.9	3.18									
			5	45	955.0	969.8	14.8	2.96					0	0	84	0.18	65
			5	45	969.8	984.4	14.6	2.92									
			5	45	984.4	999.0	14.6	2.92									
			5	35	20010.0	23.8	13.8	2.76					0	0	74	0.17	70
			5	35	23.8	37.5	13.7	2.74									
			5	20	50.0	62.8	12.8	2.56									
			5	20	62.8	75.4	12.6	2.52					0	0	59	0.15	65
			5	20	75.4	87.9	12.5	2.50									
9.8.65	109' 6"	130'	5	25	20160.0	20198.3	38.3	7.66	20.5	102	10 7/8"	44.3	0	0	69	0.38	160
			5	25	198.3	235.1	36.8	7.36					AX				
			5	25	235.1	272.5	37.4	7.48					Casing				
			5	25	272.5	399.7	42.2	8.44									
			5	35	390.0	441.5	51.5	10.30					0	18	74	0.50	200
			5	35	441.5	493.0	51.5	10.30									
			5	35	493.0	545.0	52.0	11.40									
			5	45	600.0	667.3	67.3	13.46					0.22	2.2	77	0.56	200
			5	45	667.3	714.3	47.0	9.40									
			5	45	714.3	771.3	57.0	11.41									
			5	45	771.3	828.5	57.2	11.44									
			5	45	828.5	886.8	58.3	11.66									
			5	55	970.0	21033.8	63.8	12.76					0.27	2.6	76	0.63	200
			5	55	21033.8	1097.7	63.9	12.78									
			5	55	1097.7	162.5	64.8	12.96									
			5	45	200.0	260.5	60.5	12.10					0.24	2.4	77	0.59	200
			5	45	260.5	320.7	60.2	12.04									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

W.D 1 Sheet 3

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)							Permeability ft/yr				
Hole No W.D. / (cont.)																	
9.8.65.	109'6"	130'	5	35	360.0	416.7	56.7	13.34	20.5	102'	107'	44.3	0.21	2.1	77	0.55	200
			5	35	416.7	473.0	56.3	11.26									
			5	35	473.0	529.3	56.3	11.26									
			5	25	560.0	610.0	50.0	10.0					0	1.7	68	0.49	200
			5	25	610.0	660.0	50.0	10.0									
			5	25	660.0	709.8	49.8	9.96									
23.8.65	130'6"	145'	5	25	650	698	48	9.6	14.5	124'	128'	53.8	0	1.5	77	0.66	250
			5	25	698	744	46	9.2									
			5	25	744	792	48	9.6									
			5	40	850	908	58	11.6									
			5	40	908	966	58	11.6									
			5	40	966	1023	57	11.4					0.6	4.8	103	1.17	350
			5	55	1050	1133	83	16.6									
			5	55	1133	1222	89	17.8									
			5	55	1222	1305	83	16.6					0.9	6.6	111	1.47	400
			5	65	1400	1505	105	21.0									
			5	65	1505	1610	105	21.0									
			5	65	1610	1720	110	22.0					0.7	5.2	103	1.28	400
			5	55	1800	1892	92	18.4									
			5	55	1892	1985	93	18.6									
			5	55	1985	2088	93	18.6					0.4	3.1	90	1.01	350
			5	40	2150	2225	75	15.0									
			5	40	2225	2300	75	15.0									
			5	40	2300	2370	70	14.0					0	1.8	77	0.72	300
			5	25	2400	2455	55	11.0									
			5	25	2455	2505	50	10.0									
			5	25	2505	2558	53	10.6									
25.8.64	145'	159'2"	5	25	21960.0	21975.7	15.7	3.14	14.2	119'	142'6"	51.6	0	0	77	0.22	90
			5	25	21975.7	21991.4	15.7	3.14									
			5	25	21991.4	22007.2	15.8	3.16									
			5	45	22007.2	22044.7	14.7	2.94									
			5	45	22044.7	22059.1	14.4	2.88									
			5	45	22059.1	22073.7	14.6	2.92					0	0	107	0.19	60
			5	55	22073.7	22108.9	13.9	2.78									
			5	55	22108.9	22122.6	13.7	2.74									
			5	55	22122.6	22136.3	13.7	2.74					0	0	122	0.19	50
			5	70	22136.3	22163.8	13.8	2.76									
			5	70	22163.8	22177.8	14.0	2.80									
			5	70	22177.8	22191.7	13.9	2.78					0	0	107	0.19	60
			5	55	22191.7	22213.4	13.4	2.68									
			5	55	22213.4	22226.7	13.4	2.68									
			5	55	22226.7	22240.3	13.5	2.70					0	0	97	0.20	65
			5	45	22240.3	22264.1	14.1	2.82									
			5	45	22264.1	22278.2	14.1	2.82									
			5	45	22278.2	22292.3	14.1	2.82					0	0	77	0.22	90
			5	25	22292.3	22321.1	16.1	3.22									
			5	25	22321.1	22336.9	15.8	3.16									
			5	25	22336.9	22352.8	15.9	3.18									

WARANGOI HYDRO ELECTRIC

WD1 Sheet 4

WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION LOSSES		EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS	
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)												
Hole No WD.1 (cont.)																		
26.8.65	158'6"	169'2"	5	25	22400.0	416.5	16.5	3.3	10.6	138'	156'	59.9	0	0	85	0.31	110	
			5	25	416.5	433.6	17.1	3.42										
			5	25	433.6	449.5	15.9	3.18										Ax Casing
			5	25	449.5	465.9	16.4	3.28										
			5	45	490.0	505.3	15.3	3.06										
			5	45	505.3	520.3	15.0	3.00										
			5	45	520.3	535.2	14.9	2.98										
			5	60	580.0	595.4	15.4	3.08										
			5	60	595.4	610.7	15.3	3.06										
			5	60	610.7	627.6	16.9	3.38										
			5	60	627.6	644.3	16.7	3.34										
			5	75	665.0	682.5	17.5	3.50										
			5	75	682.5	700.0	17.5	3.50										
			5	75	700.0	717.3	17.3	3.46										
			5	60	730.0	747.1	17.1	3.42										
			5	60	747.1	764.0	16.0	3.20										
			5	60	764.0	781.0	17.0	3.40										
			5	45	790.0	806.6	16.6	3.32										
			5	45	806.6	823.4	16.8	3.36										
			5	25	835.0	851.4	16.4	3.28										
5	25	851.4	867.6	16.2	3.24													
5	25	867.6	883.8	16.2	3.24													
1.9.65	169'	179'6"	5	25	22900.0	908.3	8.3	1.66	10.5	164'	166'6"	71'2"	0	0	96	0.15	50	
			5	25	908.3	916.2	7.9	1.58										
			5	25	916.2	924.1	7.9	1.58										Ax Casing
			5	25	924.1	932.0	7.9	1.58										
			5	50	950.0	964.8	14.8	3.96										
			5	50	964.8	979.3	14.5	3.90										
			5	50	979.3	991.1	11.8	2.36										
			5	50	991.1	23002.3	11.2	2.24										
			5	50	002.3	013.0	10.7	2.14										
			5	65	030.0	041.4	11.4	2.28										
			5	65	041.4	052.8	11.4	2.28										
			5	65	052.8	064.5	11.7	2.34										
			5	65	064.5	075.8	11.3	2.26										
			5	80	090.0	102.2	12.2	2.44										
			5	80	102.2	114.1	11.9	2.38										
			5	80	114.1	126.0	11.9	2.38										
			5	80	126.0	138.0	12.0	2.40										
			5	65	145.0	155.6	10.6	2.12										
			5	65	155.6	166.2	10.6	2.12										
			5	50	170.0	179.2	9.2	1.84										
			5	50	179.2	188.5	9.3	1.86										
			5	50	188.5	197.7	9.2	1.84										
			5	25	202.0	209.1	7.1	1.42										
			5	25	209.1	215.9	6.8	1.36										
			5	25	215.9	222.8	6.9	1.38										

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

WD1 Sheet 5

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS							
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)																		
Hole No. W.D. (cont.)																								
2.9.65	179'	192'6"	5	25	23240.0	256.0	16.0	3.20	13.5	168'	176' 4x Casing	72.4	0	0	98	0.24	80							
			5	25	256.0	271.9	15.9	3.18																
			5	25	271.9	287.7	15.8	3.16																
			5	50	310.0	330.6	20.6	4.12					0	0	123	0.30	80							
			5	50	330.6	350.8	20.2	4.04																
			5	50	350.8	370.9	20.1	4.02																
			5	75	390.0	417.5	27.5	5.50					0	0	148	0.41	90							
			5	75	417.5	445.3	27.8	5.56																
			5	75	445.3	473.0	27.7	5.54																
			5	85	500.0	530.1	30.1	6.02					0	0	158	0.44	100							
			5	85	530.1	559.8	29.7	5.94																
			5	85	559.8	589.8	30.0	6.00																
			5	75	610.0	638.5	28.5	5.70					0	0	148	0.43	90							
			5	75	638.5	667.3	28.8	5.76																
			5	75	667.3	696.1	28.8	5.76																
			5	50	710.0	733.0	23.0	4.60					0	0	123	0.34	80							
			5	50	733.0	755.5	22.5	4.50																
			5	50	755.5	779.9	22.4	4.48																
			5	25	785.0	803.3	18.3	3.66					0	0	98	0.27	90							
			5	25	803.3	821.4	18.1	3.62																
			5	25	821.4	839.4	18.0	3.60																
7.9.65	192'6"	202'2"	5	30	23870.0	886.2	16.2	3.24	9.6	179'	189'6" 4x Casing	77.7	0	0	108	0.34	90							
			5	30	886.2	902.3	16.1	3.22																
			5	30	902.3	918.3	16.0	3.20																
			5	55	940.0	958.5	18.5	3.70					0	0	133	0.39	90							
			5	55	958.5	977.0	18.5	3.70																
			5	55	977.0	995.5	18.5	3.70																
			5	75	24010.0	032.3	22.3	4.46																
			5	75	032.3	054.7	22.4	4.48					0	0	153	0.47	90							
			5	75	054.7	077.4	22.7	4.54																
			5	75	077.4	100.1	22.7	4.54																
			5	95	135.0	160.5	25.5	5.10					0	0	173	0.53	90							
			5	95	160.5	185.9	25.4	5.08																
			5	95	185.9	211.4	25.5	5.10																
			5	75	220.0	243.2	23.2	4.64					0	0	153	0.48	90							
			5	75	243.2	266.3	23.1	4.62																
			5	55	275.0	295.6	20.6	4.12					0	0	133	0.43	100							
			5	55	295.6	316.1	20.5	4.10																
			5	30	330.0	347.8	17.8	3.56					0	0	108	0.37	90							
			5	30	347.8	365.6	17.8	3.56																
			30.9.65	213'6"	232'6"	5	30	24375.0					377.8	2.8	0.56	19	199'	211' 4x Casing	86.3	0	0	116	0.029	8
						5	30	377.8					380.6	2.8	0.56					B Hydraulic Packer				
5	30	380.6				383.2	2.6	0.52																
5	65	395.0				398.6	3.6	0.72	0	0	151	0.038	8											
5	65	398.6				402.0	3.4	0.68																
5	65	402.0				405.8	3.8	0.76																
5	90	410.0				412.4	2.4	0.84	0	0	176	0.026	5											
5	90	412.4				414.8	2.4	0.84																
5	90	414.8				417.3	2.5	0.50																
5	110	418.6				421.3	2.7	0.54	0	0	196	0.028	5											
5	110	421.3				424.0	2.7	0.54																
5	110	424.0				426.6	2.6	0.52																

WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS	
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)												
Hole No W.D. 1 (cont.)																		
30.9.65	213' 6"	232' 6"	5	90	427.0	428.5	1.5	0.30	19	199'	211'	86.3	0	0	176	0.016	3	
			5	90	428.5	430.0	1.5	0.30					Ax					
			5	65	430.0	430.5	0.5	0.10					Casing	0	0	151	0.005	1
			5	65	430.5	431.0	0.5	0.10						0	0	116	0.003	<1
			5	30	430.1	430.4	0.3	0.06										
			5	30	430.4	430.7	0.3	0.06										
16.10.65	232'	248'	5	30	24450.0	24453.1	3.1	0.62	16	207'	229' 6"	89.8	0	0	120	0.039	10	
			5	30	453.1	456.1	3.0	0.60					Ax					B Hydraulic Packer
			5	30	456.1	459.2	3.2	0.64					Casing					
			5	65	470.0	474.2	4.2	0.84					0	0	155	0.053	11	
			5	65	474.2	478.5	4.3	0.86										
			5	65	478.5	482.7	4.2	0.84										
			5	90	490.0	494.5	4.5	0.90										
			5	90	494.5	498.9	4.4	0.88					0	0	180	0.054	9	
			5	90	508.9	503.1	4.2	0.84										
			5	115	510.0	514.7	4.7	0.94										
			5	115	514.7	519.2	4.5	0.90					0	0	205	0.056	9	
			5	115	519.2	523.6	4.4	0.88										
			5	90	530.0	532.2	2.2	0.44					0	0	180	0.027	5	
			5	90	532.2	534.4	2.2	0.44										
			5	65	536.0	537.8	1.8	0.36					0	0	155	0.022	5	
			5	65	537.8	539.5	1.7	0.34										
			5	30	541.0	541.8	0.8	0.16					0	0	90	0.010	4	
			5	30	541.8	542.6	0.8	0.16										
23.10.65	248' 6"	263'	2:18	30	150	200	50	21.72	14.5	212'	246'	92	2.0	40	80	1.57	600	
			2:05	30	200	250	50	24.00					Ax				B Mechanical Packer	
			2:12	30	250	300	50	22.74					Casing					
			1:35	70	400	450	50	31.56					4.1	68	90	2.26	800	
			1:30	70	450	500	50	33.30										
			1:30	70	500	550	50	33.30										
			1:20	95	600	650	50	37.50					56	88	93	2.69	900	
			1:18	95	650	700	50	38.46										
			1:13	95	700	750	50	41.10										
			1:1	120	850	900	50	49.18					7.8	120	84	3.18	1200	
			1:6	120	900	950	50	45.48										
			1:9	120	950	1000	50	43.50										
			1:8	95	050	100	50	44.16					6.5	97	84	2.89	1000	
			1:14	95	100	150	50	40.56										
			1:13	95	150	200	50	41.10										
			1:23	70	250	300	50	36.30					5.5	82	75	2.60	1100	
			1:19	70	300	350	50	37.98										
			1:17	70	350	400	50	38.94										
			1:38	30	450	500	50	30.60					3.5	60	59	2.07	1100	
			1:41	30	500	550	50	29.70										
			1:41	30	550	600	50	29.70										
2.11.65	279' 6"	300	5	35	610.0	613.7	3.7	0.74	10.5	203	278.5	88.2	0	0	123	0.067	18	
			5	35	613.7	617.2	3.5	0.70					0.70				B Mechanical Packer	
			5	35	617.2	620.5	3.3	0.66										
			5	100	635.0	647.2	12.2	2.44					2.48	0	16	187	0.236	40
			5	100	647.2	659.9	12.7	2.54										
			5	100	659.9	672.2	12.3	2.46										

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS			
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)														
Drill Hole WD1 Sheet 7.																				
2.11.65	279'6"	300	5	120	680.0	702.0	22.0	4.40	7.41				0	8.3	200	0.705	110			
			5	120	702.0	727.9	25.9	5.18												
			5	120	785.0	830.6	45.6	9.12												
			4.34	120	870.0	920	50	10.95												
			4.35	100	920	970	50	10.90	10.95		0	14	174	1.04	190					
			4.37	100	970	20	50	10.85												
			4.31	100	20	70	50	11.10												
			5	35	935.0	959.7	22.7	4.54	4.49		0	4	119	0.428	110					
			5	35	957.7	980.2	22.5	4.50												
			5	35	980.2	002.4	22.2	4.44												
			13.11.65	299	320	2.13	40	200	250	50	22.6	21	213	297	925	2.5	40	90	1.07	400
						2.14	40	250	300	50	22.4	22.5		AX						B Mechanical Packer
						2.02	40	300	350	50	24.6			Casing						
						1.27	100	450	500	50	34.5	33.5				5.3	69	118	1.59	400
						1.32	100	500	550	50	32.6									
			1.30	100	550	600	50	33.3												
			1.16	120	680	730	50	39.4	38.4				6.8	87	119	1.82	500			
			1.20	120	730	780	50	37.5												
			1.18	120	780	830	50	38.4												
			1.27	100	80	130	50	34.5	35.0				5.6	72	115	1.66	450			
			1.24	100	130	180	50	35.7												
			1.26	100	180	230	50	34.9												
			2.14	40	310	360	50	22.4	22.4				2.5	40	90	1.06	400			
			2.12	40	360	410	50	22.7												
			2.15	40	410	460	50	22.2												
			17.11.65	319	340	2.31	40	400	450	50	19.9	21	213	317	925	2.0	34	97	0.92	300
						2.37	40	450	500	50	19.1	19.3		AX						B Mechanical Packer
						2.40	40	500	550	50	18.8			Casing						
						1.51	90	600	650	50	27.0	26.8				3.6	51	128	1.23	300
						1.52	90	650	700	50	26.8									
			1.53	90	700	750	50	26.6												
			1.25	110	800	850	50	35.3	31.6				5.1	65	132	1.50	300			
			1.42	110	850	900	50	29.4												
			1.42	110	900	950	50	29.4												
			1.32	110	950	00	50	32.6												
			1.36	110	00	50	50	31.2												
			1.30	125	100	150	50	33.3	32.1				5.4	66	146	1.53	350			
			1.36	125	150	200	50	31.2												
			1.34	125	200	250	50	31.9												
			1.43	110	300	350	50	29.1	30.2				4.8	61	137	1.44	350			
			1.37	110	350	400	50	30.9												
			1.38	110	400	450	50	30.6												
			1.47	90	500	550	50	28.0	28.1				4.1	55	123	1.34	350			
			1.46	90	550	600	50	28.3												
			1.47	90	600	650	50	28.0												
			2.15	40	680	730	50	22.2	21			925	1.6	27	104	0.83	250			
			2.54	40	730	780	50	17.2	17.4											
			3.13	40	880	830	50	15.5												
			3.25	40	930	970	50	14.6												

B56/A2/60-51.

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)											
Hole No. WD 2			Co-ordinates I. 34, 317 NE (C.D.W. Grid)						R.L. 361 feet.		Angle from horizontal -90°						
Packer :- N Hydraulic & Mechanical			Supply line & AX Casing						Water Supply :-		Counting		Climax		Pump		
11.12.65	80	90	1.20	20	450	500	50	37.5	10	NIL	77'	34.7	1.7	19	35	3.78	3000
			1.21	20	500	550	50	37.0	37.8		AX Casing						
			1.17	20	550	600	50	39.0									
			1.22	30	650	700	50	36.6	28.1				1.0	11	43	2.81	2000
			1.48	30	700	750	50	27.8									
			1.59	30	750	800	50	25.2									
			1.56	30	800	850	50	25.9									
			2.00	30	850	900	50	25.0									
			1.52	35	950	1000	50	26.8	26.6				0.9	9.6	59	2.66	1500
			1.53	35	1000	050	50	26.5									
			1.53	35	050	100	50	26.5									
			1.54	40	150	200	50	26.3	26.8				0.9	9.6	64	2.68	1500
			1.51	40	200	250	50	27.0									
			1.51	40	250	300	50	27.0									
			2.10	35	400	450	50	23.1	24.2				0.7	8.5	61	2.42	1300
			2.8	35	450	500	50	23.5									
			2.00	35	500	550	50	25.0									
			1.59	35	550	600	50	25.2									
			2.00	30	650	700	50	25.0	24.8				0.7	8.8	55	2.48	1400
			1.59	30	700	750	50	25.2									
			2.04	30	750	800	50	24.2									
			2.25	20	900	950	50	20.7	21.8				0.5	6.4	48	2.18	1400
			2.20	20	950	1000	50	21.4									
			2.27	20	1000	050	50	20.4									
14.12.65	90	100	1.02	20	200	250	50	48.4	10	NIL	875'	39.1	2.7	27	29	4.58	5000
			1.06	20	250	300	50	45.5	45.8		AX Casing						
			1.09	20	300	350	50	43.4									
			1.00	30	450	500	50	50.0	51.8				3.4	34	32	5.18	5000
			0.55	30	500	550	50	54.5									
			0.59	30	600	650	50	50.8									
			0.52	35	680	730	50	57.7	51.6				3.9	34	32	5.16	5000
			0.54	35	730	780	50	55.5									
			0.56	35	780	830	50	53.5									
			0.58	20	900	950	50	51.7	47.8				3.0	30	22	4.78	7000
			1.03	20	950	1000	50	47.6									
			1.08	20	1000	050	50	44.1									
			0.56	15	080	130	50	53.5	46.4				2.9	28	23	4.64	6500
			1.11	15	130	180	50	42.2									
			1.09	15	180	230	50	43.4									
20.12.65	98.5	110	0.48	20	520	570	50	62.4	11.5	NIL	97'	42.7	6.5	55	1	5.80	7100,000
			0.43	20	600	650	50	69.6	66.6		AX Casing						
			0.44	20	650	700	50	68.2									
			0.41	30	770	820	50	73.2	79.4				9.0	74	10	6.90	
			0.35	30	820	870	50	85.8									
			0.38	30	870	920	50	79.2									
			0.35	35	980	1030	50	85.8	82.7				9.8	79	11	7.20	
			0.38	35	1040	1090	50	79.2									
			0.36	35	1090	1140	50	83.4									
			0.42	40	1230	1280	50	71.4	75.6				8.2	68	7	6.59	30,000
			0.39	40	1280	1330	50	76.8									
			0.38	40	1330	1380	50	79.2									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION LOSSES		EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)							SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)			
WD 2 (cont.) Sheet 2.																	
20-12-65	985	110	0.46	35	1460	1510	50	65.4	11.5	NIL	97'	42.7	7.6	61	9	6.24	22000
			0.39	35	1510	1560	50	76.8	71.5		AX						
			0.41	35	1600	1650	50	73.2			Casing						
			0.41	30	1750	1800	50	73.2	74.9				8.2	67	2	6.54	
			0.38	30	1800	1850	50	79.2									
			0.41	30	1850	1900	50	73.2									
			0.44	20	2000	2050	50	68.2	71.2				7.4	61	6	6.22	
			0.42	20	2050	2100	50	71.4									
			0.40	20	2100	2150	50	75.0									
21-12-65	110	120	0.47	25	300	350	50	63.6	10	NIL	107'	47.7	6.2	60	7	6.48	30,000
			0.46	25	350	400	50	65.4	64.8		AX						N Mechanical Packer
			0.46	25	400	450	50	65.4			Casing						
			0.42	35	540	590	50	71.4	73.2				7.7	78	3	7.32	
			0.41	35	590	640	50	73.2									
			0.40	35	640	690	50	75.0									
			0.41	50	850	900	50	73.2	77.8				8.6	90	1	7.78	
			0.38	50	900	950	50	79.2									
			0.37	50	950	1000	50	81.0									
			0.36	60	1140	1190	50	83.4	83.0				10.0	105	7	8.30	
			0.35	60	1190	1240	50	85.8									
			0.35	60	1240	1290	50	85.8									
			0.37	50	1410	1460	50	81.0	80.4				9.3	100	12	8.04	
			0.37	50	1460	1510	50	81.0									
			0.38	50	1510	1560	50	79.2									
			0.41	35	1700	1750	50	73.2	73.5				7.7	78	3	7.35	
			0.41	35	1750	1800	50	73.2									
			0.40	35	1800	1850	50	75.0									
0.45	20	1930	1980	50	66.6	67.3				6.6	64	3	6.73				
0.44	20	1980	2030	50	68.2												
0.45	20	2030	2080	50	66.6												
22-12-65	120	130	0.52	25	180	230	50	57.6	10	NIL	119'	52.1	6.4	50	21	6.00	9000
			0.48	25	230	280	50	62.4	60.0		AX						N Mechanical Packer
			0.50	25	280	330	50	60.0			Casing						
			0.47	35	400	450	50	63.6	61.2				6.6	53	28	6.12	6500
			0.51	35	450	500	50	58.8									
			0.49	35	500	550	50	61.2									
			0.46	45	580	630	50	65.4	67.7				8.1	65	24	6.77	9000
			0.43	45	630	680	50	69.6									
			0.44	45	680	730	50	68.2									
			0.37	50	830	880	50	81.0	79.8				11.1	98	7	7.98	
			0.38	50	880	930	50	79.2									
			0.38	50	930	980	50	79.2									
			0.44	45	210	260	50	68.2	64.1				7.3	58	32	6.41	6000
			0.46	45	260	310	50	65.4									
			0.51	45	310	360	50	58.8									
			0.55	25	450	500	50	54.6	55.4				5.5	42	30	5.54	6000
			0.54	25	500	550	50	55.8									
			0.54	25	550	600	50	55.8									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO-ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION LOSSES		EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)							SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)			
23.12.65	130	140	5.22	20	700	750	50	8.5	10	NIL	129'	56.4	0	0.9	76	1.00	400
			4.54	20	750	800	50	10.2	10.0		AX						N Mechanical Packer
			4.42	20	800	850	50	10.6			Casing						
			4.38	20	850	900	50	10.7									
			20.57	35	950	1050	50	16.9	16.4				0.6	2.6	88	1.64	600
			3.03	35	1000	1050	50	16.4									
			3.07	35	1050	1100	50	16.0									
			2.10	50	150	200	50	23.0	23.5				1.2	5.9	99	2.35	750
			2.06	50	200	250	50	23.8									
			2.06	50	250	300	50	23.8									
			1.35	60	350	400	50	31.6	32.4				2.2	12.5	102	3.24	1000
			1.31	60	400	450	50	32.9									
			1.32	60	450	500	50	32.6									
			1.45	50	550	600	50	28.6	29.3				1.8	10	95	2.93	900
			1.41	50	600	650	50	29.7									
			1.41	50	650	700	50	29.7									
			1.55	35	750	800	50	26.1	26.1				1.4	7.5	83	2.61	1000
			1.55	35	800	850	50	26.1									
			1.57	35	850	900	50	26.0									
			2.10	20	950	1000	50	23.0	21.7				0.9	4.9	71	2.17	900
			2.23	20	1000	1050	50	20.9									
			2.22	20	1050	1100	50	21.1									
27.12.65	140	150	1.19	20	200	250	50	37.9	10	NIL	137.5'	60.8	3.4	19.5	58	4.00	2200
			1.10	20	250	300	50	42.8	40.0		AX						N Mechanical Packer
			1.16	20	300	350	50	39.4			Casing						
			1.05	35	450	500	50	46.1	45.9				4.5	27	64	4.59	23000
			1.05	35	500	550	50	46.1									
			1.06	35	550	600	50	45.4									
			0.51	50	660	710	50	38.8	59.6				7.4	49	54	5.96	3500
			0.50	50	710	760	50	60.0									
			0.50	50	760	810	50	60.0									
			0.52	60	900	950	50	57.6	65.6				8.5	61	51	6.56	4000
			0.44	60	950	1000	50	68.2									
			0.44	60	1000	1050	50	68.2									
			0.44	60	1050	1100	50	68.2									
			0.50	50	630	680	50	60.0	60.4				7.4	52	51	6.04	3500
			0.50	50	680	730	50	60.0									
			0.49	50	730	780	50	61.2									
			0.56	35	850	900	50	53.5	53.1				5.9	36	54	5.31	3000
			1.00	35	900	950	50	50.0									
			0.54	35	950	1000	50	55.8									
			1.10	20	100	150	50	42.8	44.1				4.1	25	52	4.41	2500
			1.09	20	150	200	50	43.4									
			1.05	20	200	250	50	46.1									
30.12.65	150	160	1.00	25	330	380	50	50.0	10	NIL	147.5'	65.1	5.7	35	49	5.11	3000
			0.58	25	380	430	50	51.7	51.1		AX						
			0.58	25	430	480	50	51.7			Casing						
			1.00	35	540	590	50	50.0	51.4				5.7	35	59	5.14	2500
			0.59	35	590	640	50	50.8									
			0.56	35	640	690	50	53.5									
			0.55	50	800	850	50	54.6	55.2				6.8	42	66	5.52	2500
			0.54	50	850	900	50	55.5									
			0.54	50	900	950	50	55.5									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION LOSSES		EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)							SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)			
WD 2 (cont) Sheet 4																	
30.12.65	150	160	0.42	70	1030	1080	50	71.4	10	NIL	1475'	65.1	12.6	89	34	7.72	7000
			0.37	70	1080	1130	50	81.0	77.2		AX						
			0.38	70	1130	1180	50	79.2			Casing						
			0.45	50	300	350	50	66.6	66.7				9.6	63	43	6.67	5000
			0.46	50	350	400	50	65.4									
			0.44	50	400	450	50	68.2									
			1.03	35	600	650	50	47.6	47.1				5.0	29	66	4.71	2200
			1.05	35	650	700	50	46.1									
			1.03	35	700	750	50	47.6									
			1.00	25	870	920	50	50.0	55.6				6.8	42	41	5.56	4500
			0.48	25	920	970	50	62.4									
			0.56	25	970	1020	50	53.5									
			0.55	25	1020	1070	50	54.5									
23.2.66	170	189	0.43	25	080	130	50	69.6	10	NIL	168'	73.8	12.1	71	16	7.02	14000
			0.43	25	130	180	50	69.6	70.2		AX						
			0.42	25	180	230	50	71.4			Casing						
			0.41	50	255	305	50	73.2	75.0				13.8	82	28	7.50	85000
			0.39	50	305	355	50	76.8									
			0.40	50	450	500	50	75.0									
			0.36	75	540	590	50	83.4	83.4				16.8	105	27	8.34	10,000
			0.36	75	590	640	50	83.4									
			0.36	75	640	690	50	83.4									
			0.35	90	780	830	50	85.8	87.4				18.1	118	28	8.74	10,000
			0.34	90	830	880	50	88.2									
			0.34	90	880	930	50	88.2									
			0.37	75	950	1000	50	81.0	83.4				16.8	105	27	8.34	10,000
			0.35	75	1100	1150	50	85.8									
			0.42	50	1170	1220	50	71.4	71.4				12.6	74	37	7.14	6,000
			0.42	50	1220	1270	50	71.4									
			0.45	25	1280	1330	50	66.6	68.1				11.6	66	21	6.81	10,000
			0.43	25	1330	1380	50	69.6									
25.2.66	185	195	0.41	30	1515	1565	50	73.2	10	NIL	182.5'	80.3	12.1	79	17	7.29	13000
			0.42	30	1565	1615	50	71.4	72.9		AX						
			0.41	30	1615	1665	50	73.2			Casing						
			0.37	55	1720	1770	50	81.0	79.0				16.7	93	26	7.90	10,000
			0.38	55	1770	1820	50	79.2									
			0.39	55	1960	2010	50	76.8									
			0.36	75	2040	2090	50	83.4	81.7				17.3	102	36	8.17	7,000
			0.35	75	2090	2140	50	85.8									
			0.35	75	2140	2190	50	85.8									
			0.35	100	2490	2540	50	85.8	86.6				19.7	117	44	8.66	60,000
			0.34	100	2540	2590	50	88.2									
			0.35	100	2590	2640	50	85.8									
			0.37	75	2550	2600	50	81.0	83.3				18.2	108	32	8.33	8,000
			0.35	75	2600	2650	50	85.8									
			0.36	75	2650	2700	50	83.4									
			0.38	55	2795	2845	50	79.2	80.6				16.7	100	19	8.06	14,000
			0.38	55	2845	2895	50	79.2									
			0.36	55	2895	2945	50	83.4									
			0.43	30	3050	3100	50	69.6	72.0				13.8	76	21	7.20	11,000
			0.40	30	3100	3150	50	75.0									
			0.42	30	3150	3200	50	71.4									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICITION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS	
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)												
WD 2 (cont.) Sheet 5																		
26.2.66	195	205	1.25	30	3275	3325	50	35.3	10	NIL	1925	84.6	3.6	13.5	96	3.50	1100	
			1.25	30	3325	3375	50	35.3	35.0		AX						N Mechanical Packer	
			1.27	30	3375	3425	50	34.4			Casing							
			1.07	65	3460	3510	50	44.7	46.4				6.1	28	115	4.64	1200	
			1.03	65	3510	3560	50	47.6										
			1.04	65	3560	3610	50	46.9										
			0.54	90	3690	3740	50	55.5	53.6				8.3	38	128	5.36	1300	
			0.56	90	3740	3790	50	53.5										
			0.58	90	3790	3840	50	51.7										
			0.55	110	3875	3925	50	54.5	56.2				9.2	44	141	5.62	1200	
			0.53	110	4090	4140	50	56.6										
			0.52	110	4140	4190	50	57.6										
			0.57	90	4220	4270	50	52.6	52.3				7.8	37	130	5.23	1300	
			0.58	90	4270	4320	50	51.7										
			0.57	90	4320	4370	50	52.6										
			1.06	65	4440	4490	50	45.5	44.3				5.8	25	119	4.43	1200	
			1.08	65	4490	4540	50	44.1										
			1.09	65	4540	4590	50	43.4										
			1.41	30	4615	4665	50	29.7	29.1				2.7	8.8	103	2.91	900	
			1.44	30	4665	4715	50	28.8										
			1.44	30	4715	4765	50	28.8										
28.2.66	205	215	0.40	30	4830	4880	50	75.0	10	NIL	2025	89	16.4	85	18	7.56	13000	
			0.40	30	4880	4930	50	75.0	75.6		AX						N Mechanical Packer	
			0.39	30	4930	4980	50	76.8			Casing							
			0.38	50	5025	5075	50	79.2	71.8				15.0	72	52	7.18	4500	
			0.45	50	5150	5200	50	66.6										
			0.43	50	5200	5250	50	69.6										
			0.39	75	5370	5420	50	76.8	76.4				16.8	88	59	7.64	4000	
			0.38	75	5420	5470	50	79.2										
			0.41	75	5540	5590	50	73.2										
			0.38	100	5610	5660	50	79.2	80.6				18.8	99	71	8.06	3500	
			0.36	100	5660	5710	50	83.4										
			0.38	100	5710	5760	50	79.2										
			0.42	75	5825	5875	50	71.4	70.0				14.4	70	80	7.00	2500	
			0.40	75	5875	5925	50	75.0										
			0.47	50	5950	6000	50	63.6	64.5				12.2	59	68	6.45	3000	
			0.46	50	6000	6050	50	65.4										
			0.51	30	6140	6190	50	58.8	60.0				10.8	45	63	6.00	3000	
			0.51	30	6190	6240	50	58.8										
			0.48	30	6240	6290	50	62.4										
3.3.66	215	230	0.48	30	6365	6415	50	62.4	15	NIL	213	93.3	11.9	48	63	4.13	2000	
			0.49	30	6415	6465	50	61.2	62.0		AX						N Mechanical Packer	
			0.48	30	6465	6515	50	62.4			Casing							
			0.44	65	6550	6600	50	68.2	70.9				15.3	72	71	4.72	2000	
			0.41	65	6600	6650	50	73.2										
			0.42	65	6780	6830	50	71.4										
			0.40	90	6860	6910	50	75.0	76.3				18.1	88	77	5.08	2000	
			0.39	90	6910	6960	50	76.8										
			0.39	90	6960	7010	50	76.8										
			0.44	60	7240	7290	50	68.2	67.2				14.9	69	69	4.61	1800	
			0.43	60	7290	7340	50	69.6										
			0.43	60	7340	7390	50	69.6										

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICITION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)											
WD 2 (cont.) Sheet 6																	
3.3.66	215	230	0.47	30	7500	7550	50	63.6	15	N/A	213'	93.3	12.6	56	55	4.19	2,400
			0.48	30	7550	7600	50	62.4	63.0		AX						
			0.48	30	7600	7650	50	62.4			Casing						
8.3.66	228	240	0.43	35	7760	7810	50	69.6	12	N/A	225'	99	16.4	55	63	5.59	2,300
			0.41	35	7810	7860	50	73.2	67.1		AX						N Hydraulic Packer
			0.42	35	7860	7910	50	71.4			Casing						
			0.36	50	7940	7990	50	83.4	82.6				22.1	80	47	6.88	5,000
			0.37	50	8075	8125	50	81.0									
			0.36	50	8125	8175	50	83.4									
			0.34	75	8220	8270	50	88.2	87.6				24.3	87	63	7.29	3500
			0.35	75	8385	8435	50	85.8									
			0.34	75	8435	8485	50	88.2									
			0.37	50	8500	8550	50	81.0	80.3				20.7	77	51	6.68	3500
			0.38	50	8550	8600	50	79.2									
			0.39	35	8685	8735	50	76.8	76.8				19.4	70	45	6.40	4500
			0.39	35	8735	8785	50	76.8									
			0.41	25	8800	8850	50	73.2	72.4				17.3	63	44	6.03	4500
			0.42	25	8850	8900	50	71.4									
11.3.66	240	249	1.05	30	9120	9170	50	46.1	9	N/A	237.5'	104.1	7.8	28	98	5.18	1700
			1.05	30	9170	9220	50	46.1	46.7		AX						N Mechanical Packer
			1.03	30	9220	9270	50	47.6			Casing						
			0.58	40	9290	9340	50	51.7	51.6				9.5	35	100	5.74	1,700
			0.59	40	9340	9390	50	50.8									
			0.57	40	9390	9440	50	32.6									
			0.54	60	9510	9560	50	55.5	55.2				10.9	42	111	6.13	1,700
			0.55	60	9560	9610	50	54.5									
			0.54	60	9610	9660	50	55.5									
			0.53	75	9685	9735	50	56.6	57.7				11.6	45	123	6.41	1,600
			0.51	75	9735	9785	50	58.8									
			0.52	75	9785	9835	50	57.7									
			0.53	60	9910	9960	50	56.6	55.6				10.9	47	111	6.18	1,700
			0.55	60	9960	010	50	54.5									
			0.56	50	030	080	50	53.5	52.5				9.9	37	107	5.84	1,700
			0.58	50	080	130	50	51.7									
			1.05	30	150	200	50	46.1	46.5				7.8	28	98	5.17	1,700
			1.04	30	200	250	50	46.9									
2.9	258		5	35	36.0	48.5	12.5	2.5	9	252	245.5'	109.4	0	0	144	0.27	60
			5	35	48.5	60.5	12.0	2.4			AX						N Mechanical Packer
			5	35	60.5	71.5	11.5	2.3			Casing						
			5	50	74.0	88.5	14.5	2.9					0	0	159	0.31	60
			5	50	88.5	102.5	14.0	2.8									
			5	50	102.5	116.5	14.0	2.8									
			5	75	120.0	143.0	23.0	4.6					0	0	184	0.57	100
			5	75	143.0	169.5	26.5	5.3									
			5	75	169.5	196.0	26.5	5.3									
			5	50	200.0	222.0	22.0	4.4					0	0	159	0.48	100
			5	50	222.0	243.5	21.5	4.3									
			5	50	243.5	264.5	21.0	4.2									
			5	35	270.0	289.0	19.0	3.8					0	0	144	0.41	90
			5	35	289.0	307.0	18.0	3.6									
			5	35	307.0	325.5	18.5	3.7									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS			
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)														
Drill Hole WD 3.			Co-ordinates T+30, 265 ft S.W. (C.D.W. Grid).						R.L. 130 ft.		Angle from Horizontal, - 40°.									
Packer, N Mechanical			Supply Line, AX Casing						Water Supply, Coventry Climax Pump						Direction 125° Mag.					
2.5.66	59' 6"	70'	5	20	300	350	50	10	10.5	17	575'	7	0	0	27	0.92	1100			
			5	20	350	400	50	10			AX									
			5	20	400	445	45	9			Casing									
			5	30	445	515	55	11					0	1.0	36	1.01	900			
			5	30	515	570	55	11												
			5	30	570	620	50	10												
			5	40	620	710	60	12					0	1.5	45	1.21	900			
			5	40	710	775	65	13												
			5	40	775	840	65	13												
			5	50	840	960	80	16					0	2.5	55	1.52	900			
			5	50	960	1035	75	15												
			5	50	1035	1200	85	17												
			5	40	1200	215	75	15					0	1.6	45	1.30	900			
			5	40	215	280	65	13												
			5	40	280	340	65	13												
			5	30	340	420	50	10					0	0	37	0.92	800			
			5	30	420	515	45	9												
			5	30	515	565	50	10												
			5	20	565	615	35	7					0	0	27	0.60	700			
			5	20	615	645	30	6												
			5	20	645	675	30	6												
4.5.66	70'	80' 4"	5	20	730	735	15	3	10.3	17	68'	7	0	10	27	0.34	400			
			5	20	735	755	20	4			AX									
			5	20	755	775	20	4			Casing									
			5	20	775	790	15	3												
			5	30	790	825	25	5					0	0	37	0.49	400			
			5	30	825	850	25	5												
			5	30	850	885	25	5												
			5	40	885	1014	34	6.8					0	0	47	0.66	450			
			5	40	1014	1049	34	6.8												
			5	40	1049	1084	34	6.8												
			5	55	1084	1157	47	9.4					0	0	62	0.91	450			
			5	55	1157	1212	47	9.4												
			5	55	1212	1267	47	9.4												
			5	40	1267	1345	35	7					0	0	47	0.68	450			
			5	40	1345	1385	35	7												
			5	40	1385	1425	35	7												
			5	30	1425	1472	22	4.4					0	0	37	0.49	400			
			5	30	1472	1502	27	5.4												
			5	30	1502	1527	22	5.2												
			5	20	1527	1555	15	3					0	0	27	0.36	400			
			5	20	1555	1575	20	4												
			5	20	1575	1595	20	4												
5.5.66	80'	90'	5	20	620	635	15	3	10'	17	77.5'	7	0	0	27	0.30	350			
			5	20	635	650	15	3			AX									
			5	20	650	665	15	3			Casing									
			5	30	665	695	25	5					0	0	37	0.47	400			
			5	30	695	715	20	4												
			5	30	715	740	20	5												

WARANGOI HYDRO ELECTRIC

WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS		
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)							SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)					
Drill Hole WD 3 Sheet 2																			
5-5-66	80	90	5	40	750	785	35	7	10	17	77.5 AX Casing	7	0	0	47	0.70	450		
			5	40	785	820	35	7											
			5	40	820	855	35	7											
			5	55	870	915	45	9							0	0	62	0.70	450
			5	55	915	960	45	9											
			5	55	960	5	45	9											
			5	40	20	55	35	7							0	0	47	0.70	450
			5	40	55	90	35	7											
			5	40	90	125	35	7											
			5	30	165	190	25	5							0	0	37	0.50	400
			5	30	190	215	25	5											
			5	30	215	240	25	5											
			5	20	250	270	20	4							0	0	27	0.37	400
			5	20	270	285	15	3											
			5	20	285	305	20	4											
7-5-66	90	100	5.00	30			49.5	9.90	10	16	87.5 AX Casing	7	0	1.0	36	1.08	900		
			4.21	30			49.5	11.4											
			4.35	30			49.5	10.4											
			4.22	30			49.5	11.4											
			4.00	35			49	12.2							0	1.3	41	1.20	900
			4.03	35			49	12.1											
			4.10	35			49	11.8											
			2.58	50			48	16.2							0	2.6	54	1.61	900
			3.00	50			48	16.0											
			3.00	50			48	16.0											
			2.38	60			47	17.9							0	3.0	64	1.75	850
			2.36	60			47	18.1											
			2.52	60			47	16.4											
			2.59	50			48	16.1							0	2.4	54	1.57	900
			3.05	50			48	15.6											
			3.07	50			48	15.5											
			4.22	35			49	11.2							0	1.1	41	1.14	850
			4.15	35			49	11.5											
			4.13	35			49	11.6											
			4.32	30			50	11.0							0	1.1	36	1.12	1000
			4.29	30			50	11.2											
4.27	30			50	11.3														
10-5-66	100	112	5	20			5.0	1.0	12	16	97.5 AX Casing	7	0	0	27	0.079	95		
			5	20			4.8	0.96											
			5	20			4.4	0.88											
			5	45			5.5	1.10							0	0	52	0.089	55
			5	45			5.5	1.10											
			5	45			5.3	1.06											
			5	45			5.1	1.02							0	0	62	0.093	50
			5	55			5.6	1.12											
			5	55			5.8	1.16											
			5	55			5.3	1.06							0	0	77	0.121	50
			5	55			5.6	1.12											
			5	70			7.1	1.42											
			5	70			7.4	1.48											
			5	70			7.3	1.46											
			5	70			7.1	1.42											

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICITION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS	
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)												
Drill Hole WD 3, Sheet 3																		
10.5.66	100	112	5	55			6.0	1.4	12	16	97.5	7	0	0	62	0.119	60	
			5	55			6.3	1.46			AX							
			5	55			6.2	1.44			Casing							
			5	45			5.1	1.02					0	0	52	0.082	55	
			5	45			4.9	0.98										
			5	45			4.9	0.98										
			5	20			3.1	0.62					0	0	27	0.052	65	
			5	20			3.1	0.62										
12.5.66	112	122	5	25			5.6	1.12	10	16	109.6	7	0	0	32	0.111	110	
			5	25			5.6	1.12			AX							
			5	25			5.0	1.0			Casing							
			5	50			6.7	1.34					0	0	57	0.128	70	
			5	50			6.3	1.26										
			5	50			6.2	1.24										
			5	65			7.2	1.60					0	0	72	0.146	65	
			5	65			7.2	1.60										
			5	65			6.5	1.30										
			5	65			6.7	1.34										
			5	80			7.7	1.54					0	0	87	0.153	55	
			5	80			7.6	1.52										
			5	80			7.7	1.54										
			5	80			7.5	1.50										
			5	65			6.2	1.24					0	0	72	0.126	55	
			5	65			6.5	1.30										
			5	65			6.3	1.26										
			5	65			6.1	1.22										
			5	50			5.1	1.02					0	0	57	0.101	65	
			5	50			5.1	1.02										
			5	50			5.0	1.00										
			5	25			3.4	0.68					0	0	32	0.067	65	
			5	25			3.4	0.68										
			5	25			3.2	0.64										
17.5.66	122	142	5	30			14.0	2.80	20	16	121.5	7	0	0	37	0.121	100	
			5	30			11.7	2.34			AX							
			5	30			11.9	2.38			Casing							
			5	30			10.8	2.16										
			5	65			17.5	3.50					0	0	72	0.153	65	
			5	65			15.0	3.00										
			5	65			14.2	2.84										
			5	65			14.4	2.88										
			5	90			16.8	3.36					0	0	97	0.169	55	
			5	90			18.4	3.68										
			5	90			15.3	3.06										
			5	90			17.2	3.44										
			5	110			20.4	4.88					0	0	117	0.235	65	
			5	110			2.30	4.60										
			5	110			23.7	4.74										
			5	110			23.1	4.62										
			5	90			19.5	3.90					0	0	97	0.191	65	
			5	90			19.2	3.84										
5	90			18.8	3.76													

WARANGOI HYDRO ELECTRIC

WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION SUPPLY LINE (p.s.i.)	LOSSES PACKER (p.s.i.)	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)											
Drill Hole WD 3. Sheet 4.																	
17.5.66	122	142	5	65			15.0	3.00	20	16	121.5	7	0	0	72	0.144	60
			5	65			14.1	2.82			AX						
			5	65			14.2	2.84			Casing						
			5	30			9.9	1.98					0	0	37	0.097	85
			5	30			9.9	1.98									
			5	30			9.3	1.86									
19.5.66	142	162	5	35			25	5.0	20	16	139.5	7	0	0	42	0.215	160
			5	35			21	4.2			AX						
			5	35			20	4.0			Casing						
			5	35			19	3.8									
			5	80			43	8.6					0	0	87	0.320	110
			5	80			35	7.0									
			5	80			25	5.0									
			5	80			26	5.0									
			5	105			33	6.6					0	0	112	0.290	80
			5	105			30	6.0									
			5	105			27	5.4									
			5	105			25	5.0									
			5	130			42	8.4					0	0	137	0.395	90
			5	130			41	8.2									
			5	130			37	7.4									
			5	130			37	7.4									
			5	105			22	4.4					0	0	112	0.225	60
			5	105			23	4.6									
			5	80			23	4.6					0	0	87	0.225	80
			5	80			22	4.4									
			5	35			13	1.6					0	0	42	0.080	60
			5	35			13	1.6									
21.5.66	162	183															

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION SUPPLY LINE (p.s.i.)	LOSSES PACKER (p.s.i.)	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS		
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)													
Drill Hole WD 3, Sheet 5.																			
21.5.66	162	183	5	40	753	774.8	21.5	4.3	21	16	159.5 9x Casing	7	0	0	47	0.19	130		
			5	40	774.5	794.8	20.3	4.1											
			5	40	794.8	814.8	20.0	4.0											
			5	100	530	571	41	8.2											
			5	100	573	610	37	7.4											
			5	100	612	646	34	6.8											
			5	120	675	719	44	8.8											
			5	120	723	757	34	6.8											
			5	120	761	789	28	5.6											
			5	120	793	816	23	4.6											
			5	150	900	830	30	6.0											
			5	150	935	970	35	7.0											
			5	150	925	03	28	5.6											
			5	150	8	35	37	5.4											
			5	120	50	66	16	3.2											
			5	120	70	86	16	3.2											
			5	100	100	105	5	1.0											
			5	100	108	112	4	0.8											
			5	40	834.0	845.0	11.0	2.2											
			5	40	845.0	856.7	11.7	2.3											
			5	40	856.7	868.0	11.3	2.3											
25.5.66	183	203	5	40	700	825	175	35.0	20	16	180.5 9x Casing	7	3.3	14	130	1.725	1700		
			5	40	875	55	180	36.0											
			5	40	55	230	175	35.0											
			5	40	230	390	160	32.0											
			5	100	470	745	275	55.0											
			5	100	745	35	290	58.0											
			5	100	835	320	285	57.0											
			5	100	320	585	265	53.0											
			3.09	120	700	900	200	63.6											
			1.32	120	900	0	100	64.8											
			1.38	120	100	200	100	61.2											
			1.33	120	200	300	100	64.2											
			1.27	150	400	500	100	68.4											
			1.29	150	500	600	100	67.2											
			1.27	150	600	700	100	68.4											
			1.25	150	700	800	100	70.2											
			1.40	120	300	400	100	60.0											
			1.41	120	400	500	100	59.4											
			1.43	120	500	600	100	58.2											
			1.41	120	600	700	100	59.4											
			1.46	100	800	900	100	56.4											
			1.44	100	900	0	100	57.6											
			1.43	100	00	100	100	58.2											
			1.43	100	100	200	100	58.2											
			1.25	45	300	350	50	35.4											
			1.24	45	350	400	50	36.0											
			1.23	45	400	450	50	36.6											
			1.24	45	450	500	50	36.0											

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION OF STANDING WATER (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE (ft. x in.)	WATER COLUMN PRESSURE (p.s.i.)	FRICTION LOSSES		EFFECTIVE PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)							SUPPLY LINES	PACKER			
Drill Hole WD 3. Sheet 6																	
27.5.66	190	210	5	40	700	875	175	35.0	20	17	182.5 AX Casing	71	3.8	15	28	1.765	2000
			5	40	875	1060	185	37.0									
			5	40	1060	1230	170	34.0									
			1.55	100	410	510	100	52.2					7.9	38	61	2.645	1300
			1.50	100	510	610	100	54.6									
			2.00	100	610	710	100	50.0									
			1.50	100	710	810	100	54.6									
			1.34	120	920	20	100	63.6					10.3	51	66	3.03	1400
			1.40	120	20	120	100	60.0									
			1.40	120	120	220	100	60.0									
			1.42	120	220	320	100	58.8									
			0.49	150	500	550	50	61.2					11.1	57	89	3.165	1100
			0.47	150	550	600	50	63.6									
			0.45	150	600	650	50	66.6									
			0.44	150	650	700	50	68.4									
			0.49	125	870	920	50	61.2					10.5	53	68	3.075	1400
			0.49	125	920	970	50	61.2									
			0.48	125	970	20	50	62.4									
			0.49	125	20	70	50	61.2									
			0.54	100	220	270	50	58.8					7.5	33	66	2.56	1200
			0.55	100	270	320	50	54.6									
			1.03	100	320	370	50	47.4									
			1.04	100	370	420	50	46.8									
			1.42	40	510	560	50	29.4					3.0	12	32	159	1600
			1.30	40	560	60	50	33.6									
			1.35	40	610	660	50	31.8									
			1.32	40	660	710	50	32.4									
28.5.66	201	211	1.55	40	880	930	50	25.8	17	198.5 AX Casing	71	2.0	6.3	39	2.42	1900	
			2.02	40	930	980	50	24.6									
			2.05	40	980	30	50	24.0									
			2.16	40	30	80	50	22.2									
			1.20	100	200	250	50	37.2				4.9	19	83	3.95	1500	
			1.05	100	250	300	50	46.2									
			1.12	100	300	350	50	41.4									
			1.23	100	350	400	50	36.0									
			1.22	100	400	450	50	36.6									
			1.06	120	500	550	50	45.6				6.3	26	95	4.50	1500	
			1.07	120	550	600	50	45.0									
			1.08	120	600	650	50	44.4									
			1.07	120	650	700	50	45.0									
			0.57	150	800	850	50	58.8				9.6	45	102	5.72	1700	
			0.57	150	850	900	50	57.6									
			0.54	150	900	950	50	55.8									
			0.53	150	950	00	50	56.4									
			1.07	120	100	150	50	45.0				6.4	26	95	4.56	1500	
			1.05	120	150	200	50	46.2									
			1.08	120	200	250	50	44.4									
			1.04	120	250	300	50	46.8									
			1.22	100	350	350	50	36.6				4.0	15	88	3.62	1700	
			1.24	100	400	450	50	36.0									
			1.22	100	450	500	50	36.6									
			1.25	100	500	550	50	35.4									
			2.21	40	650	700	50	21.2				1.4	4.4	42	2.11	1600	
			2.21	40	700	750	50	21.2									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION LOSSES		EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)							SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)			
Drill Hole WD 3. Sheet 7.																	
28.5.66	201	211	2.24	40	750	800	50	21.0	10	17	1985	7					
			2.24	40	800	850	50	21.0			AX						
30.5.66	210	220	5	40	900	930	30	6.0	10	17	207.5	7	0	0	47	0.48	300
			5	40	930	955	25	5.0			AX						
			5	40	955	975	20	4.0			Casing						
			5	40	975	995	20	4.0									
			3.05	100	30	80	50	16.2					0	1.1	10.6	0.48	140
			4.31	100	80	130	50	10.8									
			5.09	100	130	180	50	9.6									
			5.30	100	180	230	50	9.0									
			4.50	125	280	330	50	10.2					0	0	132	0.94	220
			5.05	125	330	380	50	9.8									
			5.40	125	380	430	50	8.8									
			5.35	125	430	480	50	8.9									
			4.25	150	140	190	50	11.3					0	1	156	1.06	210
			4.35	150	190	240	50	10.8									
			4.55	150	240	290	50	10.1									
			4.55	150	290	340	50	10.1									
			5	120	350	390	40	8.0					0	0	127	0.77	200
			5	120	390	425	35	7.0									
			5	120	425	460	35	7.0									
			5	100	470	505	35	7.0					0	0	107	0.70	200
			5	100	505	540	35	7.0									
			5	100	540	575	35	7.0									
			5	40	930	950	20	4.0					0	0	47	0.38	250
			5	40	950	969	19	3.8									
			5	40	969	990	21	4.2									
	220'6"	231	5	40	710	740	30	6.0	10.5	17							
			5	40	740	765	25	5.0					0	0	47	0.52	350
			5	40	765	795	30	6.0									
			5	40	795	820	25	5.0									
			2.59	100	850	900	50	16.8					0	2.0	105	1.38	400
			3.36	100	900	950	50	13.8									
			3.41	100	950	00	50	13.6									
			3.42	100	00	50	50	13.6									
			2.55	120	80	130	50	17.1					0	2.1	125	1.44	350
			3.26	120	130	180	50	14.5									
			3.30	120	180	230	50	14.3									
			3.30	120	230	280	50	14.3									
			2.40	150	300	350	50	18.7					1.2	3.3	153	1.74	350
			2.45	150	350	400	50	18.2									
			2.46	150	400	450	50	18.1									
			2.47	150	450	500	50	18.0									
			3.46	120	520	570	50	13.3					0	1.6	125	1.26	300
			3.47	120	570	620	50	13.2									
			3.45	120	620	670	50	13.4									
			3.45	120	670	720	50	13.4									
			4.42	100	750	800	50	10.6					0	1	106	1.01	300
			4.45	100	800	850	50	10.5									
			4.45	100	850	900	50	10.5									
			4.38	100	900	950	50	10.7									
			5	40	980	00	20	4.0					0	0	47	0.45	300
			5	40	00	25	25	5.0									
			5	40	25	50	25	5.0									

B56/A2/60-48

BUREAU OF MINERAL RESOURCES
WARANGOI - HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION LOSSES		EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)							SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)			
	Drill Hole W.D. 6.				Location Southern Ridge, midway pgs 48 and 49.								R.L. 291 ft.			Angle from Horizontal, - 90°.	
	Packer, N. Hydraulic.				Supply Line, AX Casing.								Water Supply, Coventry Climax Pump.				
	75'	85	3.28	15			50	14.4	10	NIL	75'	33	0	2.8	45	1.33	900
			3.47	15			50	13.2			AX						
			4.04	15			50	12.3			CASING						
			3.20	25			50	15.0					0	5.2	53	1.85	1100
			2.30	25			50	20.0									
			2.25	25			50	20.7									
			1.38	35			50	30.5					1	13	54	3.01	1700
			1.42	35			50	29.4									
			1.39	35			50	30.3									
			1.24	40			50	35.6					15	16	56	3.56	2000
			1.26	40			50	34.8									
			1.22	40			50	36.5									
			1.44	35			50	28.8					0	12	56	2.97	1700
			1.42	35			50	29.4									
			1.37	35			50	30.9									
			2.19	25			50	21.6					0	7.4	51	2.27	1400
			2.06	25			50	23.8									
	85	95	5	15			27.3	5.5	10	NIL	85'	37	0	0	52	0.50	300
			5	15			25.6	5.1			AX						
			5	15			24.3	4.8			CASING						
			5	15			24.3	4.8									
			5.32	25			50	9.0					0	1.4	61	0.94	500
			5.30	25			50	9.1									
			4.58	25			50	10.1									
			4.46	25			50	10.5									
			5	30			30	6.0					0	0	67	0.60	270
			5	30			29.9	6.0									
			5	30			29.4	5.9									
			5	40			34.2	6.8					0	0	77	0.68	270
			5	40			34.3	6.9									
			5	40			33.8	6.8									
			5	30			22.5	4.5					0	0	67	0.45	200
			5	30			22.5	4.5									
			5	25			20.7	4.1					0	0	62	0.42	190
			5	25			21.0	4.2									
			5	15			16.0	3.2					0	0	52	0.32	180
			5	15			16.7	3.3									

WARANGOI HYDRO ELECTRIC

WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF GAUGE TEST (min)	GAUGE PRESSURE (P.S.I.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (G.P.M.)	LENGTH OF SECTION (ft)	VERTICAL DEPTH (ft)	WATER COLUMN PRESSURE (P.S.I.)	FRICTION LOSSES		EFFECTIVE TEST PRESSURE (P.S.I.)	WATER LOSS (g.p.m. per ft)	REMARKS	
	FROM (ft)	TO (ft)			START (gallons)	FINISH (gallons)						SUPPLY LINE (ft)	PACKER (ft)				
WD 6. Sheet 2.																	
	95	105	2.10	20			50	23.1	10	NIL	95	41	0	6.2	55	2.02	1100
			2.27	20			50	20.4			AX						
			2.28	20			50	20.2			Casing						
			2.37	20			50	19.1									
			1.47	30			50	28.1				1	11	59	2.85	1500	
			1.44	30			50	28.8									
			1.45	30			50	28.6									
			1.24	40			50	35.7				2	18	61	3.66	1800	
			1.20	40			50	37.5									
			1.22	40			50	36.6									
			1.09	50			50	43.5				3	25	63	4.48	2200	
			1.05	50			50	46.2									
			1.07	50			50	44.7									
			1.25	40			50	35.4				2	18	61	3.73	1800	
			1.17	40			50	39.0									
			1.20	40			50	37.5									
			1.47	30			50	28.1				1	11	59	2.84	1500	
			1.45	30			50	28.6									
			2.56	20			50	17.0				0	4.4	57	1.70	900	
			2.58	20			50	16.9									
9.7.66	105	115	3.25	20	550	600	50	14.6	10	90	102.5	39	0	2.8	56	1.33	750
			3.43	20	600	650	50	13.4	13.3		AX						
			4.10	20	650	700	50	12.0	10		Casing						
			2.20	30	750	800	50	21.4	21.3				0	6.8	62	2.13	1100
			2.19	30	800	850	50	21.5									
			2.23	30	850	900	50	20.9									
			1.41	40	960	10	50	29.4	28.2			1.3	11	67	2.82	1300	
			1.37	40	10	60	50	25.8									
			1.42	40	60	110	50	29.4									
			1.10	55	150	200	50	42.8	44.1			3.0	24.5	67	4.41	2000	
			1.06	55	200	250	50	45.4									
			1.08	55	250	300	50	44.1									
			1.32	40	320	370	50	32.6	31.6			1.6	14	64	3.16	1600	
			1.38	40	370	420	50	30.6									
			1.35	40	420	470	50	31.6									
			2.15	30	580	630	50	22.2	22.2			0	7.3	62	2.22	1100	
			2.15	30	630	680	50	22.2									
			3.22	20	690	740	50	14.8	14.2			0	3.3	56	1.42	750	
			3.32	20	740	790	50	14.1									
			3.40	20	790	840	50	13.6									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min)	GAUGE TEST PRESSURE (psi)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft)	VERTICAL DEPTH OF STANDING WATER (ft)	LENGTH & SIZE OF SUPPLY LINE (ft. in.)	WATER COLUMN PRESSURE (psi)	FRICTION LOSSES		EFFECTIVE TEST PRESSURE (psi)	WATER LOSS (gallons)	REMARKS
	FROM (ft)	TO (ft)			START (gallons)	FINISH (gallons)							SUPPLY LINE	PACKER			
WD 6. Sheet 3.																	
11.7.66	115	125	3.06	20	810	860	50	16.1	10	NIL	112.5	50	0	3.6	66	1.51	700
			3.24	20	860	910	50	14.7	15.1		AX						
			3.25	20	910	960	50	14.6			CASING						
			3.02	30	980	30	50	16.4	15.7				0	3.8	76	1.57	600
			3.10	30	30	80	50	15.8									
			3.23	30	80	130	50	14.8									
			1.32	45	170	220	50	32.6	31.8				1.8	14	79	3.18	1200
			1.35	45	220	270	50	31.6									
			1.36	45	270	320	50	31.2									
			1.15	60	420	470	50	40.0	38.8				2.6	19	88	3.88	1300
			1.19	60	470	520	50	37.9									
			1.18	60	520	570	50	38.5									
			1.45	45	600	650	50	28.6	27.5				1.4	10.5	83	2.75	1000
			1.49	45	650	700	50	27.5									
			1.47	45	700	750	50	28.0									
			3.17	30	770	820	50	15.2	15.1				0	3.6	76	1.51	600
			3.19	30	820	870	50	15.8									
			3.28	30	870	920	50	14.4									
			5.15	20	950	00	50	9.5	9.5				0	1.5	68	0.95	350
			5.16	20	00	50	50	9.5									
12.7.66	125	135	0.41	20	200	250	50	73.1	10	NIL	122.5	54.3	9.7	65	0	7.35	7100,000
			0.42	20	250	300	50	71.4			AX						MAXIMUM OBTAINABLE
			0.40	20	300	350	50	74.9	73.5		CASING						GAUGE PRESSURE
			0.41	20	350	400	50	73.1									
			0.40	20	400	450	50	74.9									
			0.41	20	450	500	50	73.1									
			0.40	20	500	550	50	74.9									
			0.42	20	550	600	50	71.4									
			0.40	20	600	650	50	74.9									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS						
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)																	
Drill Hole No WD 8A			Co-ordinates, K+23, 134 ft. NE.						RL. 120 ft.		Angle from horizontal, -70°												
Packer, N Hydraulic			B Mechanical		Supply line, Ax Casing			Water Supply, Coventry Climax pump.						Bearing 252° Magnetic									
2.12.65	98.5	110	5	15	15.0	42.2	27.2	5.44	11.5	7	96'	3.0	0	0	18	0.43	800						
			5	15	42.2	68.3	26.1	5.22					Ax Casing										
			5	15	68.3	92.0	23.7	4.74															
			5	15	92.0	114.1	22.1	4.42															
			5	25	140.0	168.8	28.8	5.56						0	0	28	0.47	500					
			5	25	168.8	196.8	28.0	5.60						0	0	38	0.62	500					
			5	25	196.8	222.1	25.3	5.06															
			5	35	255.0	294.9	39.9	7.98															
			5	35	294.9	331.5	36.6	7.32															
			5	35	331.5	364.1	32.6	6.52															
			5	40	385.0	422.8	37.8	7.56											0	0	43	0.63	500
			5	40	422.8	458.9	36.1	7.22															
5	40	458.9	493.9	35.0	7.00																		
8.12.65	108.5	120	5	20	540.0	565.8	25.8	5.16	11.5	6	106'	2.6	0						0	23	0.40	600	
			5	20	565.8	588.7	22.9	4.58					Ax Casing										
			5	20	588.7	611.4	22.7	4.54															
			5	20	611.4	632.6	21.2	4.24															
			5	30	720.0	741.9	21.9	4.38						0	0	33	0.37	400					
			5	30	741.9	763.8	21.9	4.38															
			5	30	763.8	784.6	20.8	4.16															
			5	40	810.0	842.1	32.1	6.42						0	0	43	0.52	400					
			5	40	842.1	873.0	30.9	6.18															
			5	40	873.0	902.3	29.3	5.86															
			5	50	950.0	988.0	38.0	7.60						0	0	53	0.62	400					
			5	50	988.0	1025.1	37.1	7.42															
			5	50	1025.1	1085.0	59.9	12.78															
			5	40	130.0	156.3	26.3	5.26						0	0	43	0.45	300					
			5	40	156.3	181.7	25.4	5.08															
			5	30	195.0	215.7	20.7	4.14						0	0	33	0.34	300					
			5	30	215.7	236.8	20.6	4.12															
			5	20	245.0	259.8	14.8	2.96						0	0	23	0.25	300					
			5	20	259.8	273.9	14.1	2.82															
			5	20	273.9	288.0	14.1	2.62															
10-12-65	120	130	4.13	20	200	250	50	11.8	10	7	117'	3.0		0	2.4	21	1.18	1700					
			4.40	20	250	300	50	10.7					Ax Casing										
			4.20	20	300	350	50	11.5															
			3.35	35	400	450	50	13.9						0	3.4	35	1.37	1300					
			3.40	35	450	500	50	13.6															
			3.40	35	500	550	50	13.6															
			2.35	50	600	650	50	19.3						0	5.7	47	1.93	1300					
			2.30	50	650	700	50	20.0															
			2.40	50	700	750	50	18.7															
			2.20	60	800	850	50	21.4						0	7	50	2.19	1200					
			2.10	60	850	900	50	23.0															
			2.20	60	900	950	50	21.4															
			2.50	50	1000	1050	50	17.6						0	4.8	48	1.79	1100					
			2.45	50	1050	1100	50	18.2															
			4.10	35	150	200	50	12.0						0	2.7	27	1.19	1100					
			4.15	35	200	250	50	11.8															
			5.00	20	310.0	352.9	42.9	8.6						0	1.0	20	0.83	1100					
			5.00	20	352.9	392.9	40.0	8.0															

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICITION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)							SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)			
WD 81 Sheet 2																	
14.12.65	130	140	5	25	400	447	47	9.5	10	6	127' AX Casing	2.6	0	1	27	0.77	900
			5	25	447	482	35	6.6									
			5	25	480	515	35	7.0									
			3.10	45	550	600	50	15.8					0	3.7	44	1.54	1100
			3.20	45	600	650	50	15.0									
			3.15	45	650	700	50	15.4									
			2.12	55	750	800	50	22.7					0	7.2	50	2.21	1400
			2.15	55	800	850	50	22.2									
			2.20	55	850	900	50	21.4									
			1.55	70	950	1000	50	26.0					1.8	12	59	2.92	1600
			1.40	70	1000	050	50	30.0									
			1.35	70	050	100	50	31.6									
			2.15	55	150	200	50	22.2					0	7.3	50	2.22	1400
			2.15	55	200	250	50	22.2									
			3.05	45	300	350	50	16.2					0	3.9	44	1.58	1100
			3.15	45	350	400	50	15.4									
			5	25	450	485	35	7.0					0	0	28	0.65	700
			5	25	485	515	30	6.0									
20.12.65	139	150	5	20	420.0	444.8	24.8	4.96	11	6	136.5' AX Casing	2.6	0	0	20	0.45	700
			5	20	444.8	469.8	25.0	5.00									
			5	20	469.8	494.5	24.3	4.86									
			5.45	35	700	750	50	8.64					0	13	36	0.79	700
			6.26	35	750	800	50	7.74									
			5.07	35	800	850	50	9.72									
			5.02	50	860	910	50	9.90					0	1.5	51	0.87	550
			5.16	50	910	960	50	9.48									
			5.24	50	960	1010	50	9.21									
			4.00	60	1020	070	50	12.50					0	2.6	60	1.14	600
			3.55	60	070	120	50	12.72									
			4.00	60	120	170	50	12.50									
			6.02	50	180	230	50	8.28					0	1.1	50	0.74	500
			6.10	50	230	280	50	8.10									
			7.12	50	260	330	50	8.04									
			5.02	35	340	360	20	3.97					0	0	38	0.34	250
			5.00	35	360	380	20	4.00									
			5.52	35	380	400	20	3.41									
			5	20	510	531	21	4.20					0	0	23	0.38	550
			5	20	531	551.7	20.7	4.14									
			5	20	551.7	572.0	20.3	4.06									
12.1.66	155	165	5	25	640	685	45	9.0	10	6	152.5' AX Casing	2.6	0	0	28	0.73	800
			5	25	685	725	40	8.0					N Mechanical Packer				
			5	25	725	759	34	6.8									
			5	25	759	785	26	5.2									
			5	25	785	823	38	7.6									
			5	50	540	575	35	7.0					0	0	53	0.50	300
			5	50	575	605	30	6.0									
			5	50	605	625	20	4.0									
			5	50	625	645	20	4.0									
			5	50	645	665	20	4.0									
			5	65	680	715	35	7.0					0	0	68	0.60	250
			5	65	715	740	25	5.0									
			5	65	740	770	30	6.0									
			5	65	770	800	30	6.0									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS							
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)																		
WORA Shaft 3																								
12.1.66	135	165	5	80	830	875	45	9.0	10	6	152.5'	2.6	0	0	83	0.82	300							
			5	80	875	915	40	8.0																
			5	80	915	955	40	8.0																
			5	80	955	995	40	8.0																
			5	65	40	65	25	5.0					0	0	68	0.45	200							
			5	65	65	90	25	5.0																
			5	65	90	110	20	4.0																
			5	65	110	130	20	4.0																
			5	50	140	155	15	3.0					0	0	53	0.28	170							
			5	50	155	170	15	3.0																
			5	50	170	180	10	2.0																
			12.1.66	169	179	5	25	480					635	155	31.0	10	6	165'	2.6	2.1	9	17	2.88	5500 N Mechanical Packer
						5	25	635					775	140	28.0									
						5	25	775					915	140	28.0									
						5	25	915					1060	145	29.0									
5	25	1065				1200	140	28.0	3.8	18	31	3.86	4000											
5	50	350				535	185	37.0																
5	50	535				725	190	38.0																
5	50	725				920	195	39.0																
5	50	920				1115	195	39.0																
5	50	1115				1315	200	40.0																
5	65	400				600	200	40.0	4.6	23	40	4.26	3000											
5	65	600				810	210	42.0																
5	65	810				1030	220	44.0																
5	65	1030				1250	220	44.0																
5	65	1250				1465	215	43.0																
5	80	540				775	235	47.0	5.9	31	46	4.85	3000											
5	80	775				1030	255	51.0																
5	80	1030				1275	245	49.0																
5	80	1275				1510	235	47.0																
5	65	640				850	210	42.0	4.5	22	41	4.20	3000											
5	65	850				1060	210	42.0																
5	65	1060				1270	210	42.0																
5	65	1270				1480	210	42.0																
5	50	570				675	165	33.0	3.1	14	36	3.45	3000											
5	50	675				855	175	35.0																
5	50	850	1025	175	35.0																			
5	50	1025	1200	175	35.0																			
5	25	220	340	120	24.0	1.3	52	21	2.22	3000														
5	25	340	450	110	22.0																			
5	25	450	560	110	22.0																			
5	25	560	665	105	21.0																			
26.1.66	193	203	3.52	25	780	830	50	12.9	10	6	190'	2.6	0	15.8	12	1.18	3000 B Mechanical Packer							
			3.45	25	830	880	50	13.3																
			4.00	25	880	930	50	12.5																
			4.45	25	930	980	50	10.5																
			5.10	25	980	1030	50	9.7																
			2.45	50	60	110	50	18.2					0	28	25	1.78	2500							
			2.47	50	110	160	50	17.9																
			2.50	50	160	210	50	17.6																
			2.49	50	210	260	50	17.7																

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS																																		
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)																																													
WD 8A Sheet 4																																																			
26.1.66	193	203	2.30	70	320	370	50	20.0	10	6	190' AX Casing	2.6	1.1	31	41	1.89	1500																																		
			2.32	70	370	420	50	19.7																																											
			2.45	70	420	470	50	18.2																																											
			2.43	70	470	520	50	18.4																																											
			2.45	70	520	570	50	18.2																																											
			2.23	90	600	650	50	20.9										1.4	38	53	2.17	1300																													
			2.17	90	650	700	50	21.8																																											
			2.17	90	700	750	50	21.8																																											
			2.20	90	750	800	50	21.4																																											
			2.20	90	800	850	50	21.4																																											
			3.07	70	880	930	50	16.0															0	2.3	40	1.54	1200																								
			3.07	70	930	980	50	16.0																																											
			3.14	70	980	1030	50	15.4																																											
			3.22	70	1030	1080	50	14.8																																											
			3.23	70	1080	1120	50	14.7																																											
			4.40	50	150	200	50	10.7																				0	11.2	41	0.94	700																			
			5.05	50	200	250	50	9.8																																											
			5.19	50	250	300	50	9.4																																											
			5.55	50	300	350	50	8.4																																											
			5.47	50	350	400	50	8.6																																											
9.45	25	410	450	40	4.1	0	2.6	25	0.34	400																																									
5	25	450	465	15	3.0																																														
5	25	465	485	20	4.0																																														
5	25	485	505	20	4.0																																														
5	25	505	515	10	2.0																																														
1.2.66	203	213	5	30	616.0						627.0	11.0	2.20	10	6	200.5' AX Casing	26	0	1.0	32	0.172	180																													
			5	30	627.0						636.5	9.5	1.90																				B Mechanical Packer																		
			5	30	636.5						644.6	8.1	1.62																																						
			5	30	644.6						652.0	7.4	1.48																																						
			5	30	652.0						659.0	7.0	1.40																																						
			5	55	663.0						675.3	12.3	2.46										0	1.2	57	0.208	120																								
			5	55	675.3						686.1	10.8	2.16																																						
			5	55	686.1						696.0	9.9	1.98																																						
			5	55	696.0						705.5	9.5	1.90																																						
			5	55	705.5						714.9	9.4	1.88																																						
			5	75	720.0						733.4	13.4	2.68															0	1.6	76	0.238	100																			
			5	75	733.4						745.7	12.3	2.46																																						
			5	75	745.7						757.5	11.8	2.36																																						
			5	75	757.5						768.9	11.4	2.28																																						
			5	75	768.9						779.6	10.7	2.14																																						
			5	100	784.0	800.5	16.5	3.30	0	2.0	101	0.284	90																																						
			5	100	800.5	815.4	14.9	2.98																																											
			5	100	815.4	828.8	13.4	2.68																																											
			5	100	828.8	842.0	13.2	2.64																																											
			5	100	842.0	855.1	13.1	2.62																																											
			5	75	859.0	868.6	9.6	1.92																										0	1.2	77	0.187	80													
			5	75	868.6	877.9	9.3	1.86																																											
			5	75	877.9	887.2	9.3	1.86																																											
			5	75	887.2	896.4	9.2	1.84																																											
			5	55	900.0	907.0	7.0	1.60																															0	0	58	0.147	90								
			5	55	907.0	914.0	7.0	1.60																																											
			5	55	914.0	920.7	6.7	1.34																																											
			5	55	920.7	927.5	6.8	1.36																																											

BUREAU OF MINERAL RESOURCES
WARANGOT HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS																														
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)																																									
WD 8A Sheet 5																																															
1.2.66	203	213	5	30	930.0	934.5	4.5	0.90	10	6	200.5	26	0	0	33	0.09	90																														
			5	30	934.5	939.1	4.6	0.92																																							
			5	30	939.1	943.6	4.5	0.90																																							
			5	30	943.6	948.1	4.5	0.90																																							
4.2.66	215	225	2.57	30	760	810	50	16.9	10	4	213'	1.7	0	25	7	1.65	8000																														
			2.54	30	810	860	50	17.2																																							
			3.01	30	860	910	50	16.6																																							
			3.09	30	910	960	50	15.9																																							
			3.10	30	960	1010	50	15.8																																							
			2.00	65	80	130	50	25.0										2.1	44	21	2.43	4000																									
			2.06	65	130	180	50	23.8																																							
			2.05	65	180	230	50	24.0																																							
			2.04	65	230	280	50	24.2																																							
			2.02	65	280	330	50	24.5																																							
			1.43	90	370	420	50	29.1															2.8	58	31	2.93	3000																				
			1.45	90	420	470	50	28.7																																							
			1.42	90	470	520	50	29.4																																							
			1.42	90	520	570	50	29.4																																							
			1.41	90	570	620	50	29.7																																							
			1.24	110	750	800	50	35.7																				4.1	74	51	3.50	2000															
			1.24	110	800	850	50	35.7																																							
			1.26	110	850	900	50	34.7																																							
			1.28	110	900	950	50	34.1																																							
			1.26	110	950	1000	50	34.7																																							
			1.40	90	60	110	50	30.0																									3.0	58	31	2.97	3000										
			1.39	90	110	160	50	30.3																																							
			1.43	90	200	250	50	29.1																																							
			1.40	90	250	300	50	30.0																																							
			1.43	90	300	350	50	29.1																																							
			2.15	65	400	450	50	22.2																														2.1	42	23	2.34	3000					
			2.02	65	450	500	50	24.5																																							
			2.05	65	500	550	50	24.0																																							
			2.10	65	550	600	50	23.0																																							
			2.08	65	600	650	50	23.4																																							
			3.11	30	700	750	50	15.7																																			0	24	8	1.47	6000
			3.17	30	750	800	50	15.2																																							
			3.34	30	800	850	50	13.8																																							
			3.28	30	850	900	50	14.4																																							
3.27	30	900	950	50	14.5																																										
3.29	30	950	1000	50	14.3																																										

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)											
Drill Hole WD 9.			Co-ordinates, 0+30, 300 ft. S.W. (C.D.W. grid).						R.L., 270 ft.		Angle from Horizontal, -90°						
Packer, N & B Mechanical.			Supply Line, AX Casing						Water Supply, Coventry Climax Pump.								
4.5.66	70	80	3.16	15	985	35	50	15.3	10	NIL	67'	30.4	0	2.2	43	1.51	1100
			3.19	15	35	85	50	15.1			AX						
			3.20	15	85	135	50	15.0			Casing						
			2.43	25	160	210	50	18.4					0	3.4	52	1.86	1100
			2.35	25	210	260	50	19.3									
			2.44	25	260	310	50	18.2									
			2.42	25	310	360	50	18.5									
			2.25	30	400	450	50	20.6					0	4.2	56	2.04	1100
			2.28	30	450	500	50	20.2									
			2.25	30	500	550	50	20.6									
			2.04	40	575	625	50	24.2					0	6	64	2.45	1200
			2.00	40	625	675	50	25.0									
			2.02	40	675	725	50	24.5									
			2.21	30	740	790	50	21.2					0	4.6	55	2.10	1200
			2.22	30	790	840	50	21.1									
			2.24	30	840	890	50	20.8									
			2.30	25	910	960	50	20.0					0	3.8	52	1.95	1200
			2.35	25	960	10	50	19.3									
			2.35	25	10	60	50	19.3									
			2.57	15	80	130	50	16.9					0	2.8	43	1.69	1200
			2.57	15	130	180	50	16.9									
			2.58	15	180	230	50	16.8									
6.5.66	84	94'6"	3.36	20			50	13.9	10.5	NIL	81.5	36.4	0	1.7	55	1.30	700
			3.39	20			50	13.7			AX						
			3.39	20			50	13.7			Casing						
			2.28	30			50	20.2					0	4.2	62	1.94	950
			2.30	30			50	20.0									
			2.27	30			50	20.4									
			2.12	40			50	22.8					0	5.8	71	2.21	950
			2.07	40			50	23.8									
			2.11	40			50	22.9									
			2.10	40			50	23.1									
			1.46	50			50	28.3					1.1	9	76	2.69	1100
			1.46	50			50	28.3									
			1.47	50			50	28.1									
			2.33	40			50	19.6					0	3.5	73	1.78	750
			2.40	40			50	18.8									
			2.45	40			50	18.2									
			2.44	40			50	18.3									
			3.41	30			50	13.6					0	1.5	65	1.23	600
			3.55	30			50	12.7									
			3.53	30			50	12.9									
			3.57	30			50	12.6									
			4.39	20			50	10.7					0	1	45	0.97	650
			5.01	20			50	9.9									
			4.56	20			50	10.2									
			4.58	20			50	10.1									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION FROM TO	TEST PRESSURE	WATER HEADINGS	WATER LOSS	LEAKAGE RATE	LENGTH OF SECTION	VERTICAL DEPTH	WATER PRESSURE	WATER LOSS	PERMEABILITY	EFFECTIVE TEST PRESSURE	WATER LOSS	PERMEABILITY	
			START FINISH	LOSS	RATE									
Drill Hole WD 9. Sheet 2.														
9.5.66	94	104	5 20	9.0	1.8	10	NIL	91	40.8	0	0	61	0.18	90
			5 20	9.5	1.9			AX						
			5 20	8.5	1.7			Casing						
			5 30	17.0	3.4					0	0	71	0.33	150
			5 30	16.5	3.3									
			5 30	16.5	3.3					0	0	81	0.56	200
			5 40	28.0	5.6									
			5 40	29.0	5.8									
			5 40	27.5	5.5									
			4.47 55	50	10.5					0	1	95	1.09	350
			4.30 50	50	11.1									
			4.39 55	50	10.7									
			4.31 55	50	11.1									
			5 40	35.0	7.0					0	0	81	0.70	250
			5 40	34.0	6.8									
			5 40	35.5	7.1					0	0	71	0.64	250
			5 30	32.0	6.4									
			5 30	32.0	6.4					0	0	61	0.57	300
			5 30	32.0	6.4									
			5 20	28.5	5.7									
			5 20	29.5	5.9									
			5 20	28.0	5.6									
11.5.66	104'6"	115	5 20	50	10.0	10.5	NIL	102	45.4	0	1	64	1.02	500
			5 20	55	11.0			AX						
			5 20	55	11.0			Casing						
			3.56 45	50	12.7					0	1.4	89	1.18	400
			4.07 45	50	12.2									
			3.58 45	50	12.6									
			4.10 45	50	12.0									
			3.46 55	50	13.3					0	1.7	99	1.27	400
			3.41 55	50	13.5									
			3.47 55	50	13.2									
			3.42 55	50	13.5									
			2.42 70	50	18.5					0	3.7	112	1.75	500
			2.45 70	50	18.2									
			2.42 70	50	18.5									
			3.16 55	50	15.3					0	2.3	98	1.46	450
			3.17 55	50	15.2									
			3.16 55	50	18									
			3.47 45	50	13.2					0	1.7	99	1.27	400
			3.45 45	50	13.3									
			3.46 45	50	13.3									
			4.47 20	50	10.5					0	1	64	0.97	500
			4.50 20	50	10.3									
			4.55 20	50	10.1									
			5.05 20	50	9.9									
16.5.66	114	124'6"	3.45 20	50	13.3	10.5	NIL	111.5	49.5	0	1.3	68	1.13	500
			4.20 20	50	11.5			AX						
			4.18 20	50	11.6			Casing						
			4.22 20	50	11.4									
			4.00 35	50	12.5					0	1.5	83	1.23	450
			3.35 35	50	13.9									
			4.02 35	50	12.4									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (P.S.I.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH OF SUPPLY LINE (ft.)	WATER COLUMN PRESSURE (P.S.I.)	PERCENTAGE LOSS	PERCENTAGE GAIN	PERCENTAGE TOTAL	REMARKS	
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)											
Drill Hole WD 9. Sheet 3.																	
16.5.66	114	124'6"	3.37	50			49	13.5	10.5	NIL	111.5	49.5	0	1.8	98	1.31	400
			3.30	50			49	14.0			AX						
			3.32	50			49	13.9			Casing						
			2.58	60			45	15.2					0	2.3	107	1.47	400
			2.55	60			45	15.4									
			2.53	60			45	15.6									
			3.07	50			45	14.4					0	1.8	98	1.34	400
			3.17	50			45	13.8									
			3.12	50			45	14.1									
			3.54	35			48	12.3					0	1.4	83	1.17	450
			3.56	35			48	12.2									
			3.54	35			48	12.3									
			4.53	20			50	10.2					0	1	69	0.98	450
			4.44	20			50	10.6									
			4.55	20			50	10.2									
			4.50	20			50	10.3									
	124'6"	135	5	25			20	4.0	10.5	NIL	122	54	0	0	79	0.362	140
			5	25			18	3.6			AX						
			5	25			17	3.4			Casing						
			5	25			20	4.0									
			7.54	40			50	6.3					0	0	94	0.580	190
			8.08	40			50	6.1									
			8.09	40			50	6.1									
			5	55			34	6.8					0	0	109	0.675	190
			5	55			36	7.2									
			5	55			36	2.2									
			5	65			41	8.2					0	0	119	0.780	200
			5	65			41	8.2									
			5	65			41	8.2									
			5	55			38	7.6					0	0	108	0.675	190
			5	55			34	6.8									
			5	55			35	7.0									
			5	55			35	7.0									
			5	40			26	5.6					0	0	94	0.552	180
			5	40			29	5.8									
			5	40			27	5.4									
			5	25			21	4.2					0	0	79	0.381	150
			5	25			20.5	4.1									
			5	25			19.0	3.8									
			5	25			19.5	3.9									
19.5.66	135	144'6"	5	20			0.5	0.10	9.5	NIL	132.5	58.2	0	0	78	0.018	7
			5	20			1.0	0.20			AX						
			5	20			0.5	0.10			Casing						
			5	45			1.0	0.20					0	0	103	0.017	5
			5	45			0.8	0.16									
			5	45			0.7	0.14									
			5	45			0.7	0.14									
			5	55			1.2	0.24					0	0	113	0.025	6
			5	55			1.3	0.26									
			5	55			1.2	0.24									
			5	70			2.3	0.46					0	0	128	0.046	12
			5	70			2.2	0.44									
			5	70			2.2	0.44									

WARANGOI HYDRO ELECTRIC

WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)							SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)			
Drill Hole WD 9. Sheet 4.																	
19.5.66	135	144'6"	5	55			1.8	0.36	9.5		1325 AX Casing	58.2	0	0	113	0.038	11
			5	55			1.9	0.38									
			5	55			1.8	0.36									
			5	45			1.5	0.30		0			0	103	0.032	10	
			5	45			1.5	0.30									
			5	45			1.5	0.30									
			5	20			1.0	0.20		0			0	78	0.019	4	
			5	20			0.8	0.16									
			5	20			0.9	0.18									
21.5.66	144'6"	155'															

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION LOSSES		EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS			
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)							SUPPLY LINES	PACKER (p.s.i.)						
Drill Hole WD 9. Sheet 5.																				
21.5.66	144' 6"	155	5	25	614.5	615.7	1.2	0.24	10.5	142	142.5	61.6	0	0	87	0.021	7			
			5	25	615.7	616.8	1.1	0.22							AX Casing					
			5	25	616.8	617.8	1.0	0.20												
			5	45	620.0	622.1	2.1	0.42								0	0	10.7	0.031	9
			5	45	622.1	623.7	1.6	0.32												
			5	45	623.7	625.0	1.3	0.26												
			5	55	627.0	628.8	1.8	0.36								0	0	11.7	0.036	9
			5	55	628.8	630.8	2.0	0.40												
			5	55	630.8	632.8	2.0	0.40												
			5	75	637.0	641.8	4.8	0.96								0	0	13.7	0.092	20
			5	75	641.8	646.6	4.8	0.96												
			5	75	646.6	651.5	4.9	0.98												
			5	55	654.0	657.4	3.4	0.68								0	0	11.7	0.062	17
			5	55	657.4	660.7	3.3	0.66												
			5	55	660.7	663.8	3.1	0.62												
			5	45	665.0	667.7	2.7	0.54								0	0	10.7	0.050	15
			5	45	667.7	670.3	2.6	0.52												
			5	45	670.3	673.0	2.7	0.54												
			5	25	674.0	675.8	1.8	0.36								0	0	8.7	0.034	12
			5	25	675.8	677.6	1.8	0.36												
			5	25	677.6	679.4	1.8	0.36												
27.5.66	155	175' 6"	5	30	11.0	14.5	3.5	0.70	20.5	146	153'	63.3	0	0		93	0.045	15		
			5	30	14.5	17.8	3.3	0.66							AX Casing					
			5	30	17.8	23.6	5.8	1.16												
			5	30	23.6	28.6	5.0	1.00												
			5	30	28.6	34.0	5.0	1.08												
			5	55	43.0	58.5	15.5	3.10								0	0	11.8	0.138	35
			5	55	58.5	72.5	14.0	2.80												
			5	55	72.5	85.5	13.0	2.60												
			5	75	03.0	18.5	15.5	3.10								0	0	13.8	0.142	30
			5	75	18.5	32.7	14.2	2.84												
			5	75	32.7	46.7	14.0	2.80												
			5	100	57.0	81.0	24.0	4.80								0	0	16.3	0.213	40
			5	100	81.0	02.7	21.7	4.34												
			5	100	02.7	24.2	21.5	4.30												
			5	100	24.2	44.2	20.0	4.00												
			5	75	54.0	69.2	15.2	3.04								0	0	13.8	0.146	30
			5	75	62.2	84.2	15.0	3.00												
			5	75	84.2	99.2	15.0	3.00												
			5	55	19.0	37.5	8.5	1.70								0	0	11.8	0.083	20
			5	55	27.5	35.7	8.2	1.64												
			5	55	35.7	44.6	8.9	1.78												
			5	30	50.0	57.1	7.1	1.42								0	0	9.8	0.070	25
			5	30	57.1	64.5	7.4	1.48												
			5	30	64.5	71.5	7.0	1.40												
31.5.66	175' 6"	196	5	30	81.0	86.5	5.5	1.10	20.5	165	173'	71.6	0	0		102	0.052	16		
			5	30	86.5	91.5	5.0	1.00							AX Casing					
			5	30	91.5	96.5	5.0	1.00												
			5	65	19.0	38.6	19.6	3.92								0	0	13.7	0.181	40
			5	65	38.6	56.2	17.6	3.52												
			5	65	56.2	73.4	17.2	3.44												
			5	65	73.4	90.0	16.6	3.32												

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION LOSSES		EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)							SUPPLY LINE (p.s.)	PACKER (p.s.)			
Drill Hole WD 9. Sheet 6.																	
31.5.66	175' 6"	196	5	90	700	749	49	9.8	20.5	165	173 AX Casing	71.6	0	0	162	0.443	85
			5	90	749	794	45	9.0									
			5	90	794	838	44	8.8									
			5	90	838	881	43	8.6									
			4.47	115	940	990	50	10.4					0	1	187	0.517	85
			4.36	115	990	40	50	10.9									
			4.46	115	40	90	50	10.4									
			5	90	105	152	47	9.4					0	0	162	0.429	85
			5	90	152	195	43	8.6									
			5	90	195	237	42	8.4									
			5	65	250	283	33	6.6					0	0	137	0.317	70
			5	65	283	315	32	6.4									
			5	65	315	348	33	6.6									
			5	30	355	379	24	4.8					0	0	102	0.229	70
			5	30	379	402	23	4.6									
			5	30	402	425	23	4.6									
2.6.66	196' 6"	210	5	35	03.0	15.6	12.6	2.52	13.5	160	194 AX Casing	69.4	0	0	104	0.184	60
			5	35	15.6	27.9	12.3	2.46									
			5	35	27.9	40.4	12.5	2.50									
			2.52	80	560	610	50	17.4					1.1	3.3	145	1.34	300
			2.45	80	610	660	50	18.2									
			2.45	80	660	710	50	18.2									
			2.43	80	710	760	50	18.4									
			2.17	105	820	870	50	21.8					1.5	4.9	168	1.61	300
			2.19	105	870	920	50	21.5									
			2.15	105	920	970	50	22.2									
			1.49	130	00	50	50	27.5					2.4	8.4	189	2.02	350
			1.52	130	50	100	50	26.8									
			1.47	130	100	150	50	28.0									
			2.13	105	170	220	50	22.5					1.7	5.7	167	1.71	300
			2.07	105	220	270	50	23.6									
			2.09	105	270	320	50	23.2									
			2.31	80	350	400	50	19.9					1.4	4.7	144	1.48	300
			2.27	80	400	450	50	20.4									
			2.20	80	450	500	50	20.0									
			3.51	35	585	635	50	13.0					0	1.5	103	0.948	300
			3.54	35	635	685	50	12.8									
			3.58	35	685	735	50	12.6									
3.6.66	210	220' 6"	2.04	40	910	960	50	24.2	10.5	160	207.5 AX Casing	69.4	1.9	6	102	2.26	650
			2.08	40	960	10	50	23.4									
			2.06	40	10	60	50	23.8									
			1.03	90	140	210	50	47.6					7.6	32.8	120	4.73	1200
			0.59	90	210	260	50	50.8									
			0.59	90	260	310	50	50.8									
			0.53	110	360	410	50	56.6					10.4	44	125	5.41	1300
			0.52	110	410	460	50	57.7									
			0.53	110	460	510	50	56.6									
			0.46	140	510	560	50	65.2					13.3	63	133	6.30	1500
			0.45	140	560	610	50	66.7									
			0.45	140	610	660	50	66.7									
			0.50	110	800	850	50	60.0					11.2	50	118	5.71	1500
			0.51	110	850	900	50	58.8									
			0.49	110	900	950	50	61.2									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST	GAUGE PRESSURE	WATER METER READINGS		WATER LOSS	LEAKAGE RATE	LENGTH OF SECTION	VERTICAL DEPTH	LENGTH OF SUPPLY LINE	WATER COLUMN PRESSURE	FRICTION SUPPLY LINE	LOSSES PACKER	EFFECTIVE TEST PRESSURE	WATER LOSS PER DAY	REMARKS
	FROM	TO			START	FINISH											
Drill Hole WD 9. Sheet 7.																	
3.6.66	210	220'6"	0.56	90	10	60	50	53.5	10.5	160	207.5	69.4	8.7	37	114	5.0	1300
			0.58	90	60	110	50	51.7									
			0.57	90	110	160	50	52.6									
			1.17	40	310	360	50	38.9									
			1.20	40	360	410	50	38.5									
			1.18	40	410	460	50	37.4									
7.6.66	220'6"	233'	1.10	40	610	660	50	42.8	12.5	158	218	68.5	6.1	22	80	3.39	1300
			1.12	40	660	710	50	41.6									
			1.10	40	710	760	50	42.8									
			0.50	100	800	850	50	60.0									
			0.51	100	850	900	50	58.8									
			0.49	100	900	950	50	61.2									
			0.45	120	990	40	50	66.7									
			0.45	120	40	90	50	66.7									
			0.44	120	90	140	50	68.2									
			0.38	150	190	240	50	78.9									
			0.39	150	240	290	50	76.9									
			0.38	150	290	340	50	78.9									
			0.41	120	400	450	50	73.1									
			0.44	120	450	500	50	68.2									
			0.44	120	500	550	50	68.2									
			0.46	100	610	660	50	65.2									
			0.45	100	660	710	50	66.7									
			0.46	100	710	760	50	65.2									
0.57	40	830	880	50	52.6												
0.57	40	880	930	50	52.6												
0.50	40	930	980	50	51.7												
9.6.66	243	253	1.18	40	770	820	50	33.4	10	160	240.5	69.4	5.5	18	86	3.81	1400
			1.16	40	820	870	50	39.4									
			1.18	40	870	920	50	37.4									
			0.56	100	975	25	50	53.5									
			0.55	100	25	75	50	54.5									
			0.56	100	75	125	50	53.5									
			0.52	120	175	225	50	57.7									
			0.52	120	225	275	50	57.7									
			0.53	120	275	325	50	56.6									
			0.48	150	370	420	50	62.4									
			0.46	150	420	470	50	65.2									
			0.47	150	470	520	50	63.8									
			0.58	120	550	600	50	51.7									
			0.52	120	600	650	50	52.7									
			0.53	120	650	700	50	56.6									
			0.58	100	790	840	50	51.7									
			1.00	100	840	890	50	50.0									
			0.59	100	890	940	50	50.8									
1.21	40	990	40	50	37.0												
1.21	40	40	90	50	37.0												
1.22	40	90	140	50	36.5												

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)											
Drill Hole WD9 Sheet 8																	
10.6.66	253	268	1.55	40	240	290	50	26.0	10	160	250.5	69.4	2.9	7.6	99	2.63	900
			1.53	40	290	340	50	26.5			AX						
			1.53	40	340	390	50	26.5			Casing						
			1.05	100	430	480	50	46.1					8.3	28	133	46.7	1100
			1.05	100	480	520	50	46.1									
			1.04	100	530	580	50	46.9									
			0.58	120	600	650	50	51.7					9.8	35	145	5.08	1100
			1.00	120	650	700	50	50.0									
			0.59	120	700	750	50	50.8									
			0.55	150	775	925	50	54.5					11.5	41	167	5.52	1000
			0.53	150	825	875	50	56.6									
			0.55	150	875	925	50	54.6									
			1.02	120	960	10	50	48.4					9.0	32	148	4.86	1000
			1.01	120	10	60	50	49.1									
			1.02	120	60	110	50	48.4									
			1.10	100	140	190	50	42.8					7.0	23	139	4.26	900
			1.10	100	190	240	50	42.8									
			1.11	100	240	290	50	42.2									
			1.57	40	320	320	50	25.6					2.6	7.2	100	2.56	750
			1.56	40	320	420	50	25.9									
			1.58	40	420	470	50	25.4									
14.6.66	263	273	0.57	40	645	695	50	52.6	10	160	260.5	69.4	10.4	34	65	5.20	2500
			0.58	40	695	745	50	51.7			AX						
			0.58	40	745	795	50	51.7			Casing						
			0.44	100	850	900	50	68.2					17.2	66	86	6.77	2500
			0.45	100	900	950	50	66.6									
			0.44	100	950	00	50	68.2									
			0.42	120	65	115	50	71.4					20.4	80	89	7.31	2500
			0.40	120	115	165	50	74.9									
			0.41	120	165	215	50	73.1									
			0.38	150	260	310	50	78.9					24.3	100	95	8.07	2600
			0.37	150	310	360	50	81.6									
			0.37	150	360	410	50	81.6									
			0.43	120	445	495	50	69.7					18.8	71	100	7.03	2700
			0.43	120	495	545	50	69.7									
			0.42	120	545	595	50	71.4									
			0.47	100	690	730	50	63.7					15.4	56	98	6.33	2000
			0.47	100	730	780	50	63.7									
			0.48	100	780	830	50	62.5									
			1.06	40	875	925	50	45.4					8.1	26	75	4.48	1800
			1.04	40	925	975	50	46.9									
			1.05	40	975	25	50	46.1									
15.6.66	273	283							10	158	270.5						
											AX						
											Casing						

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS	
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)												
Drill Hole W09 Sheet 9.																		
15.6.66	273	283	5	40	145.0	157.0	12	2.4	10	158	270.5	68.5	0	0	109	0.225	65	
			5	40	157.0	168.2	11.2	2.24										
			5	40	168.2	179.3	11.1	2.22										AX Casing
			5	40	179.3	189.9	10.6	2.12										
			5	100	200.0	219.9	19.9	3.98										
			5	100	219.9	237.7	17.8	3.56										
			5	100	237.7	254.8	17.1	3.42										
			5	100	254.8	271.9	17.1	3.42										
			5	120	281.5	305.6	24.1	4.82										
			5	120	305.6	328.9	23.3	4.66										
			5	120	328.9	351.4	22.5	4.50										
			5	120	351.4	373.0	21.6	4.32										
			5	150	245	283	38	7.6										
			5	150	283	315	32	6.4										
			5	150	315	352	37	7.4										
			5	150	352	386	34	6.8										
			5	120	441.0	468.5	27.5	5.5										
			5	120	468.5	494.9	26.4	5.28										
			5	120	494.9	521.2	26.3	5.26										
			5	100	527.5	551.4	23.9	4.78										
5	100	551.4	575.0	23.6	4.72													
5	100	575.0	597.9	22.9	4.58													
5	40	602.0	618.4	16.4	3.28													
5	40	618.4	634.1	15.7	3.14													
5	40	634.1	649.8	15.7	3.14													
21.6.66	296	308	1.43	40	490	540	50	29.1	12	156	293.5	67.7	3.8	56	48	2.38	1500 B Mechanical Packer	
			1.45	40	540	590	50	28.5										
			1.46	40	590	640	50	28.3										
			1.02	100	675	725	50	48.4										
			1.01	100	725	775	50	49.1										
			1.02	100	775	825	50	48.4										
			0.57	120	880	930	50	52.6										
			0.58	120	930	980	50	54.5										
			0.55	120	980	30	50	54.5										
			0.50	150	30	130	50	60.0										
			0.50	150	130	180	50	60.0										
			0.50	150	180	230	50	60.0										
			0.6	120	275	325	50	53.5										
			0.54	120	325	375	50	55.5										
			0.54	120	375	425	50	55.5										
			1.00	100	420	520	50	50.0										
			0.58	100	520	570	50	51.7										
			1.00	100	570	620	50	50.0										
			1.20	40	650	700	50	38.5										
			1.19	40	700	750	50	37.9										
1.21	40	750	800	50	37.0													

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION SUPPLY LINE (p.s.i.)	LOSSES PACKER (p.s.i.)	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)											
Drill Hole WD 9. Sheet 10																	
22.6.66	308	320	3.42	40	920	970	50	13.5	12	156	305.5	67.7	1.3	25	81	1.34	500
			4.07	40	970	20	50	12.1			AX						B Mechanical Packer
			4.20	40	20	70	50	11.5			Changing						
			4.25	40	70	120	50	11.3									
			2.08	100	200	250	50	23.4					2.7	42	123	1.95	500
			2.10	100	250	300	50	23.0									
			2.06	100	300	350	50	23.8									
			1.56	120	400	460	50	25.9					4.7	49	134	2.17	500
			1.55	120	450	500	50	26.0									
			1.55	120	500	550	50	26.0									
			1.28	150	600	650	50	34.1					5.9	74	128	2.87	650
			1.29	150	650	700	50	34.1									
			1.25	150	700	780	50	35.3									
			1.30	120	800	850	50	33.3					6.4	70	112	2.76	750
			1.31	120	850	900	50	32.9									
			1.30	120	900	950	50	33.3									
			2.07	100	10	60	50	23.6					2.4	38	127	1.83	500
			2.20	100	60	110	50	21.4									
			2.18	100	110	160	50	21.7									
			2.21	100	160	210	50	21.2									
			3.31	40	250	300	50	14.2					0	17	91	1.06	350
			3.45	40	300	350	50	13.3									
			4.09	40	750	400	50	12.0									
			4.04	40	400	450	50	12.2									
			4.10	40	450	500	50	12.0									
	320	330	1.37	40			50	30.9	10	158	317.5	68.6	4.8	62	42	3.08	2300
			1.37	40			50	30.9			AX						B Mechanical Packer
			1.38	40			50	30.6			Changing						
			1.13	100			50	41.1					8.2	96	64	4.13	2000

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)											
Drill Hole WD 9. Sheet 11																	
	330	340	1.14	40			50	40.5	10	160	327.5	69.5	8.2	95	6	4.09	22,000
			1.13	40			50	41.1			AX						B Mechanical Packer
			1.13	40			50	41.1			Casing						
			0.51	100			50	58.8					16.5	160	-7	5.88	
			0.52	100			50	57.7									
			0.50	100			50	60.0									
			0.47	120			50	63.8					18.7	175	-4	6.29	
			0.49	120			50	61.2									
			0.47	120			50	63.8									
			0.44	150			50	68.2					22.2	195	2	6.87	7 100,000
			0.43	150			50	69.7									
			0.44	150			50	68.2									
			0.50	120			50	60.0					17.5	170	2	6.08	100,000
			0.48	120			50	62.5									
			0.50	120			50	60.0									
			0.53	100			50	56.6					15.2	150	4	5.66	45,000
			0.53	100			50	56.6									
			0.53	100			50	56.6									
			1.08	40			50	44.2					9.5	105	-5	4.40	
			1.08	40			50	44.2									
			1.09	40			50	43.5									
6.7.66	350	360	1.12	40			50	41.7	10	154	347.5	66.9	10.7	105	9	4.42	
			1.06	40			50	45.5			AX						
			1.10	40			50	42.8			Casing						
			1.00	100			50	50.0					13.9	150	23	5.18	7000
			0.56	100			50	53.6									
			0.58	100			50	51.7									
			0.58	120			50	51.7					15.6	145	26	5.46	7000
			0.54	120			50	55.6									
			0.53	120			50	56.6									
			0.51	150			50	58.8					17.7	160	39	5.80	4500
			0.48	150			50	62.5									
			0.57	150			50	52.6									
			0.51	120			50	58.8					17.0	155	15	5.70	12,000
			0.52	120			50	57.7									
			0.55	120			50	54.6									
			0.56	100			50	53.6					14.2	135	18	5.21	9,000
			0.58	100			50	51.7									
			0.59	100			50	50.9									
			1.14	40			50	40.5					90	95	3	4.07	40,000
			1.14	40			50	40.5									
			1.13	40			50	41.1									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION SUPPLY LINE (p.s.i.)	LOSSES PACKER (p.s.i.)	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)											
Drill Hole WD 9, Steel 12.																	
9.5.66	94	104	5	60			54	10.8	10	NIL	91	41	0	1	100	1.08	350
			5	60			59	11.8			AX		0	1	100	1.18	350
			5	60			58	11.6			Casing		0	1	100	1.16	350
			5	60			59	11.8					0	1	100	1.18	350
			5	60			62	12.4					0	1	100	1.24	400
			5	60			62	12.4					0	1	100	1.24	400
			5	60			65	13.0					0	1	100	1.30	400
			5	60			66	13.2					0	2	99	1.32	400
			5	60			67	13.4					0	2	99	1.34	400
			5	60			68	13.6					0	2	99	1.36	450
			5	60			66	13.2					0	2	99	1.32	400
			5	60			66	13.2					0	2	99	1.32	400
5	60			66	13.2					0	2	99	1.32	N Mechanical Packer			

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION SUPPLY LINE (p.s.i.)	LOSSES PACKER (p.s.i.)	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (ft.)	TO (ft.)			START (gallons)	FINISH (gallons)											
Drill Hole, WD 10. Location, Traverse T4, Peg 15 R.L. $\pm$ 300 ft. Angle from Horizontal, -55'. Packer, N Mechanical. Supply Line, AX Casing Water Supply, Coventry Climax Pump Direction, 295° Mag.																	
30.6.66	110	120	5	100			9.5	1.90	10	75	107.5	32.6	0	0	133	0.199	50
			5	100			10.0	2.00	1.99		AX						
			5	100			10.1	2.02			Casing						
			5	100			10.1	2.02									
			5	130			18.1	3.62	3.59				0	0	163	0.359	50
			5	130			17.2	3.44									
			5	130			17.0	3.40									
			5	130			19.5	3.90									
			5	150			26.0	5.20	5.16				0	0	183	0.516	90
			5	150			25.3	5.06									
			5	150			25.7	5.14									
			5	150			26.1	5.22									
			5	130			21.3	4.26	4.10				0	0	163	0.410	80
			5	130			20.5	4.10									
			5	130			20.0	4.00									
			5	130			20.1	4.02									
			5	100			15.2	3.04	2.91				0	0	130	0.291	70
			5	100			14.5	2.90									
			5	100			14.4	2.88									
5	100			14.0	2.80												
6.7.66	120	130	5	25			62	12.4	10	78	117.5	33.8	0	1.5	57	1.29	700
			5	25			63	12.6	12.9		AX						
			5	25			66	13.2			Casing						
			5	25			67	13.4									
			5	50			115	23.0	22.0				0	5	79	2.20	850
			5	50			110	22.0									
			5	50			105	21.0									
			1:39	65			50	30.3	32.5				20	12.5	84	3.25	1200
			1:29	65			50	33.7									
			1:29	65			50	33.7									
			1:33	65			50	32.3									
			1:10	80			50	42.8	43.1				3.3	24	87	4.31	1500
			1:10	80			50	42.8									
			1:10	80			50	42.8									
			1:08	80			50	44.1									
			1:24	65			50	35.7	37.8				2.6	17.5	79	3.78	1500
			1:15	65			50	40.0									
			1:20	65			50	37.5									
			1:19	65			50	38.0									
			1:43	50			50	29.1	30.1				1.7	10.5	72	3.01	1300
			1:43	50			50	29.1									
			1:37	50			50	30.9									
			1:36	50			50	31.2									
			2:10	25			50	23.0	22.6				0	5.3	54	2.26	1300
			2:04	25			50	24.2									
			2:10	25			50	23.0									
			2:30	25			50	20.0									

WARANGOI HYDRO ELECTRIC

WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH OF STANDING WATER (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION LOSSES		EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS
	FROM (#)	TO (#)			START (gallons)	FINISH (gallons)							SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)			
Drill Hole WD 10, Sheet 2.																	
8-7-66	130	140	5	20	670	700	30	6.0	10	NIL	127.5	45.1	0	0	65	0.55	250
			5	20	700	730	30	6.0			AX						
			5	20	730	755	25	5.0			Casing						
			5	20	755	780	25	5.0									
			5	45	800	945	145	29.0	28.3				1.7	9.1	79	2.83	1100
			1.47	45	950	00	50	28.0									
			2.00	45	00	50	50	25.0									
			1.36	45	50	100	50	31.2									
			1.32	55	200	250	50	32.6	34.5				2.4	14	84	3.45	1300
			1.22	55	250	300	50	36.5									
			1.23	55	300	350	50	36.1									
			1.31	55	350	400	50	32.9									
			1.12	70	450	500	50	38.9	40.5				3.3	20.5	91	4.05	1400
			1.14	70	500	550	50	40.5									
			1.13	70	550	600	50	41.0									
			1.12	70	600	650	50	41.6									
			1.19	55	750	800	50	37.9	37.9				2.9	17.5	80	3.79	1500
			1.17	55	800	850	50	38.9									
			1.17	55	850	900	50	38.9									
			1.23	55	900	950	50	36.1									
			1.32	45	00	50	50	32.6	32.3				2.2	12.5	75	3.23	1300
			1.33	45	50	100	50	32.2									
			1.32	45	100	150	50	32.6									
			1.34	45	150	200	50	31.9									
			5	20	250	365	115	23.0	21.2				1.0	4.7	59	2.12	1100
			5	20	365	470	105	21.0									
			5	20	470	575	105	21.0									
			5	20	575	675	100	20.0									
12-7-66	140	150	5	20	0	0	0	0	10	NIL	137	48.6	0	0	69	0	0
			5	50	730	745	15	3	4.5		AX		0	0	99	0.45	140
			5	50	745	765	20	4			Casing						
			5	50	765	790	25	5									
			5	50	790	820	30	6									
			5	65	860	890	30	6	6.8				0	0	114	0.68	180
			5	65	890	925	35	7									
			5	65	925	960	35	7									
			5	65	960	995	35	7									
			3.52	80	00	50	50	12.9	14.2				0	1.9	127	1.42	350
			3.32	80	50	100	50	14.1									
			3.28	80	100	150	50	14.4									
			3.16	80	150	200	50	15.3									
			5	65	270	315	45	9	8.0				0	0	114	0.80	250
			5	65	315	355	40	9									
			5	65	355	390	35	7									
			5	65	390	425	35	7									
			5	50	430	450	20	4	4.0				0	0	99	0.40	120
			5	50	450	470	20	4									
			5	50	470	495	25	5									
			5	50	495	510	15	3									
			5	25	515	520	5	1	1.0				0	0	74	0.10	50
			5	25	520	525	5	1									
			5	25	525	530	5	1									

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST (min.)	GAUGE PRESSURE (p.s.i.)	WATER METER READINGS		WATER LOSS (gallons)	LEAKAGE RATE (g.p.m.)	LENGTH OF SECTION (ft.)	VERTICAL DEPTH (ft.)	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE (p.s.i.)	FRICTION	LOSSES	EFFECTIVE TEST PRESSURE (p.s.i.)	WATER LOSS (g.p.m. per ft.)	REMARKS	
	FROM (ft.)	TO (ft.)			SUPPLY LINE (p.s.i.)	PACKER (p.s.i.)												
Drill Hole WD 10 Sheet 3.																		
13.7.66	150	160	1.05	25	850	900	50	46.1	10	NIL	147	52.5	4.9	28	45	4.66	3000	
			1.04	25	900	950	50	46.9	46.6	AX								
			1.04	25	950	00	50	46.9		Casing								
			0.54	50	120	270	50	65.5	53.6				6.3	38	58	5.36	3000	
			0.56	50	270	320	50	53.5										
			0.58	50	320	370	50	51.7										
			0.56	65	400	450	50	53.5	53.9				6.5	38	73	5.39	2500	
			0.57	65	450	500	50	52.6										
			0.54	65	500	550	50	55.5										
			0.52	80	590	640	50	57.7	60.3				7.9	50	75	6.03	2500	
			0.50	80	640	690	50	60.0										
			0.49	80	690	740	50	61.2										
			0.48	80	740	790	50	62.4										
			0.49	65	840	890	50	61.2	59.7				7.6	50	60	5.97	3000	
			0.50	65	890	940	50	60.0										
			0.52	65	940	990	50	57.7										
			0.51	65	990	40	50	58.8										
			0.48	50	70	120	50	62.4	55.3				6.8	42	54	5.53	3000	
			0.58	50	120	170	50	51.7										
			0.56	50	170	220	50	53.5										
			0.56	50	220	270	50	53.5										
			1.15	25	310	360	50	40.0	39.9				3.7	19.5	54	3.99	2500	
			1.17	25	360	410	50	38.9										
			1.17	25	410	460	50	38.9										
			1.12	25	460	510	50	44.6										
15.7.66	164'8"	175'2"	5	25	373	399	26	5.2	10.5	NIL	162	57.7	0	0	83	0.50	190	
			5	25	399	426	27	5.4	5.2	AX								
			5	25	426	451	25	5.0		Casing								
			5	25	451	476	25	5.0										
			3.30	50	960	10	50	14.2	15.3				0	2.2	106	1.45	400	
			3.14	50	10	60	50	15.4										
			3.12	50	60	110	50	15.6										
			3.06	50	110	160	50	16.1										
			1.57	70	190	240	50	25.6	24.9				1.6	6.2	120	2.37	600	
			2.01	70	240	290	50	24.8										
			2.02	70	290	340	50	24.5										
			2.02	70	340	390	50	24.5										
			1.29	90	420	470	50	33.7	34.5				3.2	14	131	3.28	750	
			1.25	90	470	520	50	35.3										
			1.28	90	520	570	50	34.1										
			1.26	90	570	620	50	34.9										
			1.47	70	650	700	50	28.0	28.8				2.2	9.4	116	2.74	700	
			1.41	70	700	750	50	29.7										
			1.44	70	750	800	50	28.8										
			1.44	70	800	850	50	28.8										
			2.13	50	870	920	50	22.5	22.3				1.3	5.2	101	2.12	650	
			2.13	50	920	970	50	22.5										
			2.16	50	970	20	50	22.0										
			3.18	25	120	170	50	15.1										
			3.28	25	170	220	50	14.4					0	2	81	1.40	550	
			3.20	25	220	270	50	15.0										
			3.26	25	270	320	50	14.6										

BUREAU OF MINERAL RESOURCES
WARANGOI HYDRO ELECTRIC
WATER PRESSURE TEST RESULTS

DATE	SECTION TESTED		TIME OF TEST	GAUGE PRESSURE	WATER METER READINGS		WATER LOSS	LEAKAGE RATE	LENGTH OF SECTION	VERTICAL DEPTH OF STANDING WATER	LENGTH & SIZE OF SUPPLY LINE	WATER COLUMN PRESSURE	FRICTION LOSSES		EFFECTIVE TEST PRESSURE	WATER LOSS	REMARKS
	FROM	TO			START	FINISH							SUPPLY LINES	PACKER			
					(gallons)	(gallons)	(gallons)	(g.p.m.)	(ft.)			(p.s.i.)		(p.s.i.)		(g.p.m. per ft.)	Permeability ft./yr.
Drill Hole WD 10 Sheet 4																	
18-7-66	185	195	1.35	30	560	610	50	31.6	10	NIL	180'	65.6	2.5	9.5	84	2.90	1100
			1.44	30	610	660	50	28.8	29.0		AX						
			1.49	30	660	710	50	27.6			Casing						
			1.48	30	710	770	50	27.8									
			1.23	55	780	830	50	36.2	38.5				4.2	18	98	3.85	1200
			1.13	55	830	880	50	41.1									
			1.17	55	880	930	50	39.0									
			1.20	55	930	980	50	37.5									
			1.11	75	10	60	50	42.3	41.5				4.8	22	114	4.15	1200
			1.09	75	60	110	50	42.5									
			1.16	75	110	160	50	39.5									
			1.14	75	160	210	50	40.6									
			0.53	100	250	300	50	56.6	52.6				7.6	37	121	5.26	1300
			0.56	100	300	350	50	53.6									
			1.00	100	350	400	50	50.0									
			1.00	100	400	450	50	50.0									
			1.07	75	470	520	50	44.8	38.1				4.2	18	118	3.81	1000
			1.40	75	520	570	50	30.0									
			1.17	75	570	620	50	39.0									
			1.18	75	620	670	50	38.4									
			1.27	55	740	790	50	34.4	33.7				3.3	13.5	104	3.37	1000
			1.29	55	790	840	50	33.7									
			1.31	55	840	890	50	33.0									
			1.50	30	00	50	50	27.3	28.0				2.4	8.8	84	2.80	1100
			1.47	30	50	100	50	28.1									
			1.45	30	100	150	50	28.6									
25-7-66	193	203	0.51	30	340	380	50	59.8	10	NIL	190	68.6	8.7	4.2	48	5.57	3500
			0.55	30	390	440	50	54.6	55.7		AX						
			0.56	30	440	490	50	53.6			Casing						
			0.55	30	490	540	50	54.6									
			0.47	55	570	620	50	63.8	62.1				11.0	55	58	6.21	3000
			0.49	55	623	670	50	61.2									
			0.49	55	670	720	50	61.2									
			0.42	75	800	850	50	71.5	73.3				14.8	78	51	7.33	4500
			0.39	75	850	900	50	76.9									
			0.42	75	900	950	50	71.5									
			0.42	100	00	50	50	71.5	75.1				15.8	84	69	7.51	3500
			0.39	100	50	100	50	76.9									
			0.39	100	100	150	50	76.9									
			0.48	75	250	300	50	67.5	65.8				12.2	8.61	70	6.58	3000
			0.45	75	300	350	50	66.7									
			0.44	75	350	400	50	68.2									
			0.49	55	650	700	50	61.2	64.4				11.6	59	53	6.44	3500
			0.45	55	700	750	50	66.7									
			0.46	55	750	800	50	65.2									
			0.54	30	900	950	50	55.6	57.1				9.3	45	44	5.71	400
			0.50	30	950	00	50	60.0									
			0.54	30	00	50	50	55.6									

152°00'E

152°15'E

152°30'E


LOWER

WARANGOI

HYDRO-ELECTRIC

SCHEME

PLATE 1



LOCALITY

PLAN

N



Geological Office

Port Moresby

To Accompany Record 1968/59




B56/A2/56

LOWER WARANGOI HYDRO-ELECTRIC SCHEME

PLATE 2

GEOLOGICAL MAP OF DAMSITE




LOWER WARANGOI HYDRO-ELECTRIC SCHEME

PLATE 3

VERTICAL GEOLOGICAL SECTION ALONG AXIS OF PROPOSED DAM

LOOKING UPSTREAM. FOR LOCATION See plate 2.



- B**
- Soil and Scree
 - River Sand and Gravel
 - Andesite
 - Limestone and Agglomerate
 - Limestone
 - Inferred Geological Boundary, position approximate.
- Geological Office

- Agglomerate Fresh to Slightly Weathered
- Agglomerate Slightly to Moderately Weathered
- Agglomerate Moderately to Highly Weathered
- Agglomerate Highly to Completely Weathered

Diamond drill holes WD1 WD2 WD8A WDB WD4A WD3 and WD9 are projected to centre line of section

Port Moresby

To Accompany Record 1968/59.

PNGB56-2-23

B 56/A2/58.

LOWER WARANGOI HYDRO-ELECTRIC SCHEME

GEOLOGY, WITH DIAGRAMMATIC SECTION, OF SOUTHERN RIDGE

PLATE 4

VERTICAL SECTION ALONG RIDGE

